

GOVERNMENT OF INDIA

DEPARTMENT OF ARCHAEOLOGY

**CENTRAL ARCHAEOLOGICAL
LIBRARY**

Acc. No. 17026

CALL No. 913.394/P.V.AES

D.G.A. 79.

Publications of the Princeton University Archaeological
Expeditions to Syria in 1904-1905 and 1909

Division III 3

CAL
BHL

GREEK AND LATIN INSCRIPTIONS IN SYRIA

BY

WILLIAM KELLY PRENTICE

Section B
NORTHERN SYRIA

Part 6
DJEBEL SIM'AN

LATE E. J. BRILL
PUBLISHERS AND PRINTERS
LEYDEN — 1922.

GOVERNMENT OF INDIA

ARCHAEOLOGICAL SURVEY OF INDIA

CENTRAL
ARCHAEOLOGICAL
LIBRARY

ACCESSION NO 17026

CALL No. 913.394 / P.U.A.E.S.

D.G.A. 79

Publications of the Princeton University Archaeological
Expeditions to Syria in 1904-1905 and 1909

DIVISION III

GREEK AND LATIN INSCRIPTIONS IN SYRIA

SECTION B

NORTHERN SYRIA

PART 6



THE DJEBEL SIM'ÂN

BY

15042

WILLIAM KELLY PRENTICE

17926

913.394
P.U.A.E.S.

Ref 417.6
P.U.A.E.S.

LATE E. J. BRILL
PUBLISHERS AND PRINTERS
LEYDEN — 1922.

CENTRAL ARCHAEOLOGICAL
LIBRARY NEW DELHI.

Acc. No.

Date.

CENTRAL ARCHAEOLOGICAL
LIBRARY, NEW DELHI.

Acc. No. 17026
Date 14.8.58
In No. 913.399 / P. U. A. E. S.

SYRIA

PUBLICATIONS OF
THE PRINCETON UNIVERSITY ARCHAEOLOGICAL
EXPEDITIONS TO SYRIA IN 1904—5 AND 1909

Division III

GREEK AND LATIN INSCRIPTIONS

Section B

NORTHERN SYRIA

BY

WILLIAM KELLY PRENTICE

7



LATE E. J. BRILL LTD
PUBLISHERS AND PRINTERS
LEYDEN — 1922.

PARTS.

1. THE ʿALĀ AND ẸAŞR IBN WARDAN.
 2. ANDERĪN-KERRĀTĪN-MAʿRATĀ.
 3. DJEBEL RĪḤĀ AND DJEBEL IL-WAŞTĀNĪ.
 4. DJEBEL BĀRĪSHĀ.
 5. DJEBEL ḤALAḶAH.
 6. DJEBEL SIMʿĀN.
-

Preface to Division III, Section B.

The present volume, Publications of the Princeton University Archaeological Expeditions to Syria in 1904-1905 and 1909, Division III, Section B, contains 410 inscriptions, 409 in Greek, and one in Greek and Latin, found in Northern Central Syria. Nearly all of them were collected in the Spring of 1905 by the members of the Princeton Expedition of that year. A few, however, have been repeated here from the Publications of an American Archaeological Expedition to Syria in 1899-1900, because better copies were obtained, or for some other reason: a very few were not found by either expedition. The inscriptions published before 1905 from Dār Kītā, Bābiskā, Refādeh and Dēr Simān are republished here in order to give, as far as possible, a complete collection of all the Greek inscriptions in these four towns, which were made the objects of special study by the Princeton Expeditions. Most of the inscriptions were copied by the editor himself: wherever an inscription appears which was copied by any one else this fact is stated in the description of the monument. The earliest of the inscriptions which can be definitely dated belongs to the year 73-74 A.D.: the latest is of the year 609-610 A.D. It is probable that all the others fall between these dates. Twelve of them bear dates earlier than 325 A.D.: a few of the others probably belong to that earlier period, for example Nos. 829, 1127-1134, 1163*a* and 1193: perhaps also Nos. 1045, 1169, 1197, 1198, 1204, 1205, 1207 and some others. Most of these are of pagan, a few perhaps of Jewish origin. Practically all the rest of the inscriptions in this volume are Christian.

Christian inscriptions are somewhat disappointing as sources for our knowledge of the past. Among the pagans, documents of many sorts, both public and private, sometimes of great length, were frequently recorded on stone or metal. The Christian inscriptions, on the other hand, consist chiefly of epitaphs, or brief texts on churches, dwellings or other structures. The information which they contain, therefore, is comparatively limited. Those in the present collection are useful in that they provide an accurate basis for the chronology of the architectural monuments in which Syria abounds, and contribute something to our knowledge of secular history, and of the organization and administration of Syrian towns in the earlier centuries of our era. For example, some light is thrown on the ancient topography of Syria by Nos. 871, 1062, 1156, 1161 and 1175: on administration by Nos. 881, 885, 993, 1068, 1170 etc.: on occupations or professions by Nos. 871, 888, 988, 1080, 1089, 1094, 1096, 1120, 1141, 1143, 1146, 1170, 1176, 1177, 1201, etc. But the chief value of these inscriptions lies in the fact that much may be learned from them about the language and thought of the early Christians, the development and spread of Christian dogma, and the growth of the organized Church.

Père Louis Jalabert, who has earned a place in the front rank of epigraphists by his admirable publications and interpretations of Syrian inscriptions, has contributed to the "Dictionnaire Apologétique de la Foi Catholique" the article *Epigraphie*. This article, in addition to its value as a scholarly and interesting treatise on the subject of Christian epigraphy in general, would serve as a practical introduction to any collection of inscriptions such as this. His analysis of the various classes of Christian inscriptions, his discussion of their various styles and formulae, and his statement of the methods by which they should be classified and interpreted, are sound and useful. In particular, he points out that during the first three or four centuries of our era the Christians not only employed many of the common formulae of the pagan inscriptions in their own, but deliberately avoided all that would give a distinctly Christian character to their monuments and thus arrest the attention and excite the animosity of their religious opponents. Consequently many inscriptions have been or might be classed as pagan, which in reality belonged to adherents of the Christian faith. Many of these disguised inscriptions, however, may be recognized by careful examination and by the help of such criteria as he suggests. In the present collection it happens that a large number of the inscriptions contain definite dates later than 325 A. D., and there are very few which are not obviously of Christian origin. Yet there are some doubtful ones, for example, Nos. 807, 809, 829, 1073 and 1125, and perhaps also Nos. 881 and 896, although these last two are dated 344 and 373 A. D. respectively.

In the second part of this article Père Jalabert discusses with knowledge and clarity the value of the Christian inscriptions for the study of the origins of the Christian Church, both with respect to what he calls the "Vie extérieure de l'Église" — the peoples among whom and the conditions under which the Church was established, the unity of the Church, its struggles and factions — and also with respect to the "Vie intérieure" — the creed, the sacraments, the liturgy, the cult of the saints, ecclesiastical institutions, the morality of the Christians, and their conception of death. In the present collection certain doctrines and beliefs, for example those concerning the Trinity, the divinity of Christ, the remission of sins and the resurrection, are reflected in Nos. 917, 920, 930, 1017-1018, 1034 and 1043: it is perhaps merely an accident that all of these are from the Anderin-Kerrātin-Ma'rātā region. The worship of the Virgin Mary is shown in Nos. 860, 1024, 1062 and 1212: of archangels in Nos. 913, 921, 1050 and 1052: of apostles, martyrs and other saints in Nos. 834, 926, 961, 962, 1006-1013, 1033, 1076, 1100 and 1202. A good many inscriptions contain the names and titles of the clergy, a good many also bear witness to the belief not only in the power of God and of Christ, but also in the efficacy of holy names.

To Père Jalabert, however, as to many others before him, these inscriptions seem to support the contentions of the orthodox theologians and the authority of the Church, because they show that the doctrines, ritual and hierarchy of the Church existed from the beginning of the Church as an organized body. But there remains a question infinitely more important, namely, whether any of the doctrine and ritual of the Church arose from the paganism out of which the Church emerged rather than from the teachings of Christ. The real break, if break there was, in the developement of the Christian Church occurred between the death of Jesus and the first appearance of an organized body of Christians. The continuity of developement, during this all-important period, is in no way established by these inscriptions. On the contrary, the constantly

increasing number of the Christian inscriptions and the more enlightened study devoted to them seem to me to confirm the opinion that those, who were most influential in the organization of the Christian Church and in the formulation of its doctrines, because they were living in a pagan world and because many of them were pagans themselves before their conversion, brought into the earliest Church much that was wholly foreign to the teachings of their Master.

Some of the inscriptions in this collection are among those published by M. Seymour de Ricci in the *Revue Archéologique*, Sept.-Oct. 1907, p. 281 ff. Professor David Robinson, in his review¹ of my former volume, *Part III of the Publications of an American Archaeological Expedition to Syria in 1899-1900*, New York, 1908, said: "An acquaintance with this article by Dr. Ricci, who republishes from a manuscript in the Hague copies made of Greek and Latin inscriptions of Syria by the Belgian consul Gosche about 1700, when the stones were much more legible, would have saved Professor Prentice several mistakes and enabled him to give better readings than his own." Professor Robinson did not mention that I discussed the value of the Gosche inscriptions in my Preface, p. XIII. The question raised here is one of general importance. Undoubtedly two of the inscriptions, *A. A. E. S.*, III, Nos. 98 and 100, cited in my preface, were better preserved when seen by M. Gosche than two centuries later. It is doubtful whether the others were appreciably more legible then than now.² M. Gosche was not always a perfectly accurate epigraphist, as his copies, No. 1 = *A. A. E. S.* III, 14, No. 18 = *A. A. E. S.* III, 57 = *P. A. E. S.* III, B, 1076, and No. 20 = *A. A. E. S.* III, 61 = *P. A. E. S.* III, B, 1086 show. Even where the earlier copy is more plausible than mine, it is not certain that Gosche's reading is correct. Plausibility is not the final test of the accuracy of a copy. In particular, in his No. 6 = *A. A. E. S.* No. 9, I believe that M. Gosche read into the document what Professor Robinson approves. In the presence of the stone itself I tried for a long time to read the name of a month after ἐφέτω, and I do not believe that I neglected to try any combination of letters such as that reported by the Belgian consul. And when this earlier copy was published by M. de Ricci I tried to reconcile it with the excellent squeeze of the inscription in my possession. I still believe that in this instance and some others what M. Gosche wrote was not really upon the stone.

Critics of the earlier parts of the present publication have commented upon the fact that I did not give credit to MM. Deissmann, Mercati and Clermont-Ganneau for their comments³ on the inscriptions published by Dr. Lucas in the *Byzantinische Zeitschrift*.⁴ A word of explanation is due to these scholars. That I was not unaware of the contributions made by them is shown by my own commentary, e. g. under No. 969 below. That I did not mention their emendations in other cases was because their remarks concerned obvious faults in the copies furnished to Dr. Lucas, or were based upon citations of the original verses which were quoted in these fragmentary inscriptions and which could be found by any one in the Concordances to the Greek Bible. For the rest, my critics have rendered great service in correcting some of my mistakes.

¹ *American Journal of Philology*, xxx (1909), p. 205.

² Perhaps Gosche Nos. 10 and 25 should also be excepted.

³ *Philologus* LXIV (1905), p. 475-8. *Byz. Zeitschr.* XIV (1905), p. 587. *Byz. Zeitschr.* XV (1906), p. 279-84.

⁴ *Byz. Zeitschr.* XIV (1905), p. 1-72 and 755 f.

Finally I would like to call attention to an observation of M. Max van Berchem in a letter to M. Barbier de Maynard concerning his "Recherches Archéologiques en Syrie" in 1894, published in the *Journal Asiatique*, 1895, 2, p. 499 and 501: "A quelques heures à l'ouest d'Alep, on rentre dans la région des villes mortes gréco-romaines Ce sont des réunions de villas plutôt que de villes proprement dites". Certainly this statement is true of many, though I think not all, of the settlements where the inscriptions of this collection were found.

WILLIAM KELLY PRENTICE.





















Princeton University, June 15th, 1922.

Abbreviations of Periodicals and Publications Frequently Mentioned.

- A. E. or A. A. E. S. *Publications of an American Archaeological Expedition to Syria in 1899—1900*, I, II, III, IV.
A. J. A. *American Journal of Archaeology*.
Ann. Ép. *L'Année Épigraphique*.
B. C. H. *Bulletin de Correspondance Hellénique*.
C. I. G. *Corpus Inscriptionum Graecarum*.
C. I. L. *Corpus Inscriptionum Latinarum*.
C. I. S. *Corpus Inscriptionum Semiticarum*.
É. A. O. Clermont-Ganneau; *Études d'Archéologie Orientale*.
Ephem. Lidzbarski; *Ephemeris für semitische Epigraphik*.
G. G. A. *Göttingische Gelehrte Anzeigen*.
H. *Hermes*.
I. G. R. *Inscriptiones Graecae ad Res Romanas pertinentes*.
I. S. O. G. Dittenberger; *Orientis Graeci Inscriptiones Selectae*.
J. A. *Journal Asiatique*.
J. K. D. A. I. *Jahrbuch des Kaiserlich Deutschen Archäologischen Instituts*.
J. K. P. K. *Jahrbuch der Königlich Preussischen Kunstsammlungen*.
K. A. Strzykowski; *Klein-Asien, ein Neuland der Kunstgeschichte*.
M. A. A. Jaussen et Savignac; *Mission Archéologique en Arabie*, I.
M. N. D. P.-V. *Mittheilungen und Nachrichten des Deutschen Palästina-Vereins*.
M. S. M. Dussaud et Macler; *Mission dans les régions désertiques de la Syrie moyenne*.
N. E. Lidzbarski; *Handbuch der nordsemitischen Epigraphik*.
P. A. Brünnow; *Die Provincia Arabia*.
P. E. *Princeton Expeditions*.
P. E. F. *Quarterly Statement of the Palestine Exploration Fund*.
P. M. Guy le Strange; *Palestine under the Moslems*.
P. R. G. S. *Proceedings of the Royal Geographical Society*.
P. W. Pauly-Wissowa; *Real-Encyclopädie der classischen Altertumswissenschaft*.
R. A. *Revue Archéologique*.
R. A. O. Clermont-Ganneau; *Recueil d'Archéologie Orientale*.
R. B. *Revue Biblique*.
Rép. *Répertoire d'épigraphie sémitique*.
S. C. Marquis de Vogüe; *La Syrie Centrale, Architecture Civile et Religieuse*.
S. E. P. Conder; *Survey of Eastern Palestine*.
V. A. S. Dussaud; *Voyage Archéologique au Sefâ*.
Z. G. E. *Zeitschrift der Gesellschaft für Erdkunde zu Berlin*.
Z. D. M. G. *Zeitschrift der Deutschen Morgenländischen Gesellschaft*.
Z. D. P.-V. *Zeitschrift des Deutschen Palästina-Vereins*.

Explanation of Ground Plans.

SCALE: 0.0025 M. = 1 M. except when otherwise indicated on the plan.

	Walls standing to a height of 2 M. or more.		Arch in situ.
	Fallen walls, or foundations.		Arch fallen.
	" " material in situ.		Conjectured arch.
	Foundations only in situ, or top of low wall.		Opening high in standing wall.
	Conjectured walls.		" " fallen "
	Column standing to height of 2 M. or more.		Pavement.
	" " " " less than 2 M.		Tunnel-vault.
	Conjectured column.		Cross-vault.
	Columns and architrave in situ.		Cistern.
	Columns and arch in situ.		
	Bases in situ, arch fallen.		

Explanation of Elevations and Sections.

SCALE: 0.005 M. = 1 M. except when otherwise indicated in the drawings.

	Conjectured.		Limestone.
	Basalt.		Brick.

SCALE OF DETAILS: 5 cm. = 1 M. except when some other scale is given in drawing.

NOTE. It has not been possible to carry the above scheme into effect with absolute consistency; but it has been applied in a large majority of the drawings. Departures from the scheme are made clear by the text.

THE DJEBEL SIM'ÂN.

1153. DÊR SIM'ÂN. LINTEL, 334-5 A. D. A lintel upon the ground, about 150 yards northeast of the Southwest Church. Immediately west of it is a single block of the architrave of the second story of a portico, in situ, resting upon a column and a built pier, above two sections of the lower architrave. I suppose this portico to have been part of a private dwelling, and the lintel to have belonged to its main entrance.

The inscription is incised in a dovetail plate. The plate itself measures $89\frac{1}{2}$ by 34 cm.: the dovetails are $19\frac{1}{2}$ cm. long. The letters, 10 cm. high, are formed by broad, clear lines: they are unusually handsome and well executed, the curved lines being almost perfectly circular. The last three letters are in the dovetail on the right.

ΡΟΥΦΙΝΟC
ΚΤΙCΕΝΕΤΟΥC ΓΠΤ

Ῥουφίνος ἔκτισεν ἔτους γπς'.

Rouphinos built (this) in (the) year 383. (334-5 A. D.)

1154. TAVERN, 479 A. D. On the lintel of a doorway in a small group of buildings on the north side of the street which runs up from the wadi into the town, continuing much the same line as that of the sacred road which, on the opposite side of the wadi, led up to the church and monastery of St. Symeon Stylites. See Div. II, B, p. 278. In the center of the lintel is a disk inclosed in a square, measuring 51 cm. each way: the first two lines of the inscription are above this square, the other lines at the right side of it. The second line is 1.47 m. long, the third 39 cm. The letters, 5 to 7 cm. high, are rudely carved.



Entrance to Symeon's Tavern. Inscr. 1154.

ΧΗΓ ΕΓΕΝΤΟΥΤΟΤΟΠΑΝΔΕΝΗ
 ΠΑΝΗΜΩΙΝΔ'ΒΤΟΥΖΚΦΕΤΟΥΧΕΒΟΗΘΙ
 CVMΕΩΝΗC
 ΤΟΝΗΑ
 ΡΙΗΗC
 ΕΠΟΙΗ
 CΕΝΗΝ-Ε
 Θ Η

ΧΜΓ. Ἐγένετο τοῦτο τὸ πανδοχεῖον
 ἐν μηνί Πανήμῳ, ἰνδ. β', τοῦ ζαϑ' ἔτους.
 Χ(ριστ)ῆ βοήθη. Συμεώνης τοῦ Μαρ(ωνο)ῦ
 ἐποίησεν· μνησθῆ.

*Ch(rist) b(orn) (of) M(ary). This
 tavern was (built) in (the) month Pa-
 nemos, indication 2, of the 527th year.
 O Christ, help (us)! Symeon's (son) of
 Maron built it: may he be remembered!
 (July, 479 A. D.)*

In the fifth line M. de Vogüé also read ΠΙΜΗC. Waddington's text, however, beginning with the second line, is as follows: Πανήμ[ω] ἰβ' τοῦ ζαϑ' ἔτους. Χ(ριστ)ῆ βοήθη. Συμεώνης Τουμώας? ἐποίησεν. + In my field notes of 1905 I wrote: "Συμεώνης is certain, I think: after this Η, then Α or Ν or V, then ΡΙΝΗC or ΡΩΝC." With the reading ΗΑΡΙΗΗC the reading ΜΥΡΙΜΗΛ in No. 1156 should now be compared. See the commentary on No. 1120 above.

Waddington, in his very interesting discussion of this inscription, cites Theodoretus¹ as authority for the statement that this town, near which St. Symeon established himself, was called *Telanissos*. Symeon died about 460 A. D. This *pandocheion* or tavern was built 19 years later, evidently to serve the pilgrims visiting the holy place where the saint lived upon his pillar. The body of the saint is said to have been buried at Antioch; but the base of his column and its capital are still to be seen in the center of the octagon which unites the four basilicas of the great church at Kal'at Sim'an. That this was a place of pilgrimage, during the saint's lifetime and for many years afterwards, is well known.

The pandocheion itself was small. Its ruins suggest that it was designed to provide refreshment for its patrons rather than lodgings. I was reminded of the ancient restaurants, or cookshops, at Pompeii, except that in this Syrian establishment there was a forecourt, which seemed comparatively large. See also the following inscription.

On the letters ΧΜΓ so much has been written that it is hardly necessary to enter into a lengthy discussion of the subject here. See my article in *Classical Philology* IX (1914), p. 410-416. Also H. Leclercq in *Dictionnaire d'Archéologie Chrétienne*, I (1907), Col. 180-2 and 1691 ff.; Dölger, *Das Fischsymbol* I (1910), p. 300-317. Four theories regarding these letters are now in vogue: that they signify (1) Χ(ριστ)ῆς (ῥ) Μ(αρία) γ(εννη)θείς² or Χ(ριστ)όν Μ(αρία) γ(ενν)ῃ³; (2) Χ(ριστ)ῆς, Μ(ιχαήλ), Γ(αβριήλ)⁴; (3) Ἄγιος ὁ Θεός, or some other phrase, the sum of the numerical values of whose letters equals that of ΧΜΓ, i. e. 643⁵; (4) a multitude of phrases or combinations of names, the belief being that the more equivalents could be devised for this symbol,

¹ *Religiosa Historia*, Migne, *Patrol. Gr.* LXXXII, p. 1469 ff. See also Uspensky: "Arch. Monuments of Syria", *Izvestiya* VII (1902), p. 165-190 = Offprint, p. 73-98. Dussaud, in *R. A.* XXVIII (1896, 1), p. 332.

² Waddington, No. 2145.

³ Grenfell and Hunt, *Greek Papyri* II (1897), p. 151 and 167. Lefebvre, Blass, Kaufmann, Dieterich and others.

⁴ De Rossi, *Bulletino di Archeologia Cristiana*, 1870, p. 7-32 and 115-121. M. de Vogüé, Nestle, Dölger and many others.

⁵ Krall, in *Mitth. aus der Samml. d. Pap. Rainer*, I (1887), p. 127. Perdrizet, Smirnov (in *B. P. W.* 1906, Sp. 1082-1088), and others.

the greater its power.¹ Of course it is entirely possible that many people who used this symbol were ignorant of its original meaning: to them it was merely a sign, which was useful on house-lintels and elsewhere to avert evil, or which was merely customary. Under such circumstances it would be natural that different interpretations were found for it, and perhaps some believed it the more potent the more meanings could be given to it. But none the less it seems to me quite certain that these letters, when used understandingly, had a definite and particular meaning, and in spite of what Professor Nestle has said three times,² and although Professor Dölger, after a most thorough and careful investigation, has reached the conclusion³): "Vielleicht ist die Lösung Χριστὸς Μιχαὴλ Γαβριήλ in den meisten Fällen die richtige, wenn auch nicht gerade die einzige", yet I believe that ΧΜΓ, at least in the Syrian inscriptions, was a symbol of the Christ alone, and signified, as Waddington suggested, *Christ born of Mary*.

In the first place, there is no certain evidence against this view, no inscription which does not admit this interpretation. The strongest evidence is in an inscription on an amphora found at Rome⁴: ϠΗΓΑ. But Dölger is mistaken when he says that the Γ and Α are "zu einem Zeichen verbunden": the Α is above the Γ and in contact with it at one point; but the two letters do not form a ligature. And I do not believe it possible that here, if Ϡ stands for Χριστός, Η for Μιχαὴλ, two letters, ΓΑ, are used for Γαβριήλ. The Α may be part of an ΩΑ, or it may have some other significance; but it is far from certain that its presence affects the interpretation of ΧΜΓ. Another inscription quoted by Dölger is from "Akrabah" in the Dj. Haurân (Syria): it contains at the top ΧΕΓ on one side of a disk, Μ on the other: within the disk are ΩΑ, in this order, and below the disk Ζωή, Φῶς.⁵ Probably the Μ was omitted from its usual place by mistake, and added afterwards on the other side of the disk. But even as it stands this inscription, while not reconcilable with the formula Χριστὸν Μαρία γεννᾷ, may be, and I believe should be read Χ(ριστ)ὸς γ(εννητὴ) Μ(αρίας)⁶ or γ(ενόμενε) (ἐκ) Μ(αρίας),⁷ if not γ(εννηθεῖς) (ἐκ) Μ(αρίας). The ΘΥΗΓ⁸ cited by Dölger is an emendation.

In the second place, there is no certain evidence that the letters ΧΜΓ ever meant anything else. It is true that in the early Christian literature, in magic prescriptions and on amulets etc., Christ is often associated with the archangels. And of the archangels, Michael and Gabriel are doubtless more frequently mentioned than the others. Not, however, to the exclusion of the others, or so that Christ, Michael, Gabriel form a constant triad. As far as known to me these three names do not appear as a triad in any inscription excepting those on certain Byzantine crosses and works of art in which Christ is represented, or Christ and Mary, with these two archangels one on each side. On such monuments the choice of the triad is due to the nature of the field inscribed or to the desire of the artists for a symmetrical composition, and does not necessarily prove that this triad existed apart from Byzantine art, or that the letters ΧΜΓ, in ordinary inscriptions, were a symbol for it. M. Chapot's statement⁹: "La formule est en toutes lettres du B C H."¹⁰ is misleading: the necessary brackets

¹ Perdrizet, in *R. E. G.* xvii (1904), p. 350-360. Jalabert, Kaufmann and others.

² *B. P. W.* 1906, Sp. 381-4.

³ *Das Fischsymbol*, 1 p. 312.

⁴ *C. I. L.* xv, ii, 1, No. 4888. Dölger, p. 311 f.

⁵ Copy of the Rev. W. Ewing, published by Wright and Souter in *Pal. Expl. Fund.* Q. S. 1895, p. 51, No. 26.

⁶ Cf. *Matthew* xi, 11; *Luke* vii, 28.

⁷ Cf. *Galatians* iv, 4.

⁸ *A. A. E. S.* iii, 254.

⁹ *B. C. H.* xxvi (1902), p. 196, Note 1.

¹⁰ *I. e. B. C. H.* ii (1878), p. 31: an inscription from Attica.

were omitted from Bayet's text; but Bayet's own drawing which faces the text shows that only the three letters are on the stone. The inscriptions cited by Dölger in support of his opinion seem to me to prove exactly the opposite. Sometimes Michael and Gabriel appear in them without Christ. Where Christ is also named, other archangels and other persons are also mentioned. In no single one of these inscriptions do Christ, Michael and Gabriel appear alone together. From this fact it seems clear to me that this triad was not so well known that the symbol ΧΜΓ could represent it. I do not consider that there is any evidence either way in inscriptions such as the ΧΜΓ Καπίου found on sixty-six roof-tiles in Rome.

Thirdly, there is conclusive evidence to my mind that, at least in the Syrian inscriptions, these letters were a symbol of Christ. Apart from the inscription at Refādeh¹ from which Waddington drew his conclusion: + 'Ιη(σοῦ)ς ὁ Ναζωρεῖος, ὁ ἐκ Μαρίας γεννηθείς, ὁ Υἱὸς τοῦ Θεοῦ, ἔθα κατοικί κ. τ. λ., there are a goodly number of Syrian inscriptions in which these letters are combined with other symbols, names or words in such a way that it seems obvious that the whole inscription was intended as a continuous sentence, applying to Christ alone, so that the intrusion of the names of Michael and Gabriel would disturb the sense. Examples of such inscriptions are the following:

Εἰς Θεός, ΧΗΓ, μόνος.²
 ΧΕΓΜ · ΨΑ · Ζωή, Φῶς.³
 [Α] ϙ Ψ, ΧΗΓ, ΙΧΘΥΣ.⁴
 [Χ] ΗΓ · ἐν ὀνόματι Χριστοῦ.⁵
 [Εμμ]ανουήλ, ΧΜΓ · Χριστός νικᾷ.⁶
 ΧΜΓ · ΑΨ · 'Ιη(σοῦ)ς βροῦθι.⁷

Consequently I believe that ΧΜΓ signifies *Christ born of Mary*. It does not appear possible as yet to determine the chronological limits within which this symbol was in use. Inscriptions containing it, in this publication and in *A. A. E. S.*, extend certainly from 365⁸ A. D. to 590.⁹

On the use of *μνησθῆ* see below under No. 1203.

1155. TAVERN, 479 A. D. On a lintel in situ, on the north side of the same street as No. 1154, but farther up the hill towards the West. The building to which it belonged has been destroyed; but it is evident, from the position of the other buildings in this part of the ruins, that this tavern, like the other, was of no great size.

¹ Wad. 2697: *A. A. E. S.* III, 120; *P. A. E. S.* III, 1151.

² From Hāss. Wad. 2660: *A. A. E. S.* III, 155. I do not think the evidence of this inscription can be explained away by Dölger's assumption that ΧΜΓ had become a symbol which interrupted a text as little as a simple +, which appears sometimes in the middle of a word.

³ From "Akrahah", *Pal. Exp. Fund.*, Q. S., 1895 p. 51, also quoted above.

⁴ From Bābūdā, *A. A. E. S.* III, 215.

⁵ From B'ūdā, *A. A. E. S.* III, 216.

⁶ From Serdjillā, *A. A. E. S.* 219.

⁷ From Dellōzā, *A. A. E. S.* III, 224. See also, in the present collection, Nos. 969, 1002, 1047 and 1156. Two other inscriptions here, Nos. 913 and 1090, might throw much light upon this question if they could be interpreted with certainty. As to the first of these, my reading now seems to me as audacious as it seemed to P. Jalabert. The latter I think now may perhaps be read: + Εἰς Θεός, ΗΓΨ, Κύρις (β) [σάβι]

⁸ No. 970 above.

⁹ No. 846. See also Leclercq in *Dict. d'Archéol. Chrét.*, Col. 180 and 182.

The lintel, however, measures 2.64 m. by 93 cm. Probably it was the lintel of a gateway from the street to the court. The inscription occupies a space 79 cm. wide and 18 cm. high, beginning 91½ cm. from the left end of the stone. Above it is a disk, in relief below the surface, 48½ cm. in diameter,



Door-frame of a Tavern. Inscr. 1155.



Inscr. 1155.

containing the letters Α and Ω upside down. The inscription is incised: the letters of the first two lines vary in height from 4 to 8 cm., while those of the third line are only 2½ cm. high. The letters are not well formed; but the reading is certain.

Published by Waddington, No. 2692. *A. A. E. S.* III, No. 122.

†ΕΚΤ/ΤΟΥ ΤΟΠΑΝΔΙΕΝΗ
ΥΠΕΡΒΤΕΙΝΔΙ/ΤΟΝΗΚΦΕΤ,
ΥΓΙΑΤΟΙΣΚΥΡΙΟΙΣΑΥΤΟΥ/ΚΕΡΔΟΣ

+ Έκ(ισή) τουτο (τό) πανδοχείου ἐν
μηνί Ὑπερβ(ερεταίω) κ', ἐνθ. γ', τοῦ μην'
ἐκ(ους). Ὑγια τοῖς κυρίοις αὐτοῦ (καὶ) κέρδους.

This tavern was built in the month Hyperberetaios 15th, indiction 3, of the 528th year. Health to its masters and gain! (October, 479 A. D.)

* Waddington's reading of the last line is: Ὑγια τοῖς κυρίοις Αὐ[γ]ούσ(τοις) κέρδους. In my earlier publication I translated the line *Health to its masters (is) gain*, meaning that the health of the patrons is gain for the proprietor. Perhaps, indirectly, this is true, and certainly it is a good motto for a restaurant. But I am inclined to think now that the sign after αὐτοῦ is meant to represent καὶ, as it often does elsewhere,¹ and that these proprietors were seeking chiefly their own health and profit, as inn-keepers commonly do. Compare also No. 996. An ι with two dots, as here, occurs elsewhere in Syrian inscriptions, e. g. Nos. 1139, 1146 and 1190; *A. A. E. S.* III No. 319; Waddington No. 2619.

1156. HOUSE (?). On a lintel fallen just inside its jambs, in a house or shop on the south side of the same street as Nos. 1154 and 1155, and about 50 feet southeast

¹ For example, Nos. 867, 871, 922, 936, 1034, 1049, 1086, 1088, etc.

of the latter. The lintel is now $1.71\frac{1}{2}$ m. long, and 77 cm. high: it is broken at the right end. In the center, in low relief below the surface, is a disk 41 cm. in diameter, now almost obliterated. The inscription is incised below the disk. The letters, 6 cm. or more high, are formed by broad, shallow lines, and all are now badly weathered. The first line is now 1.61 m. long, exclusive of the cross, and begins 10 cm. from the left end of the stone. The second line, to the end of the letters ΣEN , is 73 cm. long, and begins 50 cm. from the left end of the stone. The lacuna after ΣEN is 26 cm. long. The remaining letters, OV , occupy a space of 12 cm. I am inclined to think that the whole inscription, with the exception of half a letter at the end of the first line, has been preserved, and that the two letters after the lacuna in the second line should be read with the line above. There is a small \circ above the π in the first line.

+ ΧΗΓΕΝΩΝΟΜΑΤΙΧΡ/ΣΥΜΕΩΝΑΠΜΥΡΙΜΗΛ
ΕΡΞΕΝΚΑΙΕΤΕΛΗÇΕΝ ΟΥ

+ X M Γ. Εν ὀνόματι Χρ(ιστοῦ) Συμέων ἀπὸ Μουριμήνου (?) ἔρξεν καὶ ἐτέλεσεν.

+ *Ch(rist) b(orn) of M(ary). In (the) name of Chr(ist) Symeon from (the village of) Mūrimn(?) wrought and finished.*

The last letter of the first line is most uncertain, since more than half has been destroyed by the break in the stone, and the rest is damaged. What remains looks more like A or Λ: I have read N, however, at the suggestion of Professor Littmann. There are a number of Syriac place names ending in *-in*. Perhaps we have here the same sort of an expression as in *A. A. E. S.* III, 48: Ἀπολλώνιος κτλ. ἀπὸ ἐποικίου Μειθου.

On Symeones see above under No. 1120.

The sign / as a mark of abbreviation occurs often, e. g. in Nos. 890, 899, 902, 913, 1046, 1050, 1120, 1146 and 1151.

1157. SARCOPHAGUS. On the cover of a monument in the form of a sarcophagus, hewn from the living rock, in the necropolis south of the town. The cover has the form of a temple roof, with acroteria at the four corners, and, in the middle of the side, a rounded protuberance, with a semicircular face in the plane of the side of the sarcophagus and rising above the line of the edge of the cover. The radius of this semicircular face is about 34 cm.: within it is a disk, 19 cm. in diameter: the inscription is half on each side of this disk.

The inscription is badly weathered. I am inclined to believe that originally there were three lines on each side of the disk, of which the uppermost on each side has disappeared.

.....
B O Y disk B I _
I A K W A B C A

Perhaps this may be read as follows: [Aγ](ι)ου Ἰακώβου]

B(α)[ρ]αβσα: (*The tomb*) of holy Jakobos, son of Barabsas.

But of course this reading is very uncertain. The first letter of the second half of the third line may be an O.

On the name Barabsas see above under No. 1136.

1158. HOUSE. On the jamb of a doorway, near the northeast corner of a house, south of the North Church. The letters are incised: they are 9 to 10 cm. high. Above the second κ is a small ο: the two letters after this are indistinct and doubtful. Copied by Professor Littmann.

ΚΕΒΟΗΘΗ
 CΕΡΓΙΧ
 ΔΙΑΚΝΥ

Κ(ύρι)ε, βοήθη Σεργίου διακόνου.
 Lord help Sergios (the) deacon!

Probably βοήθη is for βοήθει, and Σεργίου διακόνου for Σεργίω διακόνω.

1159. LINTEL. An inscription, copied by Waddington and published by him in his collection, No. 2693. Also in *A. A. E. S.* III, No. 123. I was not able to find the stone. Waddington, in his description says merely: "Sur un autre linteau; devant la porte il y a plusieurs auges." His epigraphical text shows, below the first line, three small disks, which break into the second and third lines.

†ΕΚΤΕΧΝΚΥΡΟC-----ΜΝΩ
 CΥΜΕΩ -----
 ΝΗC ΜΟC

Waddington has rendered this inscription as follows: + Ἐκτετην κύρος
 Συμεώνης [αἰκοδό]μος, believing

κύρος to be for κύριος; but a proper name would be more natural in this place, and Κύρος occurs as a proper name, for example in *A. A. E. S.* III, 57 (= No. 1076 above) and 288. Consequently I believe we should read Κύρος here, and translate: + *Kyros built this Symeones was the mason.*

On the name Symeones see above under No. 1120.

1160. NORTH CHURCH. In the extreme northeastern corner of the town, not far west of the first arch over the sacred road, on the lintel of the eastern doorway in the south wall of a small church. Div. III, B, p. 275, Ill. 294. The inscription is incised on a dovetail plate in relief, in the center of the uppermost fascia of the mouldings. The plate measures 33½ by 19½ cm. The letters are 4½ cm. high. In the dovetail on the left are the letters ΧC, and in that on the right ΝΙ.

Published by Waddington, No. 2694. Renan: *Mission en Phénicie*, p. 611, Note 3. Clermont-Ganneau, *Recueil*, IV, p. 85 ff., and V, p. 290. *A. A. E. S.* III, 124.

†ΤΩΟΙΚΩCΟΥ
 ΧC ΠΡΕΠΙ_ΓΙΑC ΝΙ
 ΜΑΚ_ΡΙΕ†

Χ(ριστὸ)ς νικῶν. + Τῷ οἴκῳ σου πρέπει [ἀ]γίασμα, Κ(ύρι)ε. +
 Christ Conquers! + Holiness becometh thine house, O Lord! +

Waddington's reading of this was incorrect: the words in the body of the plate are taken from *Psalms* XCII, 5.

1160 a. DOORWAY. On the westernmost of two jambs, standing alone, the building to which they belonged having been destroyed. The jambs have no mouldings. The inscription was copied by Professor Littmann. If I understand his note correctly, this

doorway faced upon the street which runs westward past the two taverns mentioned in Nos. 1154 and 1155, the doorway being about 20 meters east of the first well-preserved house as one approaches from the East. The inscription is incised, and occupies a space 44 cm. broad and 36 cm. high: the letters are 5 to 7 cm. high.



Insc. 1160 a.

Οἰκοδ(όμησε) Βάκχ(ο)ς, υἱὸς Ἀμροσίου.

Bacchos, son of Amrosios, built (this).

The name Βάκχος occurs in No. 1088 above, Βάκος in Wad. 2053 c. Perhaps, however, Βά(ρ)[α]χ(ο)ς should be read, as in *A. A. E. S.* III, 247. The name Ἀμρος or Ἀμροσος occurs often in Waddington's collection.

1161. ΚΑΛΑΤ ΣΙΜΑΝ. KEYSTONE of a flat arch over a doorway, facing south, in the last wall towards the South, between the group of buildings about the "baptistery", i. e. the small octagonal building at the south end of the hill-top, and the last, i. e. the northernmost, archway of the sacred road. The sill of the doorway is now about $4\frac{1}{2}$ feet above the present ground level. On either side of the doorway is a small window. The keystone is 54 cm. broad at the top, $26\frac{1}{2}$ at the bottom: it was originally 1.18 m. high; but about 5 cm. have been broken away from the face at the bottom. In the center is a disk in relief, 27 cm. in diameter. The inscription is incised. The letters, $4\frac{1}{2}$ to $5\frac{1}{2}$ cm. high, are well cut and most of them well formed: nearly all of them are still perfectly distinct. They are, however, difficult to read without the aid of a ladder of sufficient length, and this undoubtedly accounts for M. Chabot's remark: "Je donne le facsimilé de ma copie, sans chercher à la restituer, ce qui me paraît d'ailleurs impossible". For this reason I do not quote M. Chabot's reading, which differs considerably from mine.

Published in part by J.-B. Chabot in *Journal Asiat.*, 9e Série, vol. XVI (1900), p. 272 f., and Plate B (facing p. 300).



Inscr. 1161.

Τοῦτο τὸ ἔργον τοῦ κομέτου Ἀγαπίου· μίσθηται εἰς τὸ συναχίς. Τη χήτης Παλλάδιος Ἀβραάμ, Ἡρακλίτου, Τίλοκβαριν(ός).

This is the work of the townsman Agapios: remember (him, O Lord) continually! Builder, Palladios Abraham, son of Heraklitos, of Tilokbarin (?).

The author of this inscription seems not to have been a perfect master of the Greek language: certainly he could not spell correctly. Of course ἔργων is for ἔργον, μνήσθῃσι for μνήσθῃσι. I have assumed that κομέτου is for κομήτου, although it is possible that κόμητος was meant. If this assumption is correct, Agapios was doubtless a resident of the neighboring village of Telanissos.¹ I am indebted to my colleague Professor David Magie for the suggestion that CYNΛΞIC² is for συνεχίς, and perhaps CYNΛXEC is really on the stone. Probably τεχνίτης is for τεχνίτης; but perhaps τεχνίται Παλλάδ(ως), Ἀβραάμ, Ἡράκλειτος, Τυοκβαρν(οί) was intended. The last name I believe to be an ethnicon, and possibly this name is still preserved in *Tell 'Akibrin*, the present name of a modern village and ruin, situated about 12 miles south-southwest of Ḳal'at Sim'ān.

1162. CONVENT (?). On the keystone of a flat arch over the door in the west side of the small church south of the east basilica of the great church of St. Symeon. See Div. II, B, 6, Pl. XXIII, M: also de Vogüé, *Syrie Centrale*, Pl. 139. Before the wall in which this doorway is situated, i. e. on the western side of it, there was a colonnade of piers, in two stories, which formed the front of a portico or cloister.

The stone is 52 cm. broad at the top and 23½ at the bottom: it is 1.16 m. high. A very handsome cross, 29 cm. high and 26 cm. broad, is executed in intaglio upon the smooth surface of the block, its center 6 cm. above the center of the keystone: the arms of the cross are 4 cm. broad at the outer ends and notched, but taper considerably towards the center. Below the cross is the inscription, incised. The letters, very well cut and clear, are 5 to 5½ cm., the whole inscription 16 cm. in height. A thick, hard plaster now covers the stone above the cross and below the inscription: the whole wall seems to have been plastered so at one time.

ΧΡΙCΤΗ
ΒΩΗΘΙ
ΠΑCΙΝ

Χριστή, βοήθη πάντων.

O Christ, help (us) all!

1163. On the keystone of a flat arch over another doorway, farther north in the same wall as No. 1162. The present doorway was much smaller than the other, for the arch of the former is about at the height of the center of the latter. In the center of this keystone is a cross, similar to that of the other. In this case, however, the inscription is above the cross. The letters have the same form as the others. I could find no trace of any other letters, although there was room for another line between these and the cross.

ΚΥΡΙΕ ΗΛΗCΘΗ

I suppose this to be the very familiar Κύριε ἤλεησον (*Kyrie eleison*): *Lord have mercy (upon us)!* Certainly the form ἤλη

is peculiar, even if it is read ἤλῃ[σον], or ἤλῃ for ἤλῃ, ἤλῃ, the present imperative. Possibly the author may have had the Semitic Eli (Ἠλᾱ, Ἠλᾱ, Ἠλᾱ) in mind.³

¹ See the commentary on No. 1154.

² The word συνέχης, in itself, would not be unnatural here: among the Christians it meant the assembling of the people for worship, especially for the communion service; also the congregation.

³ *Matthew* xxvii, 46.

1163 *a*. BĀSHAMRĀ. LINTEL. On a lintel, in situ, facing west. The stone measures 2.55 m. by 71 cm. The letters are 11 to 12 cm. high, and the whole inscription is 82 cm. long. Copied by Professor Butler.

KAICOI

Kzì σοί.

To thee also.

These words are discussed above, under No. 1125.

1164. BĀṢŪFĀN. On a fragment, upside down in the east wall of an Arabic tower, which is built against the south side of the East Church. See Div. II, B, p. 284, Plan of Church. The stone is 1.11 m. long and 23 cm. wide: it is broken at the left end. It might have been part of an architrave, or of the lintel of a small door or a window.

ZWH +++ XAPA

Ζωή +++ Χαρά

Life +++ Joy!

1165. KEFR LĀB. LINTEL. On a large lintel in the south wall of a small ancient building, facing south, at the extreme north edge of the town. The lintel is not in its original place. The inscription, in letters about 5 cm. high, is incised at the bottom of the face: its total length is 1.49 m. It is so badly weathered that I could read no single word. One letter only, φ, seemed certain: farther on NX seemed probable

+ PPI ΦΤ

ΗΚΕ ΗΥΖΘΗΗΗΝΧΤΠΟΙΩΠ

Inscr. 1165.

It is possible that this document began with a date, of which the φ formed a part, and should be read: + Ετ[ου] φ', or + Το
-- φ' έτους δ θείνα έπ[ο]σ[η]σεν.

I think it is possible, however, that the inscription is not Greek at all.

1166. LINTEL. On a lintel lying on the ground, about 50 feet southeast of the foregoing. The inscription is incised on the topmost band of a series of mouldings, including two rows of dentils, forming a sort of door-cap. On each side of this door-cap is a dovetail plate in relief, upright. The letters are formed by broad lines, and are about 5 cm. high: those now preserved measure together $1.14\frac{1}{2}$ m. in length: originally there were from 3 to 6 more at the beginning, and 1 or 2 more at the end.


ΟΕ ΗΙΝΕΘΗΘΗΠΑΘΕΗΟΥΠΟΙ

The Η, in both places, is very doubtful: so also ΑΟ. The two letters before ΥΠΟ may be ΚΩ, instead of ΗΠ, or after Η(?) a Γ.

I have not been able to decipher this inscription satisfactorily. Perhaps [Ε]ς [Θ]ς [μ]όνος· βοήθη τῇ οἰκῇ: *One God only: help this house*, might be read. At the end, ὑπομή or τούτω. See the commentary on No. 1126.

1167. BURDJ HĒDAR. DOORWAY WITH A VESTIBULE, 487 A. D. On the lintel of a doorway, in what was a handsome wall, having before it a vestibule with sides

of solid masonry and roofed by single slabs of stone which are still intact, in the northwest corner of the town. See Div. II, B, p. 292, Plan of Mortuary Chapel. Immediately before the vestibule, on each side, is a small altar, about two feet high, with good simple mouldings. I did not discover the character of the building to which this entrance belonged. There has been some rebuilding here, and apparently the doorway with its vestibule was used as the entrance to some comparatively late structure. The lintel itself is very large, being about 3.00 m. long and 60 cm. high. The inscription is upside down, and begins at the right end of the stone in its present position. Professor Littmann, who made the copy, believed that the lintel is upside down, and that it was reversed when this doorway was rebuilt. The +, however, which is at the right end of the stone in its present position, and which would precede the inscription if the lintel were reversed again, is right side up now. See No. 1196 below. The letters are incised: they are well cut, but not very regular in size or alignment, the average height being about 9 cm. In the center is a disk.



Vestibule at Burdj Hêdar. Inscr. 1167.

+ ΕΚΤΙΘΗ ΠΑΡΑ ΣΙΜΕΩ disk ΕΝ ΜΗΓΛΕΙΝΔΙ ΑΙΣΛΦ

+ Ἐκτίσθη παρὰ Σιμέω, ἐν μηνί Γ(ο)ρ(πιαίω) ε', ἰνδ. α', (τοῦ) ε' λ' (ἔτους).


+ Built by Simeas, in month Gorpaios (?) 5th, indiction 11, of (the year) 536. (September, 487 A. D.)

I have read the name of the month Gorpaios. If this is correct then it is evident that in this region, at this date, the year began in September; for September 488 falls in the 12th indiction. See the commentary on No. 1108. On the other hand the letters which stand for the name of the month may be ΠΡ in a ligature, or even Π alone. In this case the month is Peritios or Panemos, and the date February or July, 488 A. D.

The name of the builder, Σιμέω, I take to be for Σιμέου. See Dussaud and Macler, *Mission*, p. 279, No. 116; Lidzbarski, *Ephemeris* II, p. 332, line 19 f. Possibly there is a connection between this name and that of the god mentioned in No. 1170 below. On the other hand, the letter after the σ may well have been γ, and, whether this letter was γ or ι, perhaps Σιμεῶ(γος) or Σιμεῶ(ιος) should be read.

I believe that this inscription is later than the door-frame on which it is carved.

1168. HOUSE (?). On the lintel of a house, facing north, in the north center of the town. Before the house was a portico, the ruins of which nearly cover the doorway, so that the ends of the lintel are hidden. In the center of the lintel is a rectangular plate in relief, 54 cm. broad and 43 cm. high. This plate seems to have contained four lines of letters, two above and one below that which is shown in the drawing. If there were really four lines on the plate, however, three of them have become quite illegible, or at least seemed so to me. The extant line on the plate is nearly level with the upper line on each side. The first line at the left of the plate is 92 cm. long, at the right 48 cm. The second line, at the left, is 70 cm. long, 3 or 4 letters having been broken away from the beginning: at the right of the plate the second line is 51 cm. long. The stone is broken at the right end, so that possibly 4 letters more have been lost from the end of the first line, and three from the end of the second. These letters vary from 6 to 9 cm. in height. The letters on the plate in the center are smaller. Below the plate is still another line of letters a little smaller still. The whole inscription is very badly weathered, and the reading altogether uncertain.



Inscr. 1168.

The first part of the first line contains, of course, the familiar *Εἰς Θεὸς ὁ βοηθῶν*: *One God that helpeth*. See the commentary on No. 1126 and also *A. A. E. S.* III, 25 (p. 51 f.).¹ For the rest, it does not seem to me that my copy has preserved

enough of the inscription to warrant any attempt at restoration. In the second line one might think of *ἐπιμελίζ* and perhaps *τῷ θεῷ σου*. Below the plate there was probably a date, ending with *ἰνδ. ε'.*

1169. WEST CHURCH. On the lintel of the west door in the south wall of the West Church. Div. II, B, p. 288. In the center of the lintel is a door-cap, and on each side of the cap a disk containing a six-pointed star. The whole lintel is about 2.40 m. long and 55 cm. high. The inscription is incised below the door-cap. It is 71 cm. long, and the letters 11 cm. high. Copied by Professor Littmann.

+ IC ΘΕΟC + + (Ε)ἰς Θεός. + + *One God.* +

See the preceding inscription.

1170. KEFR NABŌ. OIL MILL, 224 A. D. On a lintel in two pieces found together upon the ground immediately south of a small building near the southeast corner of the town. The original character of this small building I could not determine; but I doubt if there was any connection between it and the lintel. The latter, as its inscription shows, belonged to an oil mill, which was the property of three gods, and

¹ For other examples of this formula see the *Index of Phrases*, and especially Nos. 968, 1049, 1075, 1089, 1095, 1186, 1189, 1200, 1201 and 1204.

was built from the funds of their cult. There was in this town a very large temple, drums of the columns of which were afterwards built into the apse of the church. See Div. II, B, p. 294.

The lintel was originally about 2.45 m. long, and 79 cm. high. It is ornamented by a series of mouldings, of which the lowest two fasciae bear lines 1 and 2, and lines 3-5, respectively. These mouldings do not frame the lintel, but form a sort of door-cap. At the right side, the face of the lintel extended, originally, about 22 cm. farther; but from this end a rectangular hole has been cut, as if to receive the end of a beam, so that the space beyond the cap, opposite lines 1-4, is now only from 8 to 10 cm. wide. The cutting of this hole, however, does not seem to have destroyed any letters, and perhaps the hole was cut before the inscription. The space at the right of



Left half of the lintel which bears Inscr. 1170.

the cap was used for completing lines 2 and 3. The letter ζ of $\pi\rho\sigma\theta\acute{\omega}\nu$ was evidently omitted by mistake, and added on the face of the stone nearly in a line with $\Pi\rho\theta$. Then, there being a little room left at the end of line 3, after $\kappa\lambda\alpha\upsilon\delta\iota\omicron\upsilon$, the carver, wishing to add $\tau\omicron\upsilon \epsilon\beta\sigma\kappa\acute{\alpha}\tau\omicron\upsilon$, wrote a small τ on the cap, and beyond, $\omicron\upsilon$, $\beta\omicron$, $\kappa\alpha$, $\tau\psi$, these letters in pairs one under the other, beginning under the ζ mentioned above. This ζ he then seems to have changed to ϵ , adding a very small ζ for the $\pi\rho\sigma\theta\acute{\omega}\nu$ still farther up. This procedure has placed the letters in a curious order; but the meaning is clear enough. Line 5 is in very small letters, and is carved along the bottom of the lowest fascia, below line 4, where there is no proper space for it. Obviously this line was added after the rest was finished. Lines 6-8 are carved below the cap, on the plain face of the lintel.

The two inscribed fasciae were 2.20 m. long (both fragments together): the first is 12 cm. wide, the second 15 cm. Below the cap the space containing lines 6-8 is 18 cm. high. Line 6 begins 11 cm. from the left end of the stone, and is 2.18 m. long. Line 7 begins 82 cm. from the left end, and is 1.55 m. long. Line 8 begins 1.02 m. from the left end, and is 75 cm. long. Most of the letters are 5 to 6 cm. high: the smaller ones, however, are only 4 cm. high or less.

Published by M. Victor Chapot, in *B. C. H.* xxvi (1902), p. 181 ff. and by M. Th. Uspensky, in *Archaeological Monuments of Syria*, 1902, p. 71 f. = *Izvestiya of the Russian Arch. Institute at Constantinople*, Vol. vii, p. 164 f. See Lidzbarski, *Ephemeris für Semitische Epigraphik* II (1903-1907), p. 323 f. See also Dussaud, in *R. A.* iv (1904, 2), p. 251-260.



Cast of Inscription No. 1170.

1. Σεμίῳ καὶ Συμβετύλῳ καὶ Λέοντι, θεοῖς πατρώοις, τὸ
2. ἔλαιο(τ)ῶν σὺν κατασκευῇ πάσῃ ἐκ τῶν τῶν θεῶν προσ-
3. ὄδων, διὰ Νομερίου καὶ Βερίωνος καὶ Δαρείου καὶ Κλαυδίου τοῦ ἐβουκατ(ου),
4. ἐπιμελητῶν, καὶ Ἀντωνίου καὶ Σωπάτρου, λευκουρῶν,
5. — Δ[ο]μετιανός, τέκτων, μνηστῆρ. —
6. Καὶ Γαίου καὶ Σελεύκου, τεκτόνων, ἔτους β'ος', μηνὸς
7. Περιτίου ε', συνετέλεσθη καὶ ἀρμεράθη.
8. Ὁ γράψας, Θεότεκνος.

To Seimios and Symbetylos and Leon, ancestral gods, the oil-mill, with all its fixtures, from the revenues of the gods, through Nomerios and Berion and Dareios and Klaudios the *evocatus* (i. e. a veteran, still qualified for military service), *epimeletai* (i. e. directors or superintendents of the property of the gods), and Antonios and Sopatros, *leukourgoi* (i. e. marble-workers) — may Dometianos (the) builder be remembered — and Gaios and Seleukos, builders, in the year 272, month Peritios 15th, was finished and dedicated. He who wrote this was Theoteknos. (February, 224 A. D.)

The names of the three divinities mentioned here are important for the study of the religions of Northern Syria. As M. Chapot has said, Σεμίος (or Σεῖμος) is evidently the masculine counterpart of Σεμιά (or Σεμία) mentioned in the inscription from Burj el-Qaé¹ and elsewhere. The editors of the latter inscription associated this name with the Aramaic *Shemaiyā*, *Shamīn* = *Heavens*. It seems fairly clear now that there is no such connection, or at least no direct connection. The origin of the name appears to be *Simi* or *Sima*, the name of a very ancient goddess, perhaps originally from Babylon, worshipped in Northern Syria in early times. This goddess is doubtless the same as the Ἀσιμιά (*Ašimā*), imported into Samaria by the colonists from Αἰμιά (Ḥamā) after the Assyrian conquest near the end of the eighth century B. C.² Like a good many oriental deities, this one appears both in a male and in a female form. The god or goddess is mentioned in at least seven inscriptions already known, namely, (1) and (2)

¹ This letter is uncertain: if the mark was intended for a letter at all, it is badly executed. I read this name Σεῖμος originally.

² A Π in this place is almost certain: if not, then ΤΙΡ.

³ There is no *ι* here, as the squeeze shows: the mark, read as *ι* by M. Chapot, is accidental, and not large enough for a letter.

⁴ See below.

⁵ IV Kings, xvii, 30. Ronzevalle, in *R. A.* II (1903, 2), p. 35 ff. Dussaud, in *R. A.* IV (1904, 2), p. 258.

from Deir el-Qal'a,¹ (3) from Ḥomṣ (or Palmyra),² (4) from Burj el-Qaé (4 hours N. N. E. of Ḥomṣ), dated 196 A. D.,³ (5) on a gem,⁴ (6) on the wall of a rock-hewn chamber near Wastha, north of Tyre,⁵ and (7) the present inscription.

In these seven inscriptions the name appears three times certainly as feminine (Nos. 2, 4 and 5), once certainly as masculine (No. 7): three times the sex is uncertain (Nos. 1, 3 and 6). In two of these cases the feminine Σημέα appears alone, or with Ἀτταργατεῖς (Ἀτάργατις): in other cases the name appears in a triad, to which, in one instance, a Νεωτέρη Ἡφα, apparently the princess Soaemias, has been added. At Deir el-Qal'a, in one inscription (No. 2) this triad appears as *Jupiter Balmarqod*, *Juno Regina* = θεὰ Ἡφα, and *Juno* (θεὰ) *Sima*. In the other inscription from Deir el-Qal'a (No. 1) *Juno Regina* may have been omitted, *Jupiter Balmarqod* appearing with *Juno Sima* alone. In the monument found at Ḥomṣ (No. 3) a triad, of which the goddess is called Ἀθηνᾶ and the god on the right Κεραυνός, appears in the relief in its present state.⁶ In the inscription below this relief apparently the goddess is called *Seimia* or *Seima*, and the two gods *Bel Iarebol* and *Aglibol*.⁷ In the inscription from the neighborhood of Tyre (No. 6) the triad appears⁸ as *Helios*, *Aphrodite*, and *Simia* or *Simios*. In the present inscription the triad appears as *Seimios*,⁹ *Symbetylos*, and *Leon*.

M. Chapot and the other editors¹⁰ of this inscription have pointed out that the name *Symbetylos* signifies the consort, or paredros, or sharer in the baetyl, of the god. Doubtless then this consort, whose proper name is lacking, is no other than the goddess *Sima* or *Sēmea*, the female counterpart of *Seimios*. The lion is well known as the animal sacred to Atargatis and often associated with her on monuments belonging to her cults. Professor Lidzbarski suggests that perhaps the lion was deified originally because it was often represented as the bearer of the goddess. Perhaps at Kefr Nabō a lion was represented as the bearer of a sacred baetyl. M. Dussaud has entered more fully into the discussion of this subject¹¹: "Le lion à signification solaire est le *djinn* par excellence, le dieu Gennaïos, à tel point que Gennaïos est employé comme épithète du dieu solaire. Elle est appliquée à Ba'al-Marqod, à Malakbel, tandis que Gennaïos à Héliopolis était vénéré sous la forme d'un lion dans le temple même de

¹ No. (1) in *C. I. L.* III, 159 and 6669. See also Clermont-Ganneau, *Recueil* I (1888), p. 109 f., and V (1903), p. 81 f.; *R. A.* 4^e S. II (1903, 2), p. 229. Perdrizet, *R. A.* 3^e S. XXXII (1898, 1), p. 39 f. Ronzevalle, *R. A.* 4^e S. II (1903, 2), p. 41 f. Dussaud, *R. A.* IV (1904, 2), p. 252. No. (2) Published by Ronzevalle, *l. c.*, p. 29-49. Clermont-Ganneau, *Recueil* VI (1905), p. 35-41 (= *R. A.* II, p. 225-9). Dittenberger, *O. G. I. S.* II (1905), No. 590. Lidzbarski, *Ephemeris f. sem. Epigraphik* II (1903-7), p. 324 f.

² Published by P. Lammens in *Musée Belge* V (1901), p. 273 f., No. 28, and in a communication from R. P. Ronzevalle, containing a good photographic reproduction of the monument, in *C. R. de l'Acad. des Inscr.* 1902, p. 235 f. See also Ronzevalle in *R. A.* 3^e S. XI (1902, 1), p. 387-391 (written Nov. 28, 1901). Also the communication of P. Ronzevalle presented by M. de Vogüé in *C. R.* 1903, p. 276-283. Dussaud, *R. A.* IV (1904, 2), p. 248 f.; *Les Arabes en Syrie avant l'Islam* (1907), p. 131; *R. E. G.* XXI (1908), p. 204. Lidzbarski, *Ephemeris* II, p. 83 f.

³ Published by MM. Perdrizet and Fossey in *B. C. H.* XXI (1897), p. 70 f., No. 11. See also Perdrizet in *R. A.* 3^e S. XXXII (1898, 1), p. 39-41.

⁴ Published in *C. I. G.* IV, 7046 and by M. Dussaud, in *R. A.* 4^e S. IV (1904, 2), p. 252 f. Also Rayet, *B. C. H.* III (1879), p. 406-8. Mordtmann, *Z. D. M. G.* XXXIX (1885), p. 42 f.

⁵ Published by Renan in his *Mission de Phénicie*, p. 647 ff., and by Dussaud in *R. A.* IV (1904, 2), p. 253 f. Also *C. I. S.* I, p. 27.

⁶ Some believe that there were originally four persons here.

⁷ In spite of *I. G.* XIV, 971, however, I am not entirely convinced that Aglibol is masculine.

⁸ According to M. Dussaud's reading.

⁹ Or *Seimos*.

¹⁰ Dussaud, Lidzbarski, *l. c.*

¹¹ *R. A.* 4^e S. IV (1904, 2), p. 229 f.: the necessary references are given by M. Dussaud in the foot-notes. See also Ronzevalle in *C. R. de l'Acad.* 1901, p. 459 f. Heuzey in *C. R.* 1902, p. 190-200. Clermont-Ganneau, *Recueil* I (1888), p. 94-96; *C. R. de l'Acad.* 1902, p. 472 f.; *Recueil* V (1903), p. 154-163.

Jupiter Héliopolitain — ce qui autorise à le reconnaître dans la dédicace de Kefr-Nebo sous le vocable *Αἰώντι*. A Emèse, Gennaïos se manifesta sous la forme d'un bétyle⁷.

The triad at Kefr Nabō, then, was in reality Seimios, Sima and Leon = Gennaïos. The learning and research of M. Dussaud¹ and others² have made the following statements fairly certain: —

(1) In all these cases, excepting possibly the last mentioned, this triad is the same as the well-known triad of Heliopolis (Ba'albek), i. e. Jupiter Heliopolitanus, Venus, and Mercury.³

(2) The first of these deities, Jupiter Heliopolitanus at Ba'albek, Balmarqod at Deir el-Qal'a, Iarebol at Homş (or Palmyra), Helios at Tyre, etc., is the god of the heavens, the Babylonian Marduk, the Syrian Hadad,⁴ among whose symbols were sun-rays and the bull.

(3) The second is his consort, the Babylonian Ištar⁵ or 'Atar'atē, the Syrian Atargatis, Lucian's (?) Dea Syria, among whose symbols were sun-rays, sun-disk and moon-crescent combined, and the lion. This goddess was identified under Greek and Roman influences most commonly with Hera = Juno, or with Aphrodite = Venus, sometimes apparently with Athena Kyria.

(4) The third deity of the triad, Mercury at Ba'albek, elsewhere Simios, or in feminine form Sima etc., was considered the son or daughter of the other two. This Mercury has been identified with Nebo,⁶ and Nebo is the son of Marduk and Venus Sarpanitu.⁷ That Simios is the son of Juno (Atargatis), or Sima the daughter of Jupiter (Balmarqod), or that Balmarqod and Atargatis together are the parents of Simios or Sima, is stated in Inscription 1 from Deir el-Qal'a. Xanthus the Lydian tells⁸ that Atargatis had a son *Ἰχθύς*, with whom she was thrown into a lake by Mopsus. I am inclined to agree with M. Dussaud that this *Ἰχθύς* is another name for Simios. The story told by Diodorus,⁹ although confused, points to the same conclusion: Derketo, here evidently the same as Atargatis,¹⁰ fell in love with a young Syrian whose name is not given. By him she had a daughter called Semiramis. Ashamed of her conduct Derketo made away with the young man, and had her infant daughter exposed in a desert: she then changed herself into a fish and disappeared in a lake. The daughter was reared for a time by doves,¹¹ but finally was rescued by shepherds and given to a royal overseer named Simmas.

¹ "Notes de Mythologie Syrienne" IV, § 4: "Les Dieux Symbétyles Simios et Simia", in *R. A.* 4^e S. IV (1904, 2), p. 251-260, and, in general, his "Notes de Myth. Syr." I, in *R. A.* I (1903, 1), p. 347-382, and IV, in *R. A.* IV, 225-260.

² Perdrizet, in *R. A.* 3^e S. XXXII (1898, 1), p. 39-41; Ronzevalle, in *R. A.* 4^e S. II (1903, 2), p. 29-49; Clermont-Ganneau, *Recueil* VI (1905), p. 35-41.

³ See *C. I. L.* III, 7280. Perdrizet in *C. R. de l'Acad.* 1901, p. 131 f. Cumont, in *Musée Belge* V (1901), p. 149. Dussaud, *l. c.*, p. 258.

⁴ Possibly also Malachbel.

⁵ The Phoenician Astarte, though doubtless originally identical with Ištar, appears to have had an independent development, probably under Egyptian influence.

⁶ Perhaps he is also the Aglibol of Palmyra: see above, p. 183, note 7.

⁷ Dussaud, *l. c.* p. 258.

⁸ Fig. 11 in *F. H. G.* I, p. 38 (Athenaeus VIII, c. 37).

⁹ Book II, c. 4.

¹⁰ Although perhaps to be distinguished from Atargatis elsewhere, as M. Dussaud believes.

¹¹ Fishes and doves were sacred in the Cults of Atargatis, which had a wide vogue in Syria and Phoenicia, and at least the fish as a symbol was carried, doubtless chiefly by the Phoenicians, westward through the Mediterranean and especially along the African coast, where it still survives under circumstances which indicate an unbroken tradition from ancient paganism. Moreover the fish is still a sacred object to some of the modern natives of Northern Syria and Asia Minor, who will not eat fish, doubtless originally for this reason. These facts, established by Professor Dölger (*Das Fischsymbol* I (1910) p. 425-446), and others, throw a strange light upon the use of the fish and the dove as symbols by the early Christians.

In the Kefr Nabō inscription the usual triad, Hadad, Atargatis, and Nebo-Mercury-Seimios or Simos, has been replaced by Seimios, Symbetylos (i. e. Sima), and Leon. Perhaps this may be accounted for by the supposition that Nebo = Seimios was the patron god of the place, as its modern name, *Kefr Nabō*, suggests. If then the god Hadad (= Jupiter Heliopolitanus, Balmarqod, etc.) in this locality was displaced by Seimios, it is natural enough that Hadad's consort, Atargatis etc., was replaced by the counterpart or consort of Seimios, here called Symbetylos, who, as it was said above, is probably the ancient Syrian 'Ašimā ('Ασιμά), and may perhaps be identified also with Tašmet, the paredros of Nebō. The third place in the triad of Kefr Nabō was then filled by Leon = Gennaïos.

For the meaning of ἐπιμεληταί given here, see *Transactions of the Am. Philol. Ass.*, Vol. XLIII (1912), p. 121 f.

M. Chapot understands λευκοῦργοι to mean "ceux qui font les enduits", and refers to *C. I. G.* 2749, l. 5. Certainly the word might have the meaning of *plasterers, whiteners*. But in this country, where the rock upon which every house stood was a fine-grained white lime-stone, which the ancient inhabitants seem to have cut with the greatest ease and used with the greatest freedom even for the smallest and simplest buildings — indeed every cellar was a quarry and furnished the best of building material — it has seemed to me that this word must mean *white-stone workers*, and this opinion I find is shared by Professor Crönert, *Class. R.* xvii (1903), p. 197: "Nomine λευκοῦργός is significatur, qui opera marmoris (λευκοῦ λίθου) conficit". See also H. van Herwerden, *Lexicon Gr. Suppl.*, 2nd ed., 1910, p. 883.

I believe M. Chapot is also in error in his interpretation of ΗΝΗCΘΗ. Dometianos did not compose the inscription: on the contrary, as it seems to me, his name was forgotten when the names of the other τέκτονες, Gaios and Seleukos, were written, or else Dometianos' name was added to the rest after the original inscription was complete. The form is not for ἐμνήσθη, but is subjunctive: see No. 1203 and its commentary.

For the ancient name of Kefr Nabō see the commentary on No. 1175.

1171. HOUSE (?), 308 A. D. On the lintel of a small ancient building, in situ, facing southeast, in the northwestern part of the town. Div. II, B, p. 294: House of polygonal masonry. The inscription is incised along the bottom of the face. Above it is a door-cap, ornamented with a delicate vine from which hang two large, coarse bunches of grapes. The inscription, from Z through Φ, is 1.72 m. long: the lacuna, from ΚΤΙC to Ω is 17 cm. long. The letters are 2½ to 3½ cm. high, most of them being 3 cm. Above ΚΤΙC there are marks on the stone, which may possibly be letters, 5 or 6 in number: they are more like the feathers of an arrow pointing to the right. Possibly they represented a branch. Probably they are merely accidental.

ΖΟΗΑΦΡΟΝΙΟCΕΤΟΥCΣΝΤΗΗΝΟCΠΑΝΗΗΟΥCΚCΕΛΕΥΚΟCΚΤΙC.....?ΩΓΡΑΦ?

The second word looks like ΑΦΡΟΝΙΟC or ΑΦΡΟΔΙΟC; I believe, however, that ΑΦΡΟΝΤΙC is possible. After ΚΤΙC traces of the tips of the following letters appear, suggesting ΤΙC or ΤΗC. The last word may be ΓΡΑΨΕ: the Ω before this seemed to me certain.

Ζοή Ἀφροντίς· ἔτους ςν', μηνὸς Πανήμιου ςκ'. Σέλευκος κτίσ[της (?)]...Ω γραφ...

Life care-free! In the year 356, month Panemos 26th: Seleukos, (the) builder
 (July, 308 A. D.)

The ending of the inscription may be Σέλευκος κτίσ[της, ὁ ζ]ωγράφ[ος: Seleukos, the artist, (was) (the) founder, or Σέλευκος, κτίσ[ας ἐαυτ]ῶ, (ἐ)γράφ[ει: Seleukos, having built for himself, wrote (this). Or the last words may have been ὁ γράφ[ας: compare, for example, Nos. 1203-1205 below.



Door-frame. Inscr. 1171.

1172. HOUSE, 445-6 A. D. On a lintel in situ, over the entrance to what appeared to be a private house, facing west, in the southeast corner of the town. See Div. II, B, p. 296. The first line is 78, the second 35 cm. long, both together are 27 cm. in height. The letters are incised: they vary from 5 to 10 cm. in height, and are very irregularly placed. The reading I believe certain.

ΚΥΡΙΩΝΟΥ ΕΤΟΥΣ ΘΡΥ' ΕΤΕΛΕΙΩΘΗ
 ΕΤΕΛΕΙΩΘΗ

Κυρίωνου· ἔτους θρυ' ἐτελείωθη.

(The house) of Kyrion: in (the) year 494 it was finished. (445-6 A. D.)

The name *Kyrion*¹ is probably a Syriac diminutive of the Greek Κύριος (Κῦρις, Κῦρος), which is the equivalent of the Syriac *Mara* or *Mari*. See the commentary on No. 1119 above. Perhaps, however, it may have to do with the Roman *Curio*. See Pape, *Wörterbuch*, s. v.

1173. BUILDING, 504-5 A. D. On a large lintel, in situ, at the west end of the south wall of a large ancient building in the center of the town. Div. II, B, p. 297: House or Inn. The lintel measures 2.97 m. by 79 cm. The face is without mouldings. It is ornamented with three disks, executed in relief below the surface, 41, 62 and 42 cm. in diameter respectively. The inscription is incised below the disks, beginning 19 cm. from the left end of the stone. The upper line, however, extends across the left half of the lintel only, for the large disk in the center breaks into the space which otherwise might be occupied by this line, and the line is not continued on the right of this disk. The upper line, therefore, is only 1.09 m. in length: the end of it is somewhat mutilated, and there is room between the remains of ΕΥ and the rim of the central disk for an M, or perhaps for ΜΑΤΟC if these letters were a good deal cramped.

¹ Κυρίων, Κυρίωνας or Κυρίωνης: compare Μάρων, Μαρίων, Μαρώνας, etc.

The second line is badly multilated in the center. The first 19 letters occupy a space 94 cm. long, and are followed by a lacuna of 76 cm. The last 28 letters are 1.07 m. in length. The letters are 5 to 6 cm. high, excepting o which measures only 4 cm.: they are well cut; but the strokes are thin.

The first half of the inscription, i. e. the upper line and that part of the lower which is at the left of the central disk, was published by M. Chapot, *B. C. H.* xxvi (1902), p. 181. The second part of the second line was published by M. Uspensky, *Izvestiya of the Russ. Arch. Inst. at Constantinople*, vii (1902), p. 165.



Inscr. 1173.

At the end of the first line, M. Chapot read ΑΓΙΟΥΟΥΙ. In the second part of the second line M. Uspensky read ΑΓΙΟΥ ΖΑΧΕΟΥ.

Δόξα Πατρὶ καὶ Οἰῷ καὶ Ἀγίου<ου> Πνεύματος]. Κύριε φύλαξον τὴν ἐξοδὸν ἡμῶν καὶ τὴν εἰσοδόν. Διὰ εὐχῆς τοῦ ἁγίου Ἀχέου (?). Ἔτους γρψ'.

Glory to Father and Son and Holy Spirit. Lord guard our coming in and (our) going out! In fulfillment of a vow of the holy Acheos (?). In the year 553. (504-5 A. D.)

The spelling and syntax of this inscription is uncommonly incorrect. On the *Gloria Patri* see No. 1140: on the words Κύριε φύλαξον κατλ. see No. 1109 and *A. A. E. S.* iii, 119. I estimated that about 18 letters were lost from the middle of this line, and have restored that number. I am inclined to believe that M. Uspensky's reading of Ζαχέου is correct, and that in my copy I must have omitted the Z by mistake. M. Uspensky notes that St. Zacchaeus, a martyr of Antioch, is mentioned in the *Acta Sanctorum* for July, Vol. iii, p. 32 (July 10th). Probably the genitive Ζαχέου is for a dative, like the Οἰῷ and Ἀγίου Πνεύματος of the first line, and probably a vow to St. Zacchaeus was meant.

1174. THE SAME BUILDING. On the lintel of the easternmost doorway in the south wall of the same building as No. 1173. The lintel measures 3.85 m. by 99 cm. On the face are three rectangular ornamental plates, like disks, but no mouldings. The inscription, 51 cm. long and 11 cm. high, is below the central plate. The letters are incised, in double lines, making a false appearance of relief: they are very badly executed. Copied by Professor Littmann.

ΜΑΡΚΙΑΝΩ. The first two letters are much smaller than the others, and they and the last letter are very uncertain. I satisfied myself, however, comparing the copy with the stone, that Μαρκιανῶ was meant, i. e. *Of* or *For* Markianos.

With this should be compared an inscription reported by M. Chapot as "Sur le claveau inférieur de l'arcade à g.",¹ apparently in the same building. I did not find


¹ *B. C. H.* xxvi (1902), p. 181, No. 25.

this inscription. M. Chapot's text is as follows: + K(ύρι)ε βοήθη τῶν [θε]ύλ[ων σου] τῶν
[.] M[α]ρμ(α)νοῦ καὶ Σεργίου τοῦ α[.] καὶ υἱοῦ αὐτοῦ [.] καὶ K[.]
υἱοῦ αὐτοῦ +.

1175. BRÂD. LINTEL, 207-8 A. D. On the lintel of a doorway in the second



Door-frame and Wall of Polygonal Masonry. Inscr. 1175.



Door-frame bearing Inscr. 1175.

story of a half-ruined building, facing south in the eastern part of the town. Nos. 1175, 1186 and 1187 belong to the same group of buildings. This group is most remarkable in its plan. See Div. II, B, p. 303 f. The lintel itself is large and well cut. It is now very difficult of access, so that an accurate drawing of the inscription could not be made. I believe, however, that the reading given below is reliable.

Upon the center of the lintel is a door-cap, 1.31 m. broad at the bottom. The first line of the inscription is upon the next to the lowest fascia of this door-cap, the fascia being 13 cm. high and the letters $5\frac{1}{2}$ cm. The second and third lines are on the lowest fascia of the cap: this fascia is $13\frac{1}{2}$ cm. high, the letters $4\frac{1}{2}$ cm. Lines 4-7 are carved below the cap, in a space 22 cm. high. These letters also are 4 to $4\frac{1}{2}$ cm. high. The last line projects 9 cm. to the right of the cap. At the beginning of the first and also of the fourth line is a symbol, perhaps 8 or 9 cm. high, somewhat resembling a sun-disk with rays. It seems quite clear that lines 4-7 constitute a paragraph by themselves, and it is quite possible that they were added some time after the rest. I believe that this lintel originally belonged to some building connected in some way with the cult of a pagan god, perhaps that same $\Sigma\eta\mu\epsilon\varsigma$ or $\Sigma\eta\mu\epsilon\varsigma$ mentioned in the

inscription of the oil-mill at Kefr Nabō, No. 1170 above.



Inscr. 1175.

1. Ἀγαθὴ Τύχη. Οὐρβικός,
2. Ἀνδρόνικος καὶ Μάρκος, οἱ Λονγίνου
3. υἱοί, σὺν τέκνοις, ἔκτισαν ἔτους 256.
4. Ἀντώνιος καὶ Σώπατρος, ἀδελφοί, ἔ-
5. κτισαν, οἰκοῦντες ἐν Κάπερ Νάβου, καὶ Κάσ-
6. σανδρος ἀπὸ Ρεζίθα, καὶ Ζεβίνος ἀπὸ Καπρό
7. Μνηστῆ Σώπατρος, ὁ ἐπαξάμενος τὸν λίθον.

With Good Fortune! Ourbikos, Andronikos and Markos, the sons of Longinos, with (their) children, built (this) in (the) year 256.

Antonios and Sopatros, brothers, built, being residents of Kaper Nabou, and Kassandros of Rezitha, and Zebinos of Kapro[...]. May Sopatros be remembered, who put the stone in place. (207-8 A. D.)

This inscription is most interesting because of the ancient place names which it preserves. Two of them are the old Aramaic names, and at least one of these is still in use, namely Κάπερ Νάβου, the modern Kefr Nabō. Professor Butler suggests that the other, Ρεζίθα, may be the modern Zerzita. See Nos. 1170-1174: also *A. A. E. S.* III, p. 123 f., and *B. C. H.* xxvi, p. 180. I believe that ancient Semitic names appear also in the ethnikon Τησουβαρινω, in No. 1161, in the form Καπροβαράδε in *A. A. E. S.* III, 75, and in Καπαράζιζον (Κάπαρ Ἀζίζου) which occurs in an inscription found at Raïfa, north of Shèkh Miskin, and published by M. Fossey in *B. C. H.* xxi (1897), p. 54.

On μνηστῆ see the commentary on No. 1203 below.

1176. GATEWAY, 491 A. D. On the lintel of a gateway which formed the entrance to a courtyard, near a colonnade of piers, about 100 yards south-southeast of the North Church. The rest of the wall has disappeared. The whole lintel is 1.90 by 0.57 m. The inscription is incised on a dovetail plate in relief. In each dovetail is a small disk. The body of the plate is 65 cm. long and 33 cm. high. The letters vary from 3 to 6 cm. in height, most of them, however, being about 5 cm. Copied by Professor Littmann.

+ΑΓΑΘΗΤΥΧΗΑΡΓΥΡ
ΙΟΣΠΕΛΑΓΙΟΥΕΚΤΙΕΝ
ΕΚΘΑΙΜΕΛΙΩΝ ΕΝ
ΜΥΠΕΡΒΕΡΕΤΕΟΥΧΡ
ΟΝΟΙCΙΝΔΙΕΤΟΥΜΦΕΤ
ΟΥCΔΙΑΚΟCΜΑΤΕΧΝΙΤΟΥ

+ Ἀγαθὴ Τύχη. Ἀργύριος Πελαγίου ἔκτισεν ἐκ
θαυμελίων ἐν μηνί Ὑπερβερετεύ, χρόνους ἰνδ. ιε', τοῦ
μυ' ἔτους, διὰ Κοσμά, τεχνίτου.

+ *With good Fortune! Argyrios, (son) of
Pelagios built (this) from the foundations in
(the) month of Hyperbereteos, in (the) times of
indiction 15, of the 540th year, through Kosmas,
architect. (October, 491 A. D.)*

The phrase χρόνους (or χρόνων) ἰνδικτιώνος does not occur elsewhere in the inscriptions published here or in *A. A. E. S.* III: it is found, however, elsewhere, for example in Wad. 1913, 1917, 1965, 2089 and 2477.

Concerning the architect Kosmas, see the commentary on No. 1142 above.

1177. GATEWAY, 496 A. D. On the lintel of a gateway which formed the entrance to a courtyard before a building with a portico, like a private dwelling. See Div. II, B, p. 312 f. The rest of the wall, in which this gateway stood, has disappeared. The whole lintel is 2.20 m. long and 46 cm. high. The lowest fascia of the mouldings, which bears the first line of the inscription, is 1.66 m. long and 6 cm. wide. This first line, however, appears from the sense to have been carved after the others, as an addition to them: consequently I have placed it after the others in the text which accompanies the drawing. The space at the bottom of the lintel, framed by the mouldings, contains the second and third lines, and traces of a fourth. It is 1.48 m. long and, in its present condition, 11 cm. wide. The bottom has been broken and crumbled away, and the space was doubtless somewhat wider originally; but the fourth line must always have been badly cramped. The letters are incised, and are from 3 to 4 cm. high: all appear to be certain. The drawing is by Professor Littmann.



Inscr. 1177.

+ Ἀνέγχε τὸ ἐπίθυρον τοῦτω ἐπὶ Κοσμά τεχνίτου καὶ ἐπὶ Σεργωνα (?) [τοῦ?] νεοκτίστου, τοῦ
δυμ' ἔτους, ἰνδ. δ', μηνὸς Λῶος βί'. Κ(ύρι)ε, βοήθησον καὶ Ῥωμανοῦ (καὶ) Ἰωάννου
(καὶ) Εὐσταθίου (καὶ) Σεργίου τοῦ γράψου (καὶ) Συμεώνου τεχνίτου.

+ *This lintel was put in place under the direction of Kosmas, architect, and under
Sergonas (?) the neoktistos, in the 544th year, indiction 4, month Loös 12th. Lord,
help Also (under?) Romanos and Ioannes and Eustathios, who
wrote (this), and Symeones, architect. (August, 496 A. D.)*

The form ἀνέγχε is, of course, for ἀνηνέχθη, as βοήθησον for βοήθησον, and γράψου for γράψαντος. I suppose that Σεργωνας is a possible name, and that it actually occurs here, although one is tempted to read Σεργίου at the end of the second line in the drawing.

I am inclined to believe, furthermore, that the traces of letters below the third line in the drawing may be the last remains of [Σερ]ω]ν, depending upon βωβήσιον. The names which appear in the first line of the drawing, Πωμανοῦ etc., may depend, of course, upon an ἐπί to be supplied from the context. Or they may depend upon something in the fourth line. In view of the other mistakes in this inscription it is even possible that these names depend upon βωβήσιον, and we should then read: Κ(ύρι)ς βωβήσιον [Σερ]ω]ν καὶ Πωμανοῦ (καὶ) Ἰωάννου κτλ.

Concerning the word νεωκτ[ί]στον see what is said above under No. 1147. It does not seem to me possible in either inscription to connect this word with ἔτους as Professor Dölger suggests.¹ There is no evidence that the era of Boşra was ever used in this northern region of Syria: it does not seem to me possible that it could be used here except perhaps by some immigrant from the South. And certainly this explanation cannot be applied to the present inscription. For, aside from the improbability of so late a date as 544 + 105 = 649 A. D., the month Loös was not the beginning of the year according to any era.

My colleague, Professor Morey, has suggested to me that perhaps the word was a title, denoting primarily a profession or occupation, like νεωκόρος² or τεχνίτης. If that is the case, then a proper name must be read in the ΑΡΧΗ or ΑΡΧΗΤΟΥ of No. 1147, and this is certainly possible.³ Moreover it should be noticed that in both inscriptions the form of the word is ΝΕΩΚΤΙCΤΟΥ, i. e. with ω instead of ο before the κ. I do not believe, however, that the word is derived from νέος = νέος. If it were, it might mean *temple-builder* and then *church-builder*, and so perhaps become an honorary title. But I can find no evidence that it was used either in this sense, or in the sense of *new-builder*, i. e. *renovator* (from νέος = new).

It is of course possible also that there was a proper name Νεόκτιστος; but I do not know any example of such a name elsewhere.

The word νεόκτιστος occurs in the *Wisdom of Solomon*, xi, 19 (18), in the sense of *newly-created*: ἡ νεοκτίστος θυμὸς πλήρης ὕλης ἀγνώστου, *Or unknown beasts full of rage newly-created*. There is also the following statement in the *Thesaurus Ecclesiasticus* of Ioh. Caspar Suicerus (Schwyzer), edition of 1728: Νεόκτιστος proprie est, interprete Hesychio, νεοκαθάρτος, ἡ νεωστὶ κατεσκευασμένος, *recens aedificatus vel recens conditus*. Deinde improprie notat νεοφύτιστον, recens baptizatum, apud Nazianzenum, Orat. X, p. 169." The passage referred to may be found in Migne, *Patrol. Graec.*, Vol. xxxv, p. 773 = Gregory of Nazianzus, Orat. vii, c. 15: . . . καὶ τῆς νεοκτίστου ψυχῆς, ἣν τὸ Πνεῦμα δι' ὕδατος ἀνέμειρξε, ἅξια τὰ γένη καρπούμενος: *enjoying honors worthy of his NEW-CREATED soul, which the Spirit through water formed anew*. I believe this is the meaning of the word in both of these inscriptions. If so it is analogous to νεόφυτος, νεοφύτιστος, ἀνακατησθείς, etc.⁴ I do not mean that it was distinctly an ecclesiastical term, implying necessarily either baptism or confirmation, but that it signified simply that the person so described was a Christian, one born again.

¹ *Das Fischsymbol*, I, p. 251 f. Professor Dölger also quotes a card from Dr. Anton Baumstark in which the latter regards the connection of νεοκτίστου with ἔτους in No. 1147 as "evident richtig".

² Cf. *Acts* xix, 35: this word later came to mean *sacristan*.

³ A name Ἀρχης occurs in *Inscr. Graecae* XII, viii, No. 331 l. 6 (from Thasos). An Ἀρχίτης appears in *I. G. V*, 1, No. 211, l. 45 (from Laconia), and Ἀρχιτος in *Greek Papyri in the Brit. Mus.* II, p. 131, l. 18.

⁴ See Dölger, "Die Firmung in den Denkmälern des christlichen Altertums", in *Röm. Quartalschrift* xix (1905), p. 1 ff.

1178. NORTH CHURCH, 561 A. D. On the lintel of a doorway in the south side of the prothesis on the south side of the apse of the North Church, in the same wall as No. 1180. Div. II, B, p. 308 f.



Lintel bearing Inscr. 1178.

The lintel is 2.53 m. long and 58 cm. high. It has no mouldings, but in the center a complicated disk, 53 cm. in diameter, in relief below the surface. The inscription, in two lines, is incised, part on each side of the disk. The first part of the first line is 51 cm. long, the second part 76½ cm. long including the lacuna: this lacuna, from the end of ε to the beginning of Η is 55 cm. in length. The first part of the second line is 48, the second part 87 cm. in

length. The letters are from 4½ to 7, most of them 5 cm. high.

+ ANHNΓXΘ disk ΕΙ ΟΝΗΘΩ
ΤΟΥΠΕΡΘΥΡ/ Η ΜΓΟ Π/ΑΙΝΔΙΤΙΧΙΧΕΤΥC

+ Ἀνὴν(ε)χθε [καὶ ἐπ'ἀχθη] (σὺν) Θ(ε)ῶ τὸ ὑπέρθυρον, μὴ(νὸς) Γο[ρ]π(ναίου) α', ἐνθ. ε', τοῦ
εἴ' ἔτους.

+ This lintel was brought and put in place, with the help of God, month Gorpaios 1st, indiction 10, of the 610th year. (September, 561 A. D.)

Compare ἀνένχει τὸ ἐπίθυρον τοῦτω, in No. 1177; ὁ ἐπαξάμενος τὸν λίθον, in No. 1175; ἀνῆλθεν τὸ προκείμενον ὑπέρθυρον, in No. 906; ἀπετέθη (for ἀνετέθη?) δὲ σὺν Θ(ε)ῶ τὸ ὑπέρθυρον, in No. 915.

This inscription also shows that here, at this period, the year began in September: see the commentary on No. 1108.

1179. NORTH CHURCH. On the keystone of the nave-arch, at the east end of the south side of the nave, adjoining the apse, of the North Church. The upper right-hand corner of the stone has been cut off, so that from two to four letters have been lost. The letters are incised, and appear to be 6 or 8 cm. high. Copied by Professor Littmann.

+ KVPICEB
IΩANNOV
MAΛXION

+ Κύριε βοήθει Ἰωάννου Μαλχίου[ς].

+ Lord help Ioannes, (son) of Malchion!

On the names Μαλχίων, Χαλβίων etc., see A. A. E. S. iv, Syr. 4 and 5, and commentary.

1180. NORTH CHURCH. On the lintel of the western door in the south side of the "North Church", in the east center of the town, perhaps 100 yards north of the "Cathedral". The inscription is incised upon the face of the lintel, above the mouldings. This space was originally 2.50 m. long; but about 20 cm. have been broken off from the left end. The inscription begins 2 cm. from this break, and is 2.21 m. long, ending 7 cm. from the end of the mouldings. The space is 10 cm. high, the letters $5\frac{1}{2}$ to 6 cm. All the letters are perfectly clear and legible: the letters AM of ἀμήν are executed in double lines, giving the appearance of relief.



Doorway of a Church. Inscr. 1180.

+ ΚΕΒΟΗΘΙΓΕΩΓΙΟΥΥΙΟΥΣΕΡΓΙ-
ΟΥΖΟΚΟΤΑΕΥΤΥΛΙΟΥΑΜΗΝ +

+ Κ(ύρι)ε βοήθε Γεω(ρ)γίου, υἱοῦ Σερ-
γίου (και?) Ζωκота Εὐτυ(χ)ίου. Ἀμήν. +

+ Lord help Georgios, son of Sergios, (and?) Zokotas, (son) of Eutychios! Amen. +

I suppose that Γεωργίου and υἱοῦ are for Γεωργίου and υἱῶ; but I do not feel sure that και should be supplied in this inscription.

1181. DOORWAY. On the lintel of a doorway within a small vestibule, about 30 yards north-northeast of the east end of the North Church. The whole lintel is about 2.60 m. long, and 73 cm. high. It is ornamented by a trapezoidal door-cap with rather elaborate mouldings, 1.73 m. long at the top, 1.56 m. at the bottom, and 55 cm. high. The inscription is on the next to the lowest fascia of the cap. It is incised, in letters 5 cm. high. It begins at the left end of the fascia, and was never finished. Copied by Professor Littmann.

+ ΤΟΥΤΟΝ

+ Τὸ πᾶν ν[ικᾷ].

This (sign, i. e. the cross) conquers.

1182. CHURCH. On the keystone of an arch near the east end of the north wall of the "Cathedral" and connecting the north aisle with a small chapel. Div. II, B, p. 306. The remains of a moulded course, which may have run above this arch, were found upon the ground; but nothing now remains in situ above the arch. None of the pieces of the moulded course mentioned show traces of an inscription; but I think that the first part of the inscription must have been above the arch. At least two

courses of plain masonry are required above the arch to bring the moulded course in line with the rest of the cornice. The inscription faces towards the church.

The first two words are at the top of the stone. In the center of the block there seems to have been some kind of relief, now weathered off. The last word is at the bottom of the stone, the last two letters running over on the voussoir next to the key-stone on the right. The letters are about $5\frac{1}{2}$ cm. high, and are handsome in form and well cut.


ΕΖΙΔΙΩΝ

..... ἐξ ἰδίων ἐποίησαν

ΕΠΟΙΗCΑΝ

Made at their own expense.

1183. FRAGMENT, lying upon the ground, near the northwest corner of the "Cathedral", outside of the building. It is $38\frac{1}{2}$ cm. long, and 10 cm. high. The letters are incised, and are handsome and well cut: they are $6\frac{1}{2}$ cm. high. Copied by Professor Littmann.



Inscr. 1183.

The letter before ΟΥ is certainly Ι. Before that was Ρ or Β. Before that again only the very top of a hasta remains, quite close to the letter which follows: it may have been Ι or Η, but may also have been Ή or Ν, if the letters were of this form. The last letter of all, of which only a small trace remains, may have been either Ε or Ο: a vowel seems necessary. Probably this was: συμ]βίου Β].: of his (or her) wife (or husband), Β.....

1184. LINTEL, on its jambs, facing south, about 50 yards east of the "Cathedral" and very near No. 1176. The building to which this doorway belonged has disappeared. In the center is a rectangular plate in relief, 92 by 27 cm. The first line of the inscription is incised above this plate. It is 65 cm. long, and the letters 7 to 8 cm. high. The other five lines are incised upon the plate, and are so badly weathered that I was not able to read them in the time at my disposal. I think that perhaps they could be read; but I do not believe that their contents would prove to be of great importance.

ΔΙΑ ΑΡΓΥΡΙΟΥ
ΥΒΙΕΒΕΟCΚΑΙCΜ ΠΙΕΤΟΕΑ ΟΥΚΑΙ
ΠΟΙΛΑΓΙΟΗΤΗΝ ΝΟΔΑΥΑΗΟΝΕΝΤΡ
ΝΙΚΑΙΤCΕΛΙΟΔΗ

ΥΠΕ
ΤΟΥ

Σωτήρ. The third line, at the beginning, suggests τὸ Ἅγιον Πνεῦμα.

The first line is clear: διὰ Ἀργυρίου: through Argyrios. An Argyrios, son of Pelagios, is mentioned in an inscription found close by, No. 1176, dated 491 A. D.

The second line suggests Κύριε Θεὸς πατήρ, and perhaps, after this,

1185. LINTEL, fallen from its jambs, about 50 yards southeast of the "Cathedral". On the lintel is a door-cap, on each side of which is a large wreath, with a bow-knot below and a rosette within the wreath. The inscription is incised, in broad strokes, on the next to the lowest fascia of the door-cap. This fascia is 11 cm. broad. The inscription begins 3 cm. from the left end of the fascia, is 1.50 m. long, and ends $6\frac{1}{2}$ cm. from the right end. The letters are 6 cm. high. They are badly weathered;

but all seemed certain except the fifth, which may be Σ or Γ . Between ω N and $\rho \omega$ there is room for one large or two small letters.

ΥΙΕΙΕΝΩΝ ΡΩΜΕΤΑΤΟΥΔΙΚΟΥΕΩΥ

The first word is clearly $\Upsilon(\gamma)\epsilon\acute{\iota}\epsilon\nu\omega\nu$ for $\Upsilon\mu\alpha\acute{\iota}\nu\omega\nu$. The second is perhaps $\epsilon\rho\omega$: compare I Sam. xxv, 6: *Καὶ ἐρεῖτε τὰδε· Εἰς ὥρας καὶ σὺ ὕμναίνων· ὁ οἶκός σου καὶ πάντα τὰ σὰ ὕμναίνοντα.* If so the inscription may be translated: *Be healthful, I will say, with thy house.* Such a use of $\sigma\acute{\alpha}\kappa\omicron\varsigma$ is frequent in these inscriptions: compare, for example, Nos. 1186 and 977; also *A. A. E. S.* III, 223.

With $\Upsilon\mu\alpha\acute{\iota}\nu\omega$, in salutations of any sort, some form of $\chiαῖ\rho\omega$ might be expected.¹ And $[\chi\acute{\epsilon}]\rho\omega$ may be read here. But an imperative in the second person seems certainly implied by the $\sigma\omega$ at the end of the inscription. Perhaps then $\Upsilon(\gamma)\epsilon\acute{\iota}\nu\omega\nu$ $[\chi\acute{\epsilon}]\rho\omega(\nu)$ (sc. $\epsilon\sigma\theta\iota$) is possible.²

The verb $\rho\acute{o}\nu\nu\mu\iota$ is also very common in salutations, with or without $\chiαῖ\rho\omega$, $\Upsilon\mu\alpha\acute{\iota}\nu\omega$ etc., especially in the form $\epsilon\acute{\rho}\rho\omega\sigma\sigma\omicron$ or $\epsilon\acute{\rho}\rho\omega\sigma\theta\epsilon$. Compare, for example, the epitaph in *C. I. G.* II, 3706, where the dead seems to be addressing the passer-by: *Χαῖρε, παροδεῖτα. ἔργων καὶ ἔρρῳ σο, ὕμνῳ ἰάνε, εὐδίδει.* So also in letters this verb occurs frequently in formulae of address or of leave-taking. Perhaps then, if it may be assumed that the carver of the present inscription omitted a syllable by mistake, the following may be read: $\Upsilon(\gamma)\epsilon\acute{\iota}\nu\omega\nu$ $[\epsilon\acute{\rho}\rho\omega\sigma\sigma\omicron]$, $\mu\epsilon\tau\grave{\alpha}$ $\tau\omega\upsilon$ $\sigma\acute{\alpha}\kappa\omicron\varsigma$ $\sigma\omicron\upsilon$: *Be healthful and strong, with thine house, i. e. Good luck to thee and thine!* This reading certainly gives the most satisfactory sense.

1186. KEY-STONE of an arch, about 30 yards southwest of No. 1175. Above the inscription is a branch of some plant, with two flowers, and above this a disk containing a six-arm cross, all in relief below the surface. *Div. II, B, p. 304.* The inscription, in letters 2 to 3 cm. high, is incised at the bottom of the face of the stone. The whole inscription occupies a space 24 cm. broad and 13 cm. high: the letters are badly weathered and very dim.



Arch with ornamented Key-stone. Inscr. 1186.

¹ Compare, for example, the letter of Antiochos to the Jews, in II Macc. IX, 19: *Ταῖς χρησταῖς Ἰουδαίοις ταῖς πολῖταις πολλὰ χαῖρειν καὶ ὑγιαίνειν καὶ εὖ πράττειν βασιλεὺς Ἀντίοχος καὶ στρατηγός Ἑρμώης, καὶ τὰ τέκνα.*

² My field notes state that the very faint lines before $\rho \omega$ suggest χ more than any other letter. But I do not believe that $[\chi\acute{\epsilon}]\rho\omega$ is possible here. Compare, however, $\epsilon\acute{\iota}\delta' \Upsilon\mu\alpha\acute{\iota}\nuοντι$ $\chi\rho\acute{o}\mu\epsilon\tau\omicron\varsigma$ $\epsilon\alpha\nu\tau\acute{\theta}$, in Plutarch, *Nicias*, c. 17, or $\Upsilon\tau\iota$ $\chi\rho\acute{\theta}\omicron$ $\sigma\alpha\nu\tau\acute{\theta}$, in Plato's *Crito*, p. 45 B.

ΕΙCΘΕ ΟCΚΑΙ
ΟΧΡΑΥΤ ΟΥΟΒ
ΟΗΘΩΝΒΕΘΔΟ
ΤΩΚΕΤΟΥΟΙΚΟΥ

Εἰς Θεὸς καὶ ὁ Χρ(ιστός) αὐτοῦ, ὁ βοηθῶν Θεοδότω καὶ τοῦ οἴκου.

*One God and his Christ who aideth Theodotos
and (his) house.*

Compare the preceding inscription.

1187. LINTEL of an interior doorway, in a curious building consisting of three long narrow rooms, on the east side of the same court as No. 1175. This doorway is between the southern and the middle rooms. See Div. II, B, p. 303 ff. On the lintel is a door-cap, on one side of which is a large cross, and on the other a disk containing a cross. The inscription is incised on the uppermost fascia of the door-cap. This fascia measures 1.21 m. by 9 cm. The letters are $5\frac{1}{2}$ cm. high: they are well drawn, and although they are formed by shallow lines most of them are still perfectly legible. The right end of the cap is slightly broken, but in such a way that I think no letters have been lost from it. The inscription, however, may have been continued on the face of the lintel, at the right of the cap, where the stone is now badly weathered.

ΑΝΕΝΕΧΘΗΤΟΥΠΕΡΒΥΡΟΝΕΠΙΤΟΥΕΠΙC

Ἀνεῆχθη τὸ ὑπέρθυρον ἐπὶ τοῦ ἐπισκόπου

This lintel was set up under the bishop

See No. 1178 and its commentary.

1188. HOUSE(?). On a plain jamb of a doorway in a plain house, in the southeast corner of the town. The width of the jamb is 45 cm. The letters are 7 to 8 cm. high, and executed in very dim, broad lines. Below the inscription are crosses and some other ornament, perhaps two large leaves, all in broad, incised lines.

ΙΧΘΥC
ΟΗΟΝΟΓ

ΙΧΘΥC, ὁ Μωυσ(ής).

J(esus) Ch(rist) (the) S(on) of G(od) (our) S(avior), the Only-Begotten.

On the subject of the fish-symbol or the acrostic ΙΧΘΥC see the exceedingly interesting book by Professor Franz Jos. Dölger: *ΙΧΘΥC Das Fischsymbol in früh-christlicher Zeit*, Freiburg i/B. and Rom, Vol. I, 1910. Also the valuable contributions of Professor C. R. Morey, "The Origin of the Fish-Symbol", in the *Princeton Theological Review*, VIII (1910), pp. 93 ff., IX, p. 268 ff., X, p. 278 ff. Also the admirable reviews of these works by P. Louis Jalabert in the *Mélanges de la Faculté Orient. de Beyrouth*, V, 1 (1911), p. XIX-XXX, and the *Revue de Philologie*, XXXV (1911), p. 118-122. Examples of this formula in Syrian inscriptions will be found in the Index of Abbreviations and Symbols at the end of this volume, and also in the *A. A. E. S.* III and in Waddington. The examples which can be dated definitely belong to the years 349-50, 368-9, 432, 439 and 500 A. D.¹ The oldest of all may be that from Shaḡḡā,

¹ *P. A. E. S.* 1206, 1120, 971, *A. A. E. S.* 284, and *P. A. E. S.* 1147.

published by Waddington under No. 2145; but unfortunately the date of this inscription is uncertain, because the "era of the city" cannot be determined.¹ If the era of Shaḥkâ really began in 61–2 A. D., the date of this inscription would be 132–3 A. D. However this may be, many believe that the Abercius Inscription, assigned by some scholars to the end of the second century, contains a reference to ΙΧΘΥΣ as a symbol of Christ.² One of the most important inscriptions to be considered in any discussion of this matter is No. 1150 above, containing the formula in initials followed by the words themselves written out in full. Another is No. 971, which contains the words: Ἀνηρέθη τὸ κρίσμα Σιδωνίου διὰ ΙΧΘΥΣ.

1189. BURDJ IL-KÂS. LINTEL, 407 A. D. On a lintel, in situ, facing south, in the southern part of the town. Only the doorway and a small part of the adjoining wall are original: the rest has been rebuilt in comparatively recent times. Div. II, B, p. 315. The lintel is ornamented with a trapezoidal door-cap. The inscription is incised on the lowest two fasciae of the cap: these fasciae are $8\frac{1}{2}$ cm. wide, and respectively 1.31 and 1.27 m. long. Above the Greek there is an inscription in Syriac,³ which corresponds with the Greek text only in part. The Greek letters are $3\frac{1}{2}$ to $5\frac{1}{2}$ cm. high. Copied by Professor Littmann.

ΕΙCΘΕΟCΚΑΙΟΧΑΥΤΟΒΟΗΘΩΝ
ΠΑCΙΕΤΟΥCΕΝΥΗΠΑΝΕΗCΖΚ

Εἰς Θεὸς καὶ ὁ Χ(ριστὸς) αὐτ(οῦ) ὁ βοηθῶν πᾶσι.
Ἐτους εἰς, μηνὸς Πανεμ(ου) ζ΄.

One God and his Christ who aideth all! In the year 455, month Panemos 27th. (July, 407)

See the commentary on Nos. 1168 and 1126 above.

1190. LINTEL, 493 A. D. On three fragments of a lintel, found together in the southern part of the town. Fragment A, the left end, is in situ upon the left jamb of the doorway: it is 76 cm. long. The other fragments, B and C, were found close by: they are 51 and 76 cm. long respectively. The inscribed band is 7 cm. wide, and the letters, which are incised, are from $3\frac{1}{2}$ to 5 cm. high. The name ΚΟCΗΑ is written perpendicularly on the return of the inscribed moulding in line with the jamb. It is 24 cm. long, and at the end the surface of the band has been destroyed for about 12 cm. Thus there may have been one or more words after Κοσμᾶ, two or three letters of which were on the lintel, in the mutilated space, while the rest were continued along the jamb. The last name, ΛΕΩΝΙΔΟΥ, is also written perpendicularly, on the splayed edge of the inscribed band below, i. e. at the left of, ΚΟCΗΑ. After ΛΕΩΝΙΔΟΥ there appears to be another letter, like a small C, the ends of which reach the very bottom edge of the lintel. Professor Littmann, who copied the inscription, was not sure whether there was really a letter here or only an accidental mark on the stone: it may, however, have been C or O, and a part of some word continued on the first block of the jamb.

¹ See the commentary on A. A. E. S. III, 377.

² See the article by H. Leclercq in the *Dictionnaire d'Archéologie Chrétienne*, I (1907), Col. 66–87.

³ P. A. E. S. Div. IV, B, Syr. 53.



Inscr. 1190.

✠ Ἔτους αμφ', μηνὸς Ἀρτ[ε]μισίου 10', ἐπὶ Ρ[αβ]ουλα, Βαραψα, Βαδρα, Κοσμᾶ, Λεωνίδου.

✠ In the year 541, month Artemisios 10th, under Raboulas, Barapsas, Badras, Kosmas, Leonidas. (May, 493 A. D.)

Doubtless the persons mentioned here constituted a board of officials, or a commission of some sort. Perhaps they were ἐπιμεληταί, and perhaps then this word should be restored after Λεωνίδου or after Κοσμᾶ. Perhaps [ἐπιμελητῶν] might be read after Κοσμᾶ, and οἰκοδόμου after Λεωνίδου.

1191. KALÔTĀ. LINTEL, 387 A. D. On a large lintel lying upon the ground, immediately southwest of a large and well preserved house with a part of its portico, roof slabs and all, intact, in the southeast corner of the town, about 50 yards southeast of the church. I do not think, however, that the inscribed lintel had any connection with this particular house: if I remember correctly, all the lintels of the house in question were in place. In the center of the lintel is a door-cap, on which is a disk containing a cross in relief, 38 cm. in diameter. The inscription is incised on the lowest two bands of the cap. The first of these bands is $10\frac{1}{2}$ cm. wide, the second 10 cm. The whole cap is about 1.82 m. broad. The first part of the second line is 48 cm. long. The letters are 7 to 8 cm. high.

ΕΤΟΥΕΛΥΜΛ
ΖΟΗΥΓΙΑ

disk

ΧΡΙΣΤΕΒΟΗΘΗCON
ANTIOXΩΚΕΘΕΟΦΙΛ

Ἔτου(ς) ελϛ', μηνὸς Λ(ί)ου. Ζοή. Ὑγία. Χριστέ, βοήθησον Ἀντίχῳ καὶ Θεοφίλ(ῳ).

In the year 435, month Loös. Life! Health! Christ, help Antiochos and Theophilos (or Theophila)! (August, 387 A. D.)

1192. CHURCH, 492 A. D. Lintel of the west portal of the church. Div. II, B, p. 315 f. The inscription is incised on the topmost band of the lintel: this band measures 2.19 m. by $7\frac{1}{2}$ cm. The letters, 4 to 5 cm. high, are formed by thin lines, some of which are still deep and clear, while others are badly preserved.

+ ΘΕΟΣ/ΟΧΡΙΣΤΟΣΑΥΤΟΥ/Τ ΝΤΙΕΤΑΦΗΗΥΠΕΡΒΕΡΕΤΕΟΥΗΘΑΗΦ +

+ [Εἰς] Θεὸς (καὶ) ὁ Χριστὸς αὐτοῦ / Τ... ΝΤΙΕΤΑΦΗ μηνὸς Ὑπερβερετέου, (ἔτ)(ους) αμφ'. +

+ One God and his Christ in the month Hyperbereteos, of (the) year 541. + (October, 492 A. D.)

In the lacuna between T and NTI there is space for from two to four letters. Traces of letters still visible there certainly suggest $\omega\theta$. Moreover I examined this lintel very carefully after my copy was made, and believe that ΕΤΑΦΗ is really on the stone. If so, then it appears that we must read [Εἰς] Θεὸς (καὶ) ὁ Χριστὸς αὐτοῦ τῷ ὄντι ἐτάφη, i. e. *One God and his Christ: in very truth he was buried*, words which recall to our minds I Cor. xv, 4, or the "Apostles' Creed": *Was crucified, dead and buried*. This seems so strange a reading here, however, that I have not ventured to insert it in the text. The sign after αὐτοῦ, ς, presents no difficulty, for this is used not only as a sign of abbreviation or for καὶ (*and*), but also to mark a pause in the text, like a punctuation mark.¹ On the other hand, aside from the strangeness of the reading under discussion, we should expect here τὸ ὑπέρθερον ἀνηρέχθη, or some such phrase.²

1193. KAL'AT KĀLŌTĀ. FROM A TEMPLE. On a block now built into the south wall of the church, immediately east of the eastern doorway in this wall. Div. II, B, p. 319 f. The inscription is on the outer, i. e. the south face of the wall. The block contains the right half of a dovetail plate, the left half of which must have been upon a stone adjoining the present one in its original position. Probably these two blocks formed an over-lintel. The dovetail of the plate appears in relief above the surface of the right half of the block: the plate itself completely fills the left half of the block, extending to the edge at the top, bottom and left side. The whole stone measures 1.84 m. by 56 $\frac{1}{2}$ cm.: that part of the plate which is upon it is 89 cm. and the dovetail 27 $\frac{1}{2}$ cm. in length. The inscription completely fills this plate. The letters are incised and beautifully drawn and cut: they are 6 to 7 cm. high. The fifth line shows at the beginning the second hasta of the letter N which preceded the first extant letter (which is also N): the other lines show no trace of any letters preceding.



Inscribed Block built into a Church Wall. Inscr. 1193.



Inscr. 1193.

1. Σεμίω (?) καὶ Συμβ|αιτύλω, Θεοῖς πα-
2. τράσις,|μ(ῖ)αιος, Ἀφροδισίου,
3.|ρας, τῆς γυναικὸς αὐ-
4. τοῦ, ἐκ τῶν ἰδίων, μετὰ τὸ ἀπαρτ[-
5. τὸν] ναὸν καὶ τὸ χρυσοῦν ξόανον.

To Seimios (?) and Symbaitylos, ancestral gods, aios, son of Aphrodisios, with ra, his wife, at their own expense, after the (restored?) the temple and the golden image.

¹ See for example No. 1088 = A. A. E. S. III, 62 and the commentary in the earlier publication.

² Compare Nos. 1177, 1178, 1187.

Concerning these gods, see the commentary on No. 1170 above. I judge from what remains of this inscription that a temple of Seimios and his consort had been injured in some way, probably by an earth-quake, and was rebuilt or repaired by the son of Aphrodisios and his wife, of whose names only the last three or four letters have been preserved. Parts of the walls of two pagan buildings are incorporated in the church structure.

1194. TOMB. On the lintel of a built tomb, in the form of a cube, originally surmounted by a dome, south of the church and facing north. The stone is 1.58 m. long, and 49 cm. high. In the center is a circle enclosing a simple cross, 30 cm. in diameter, executed in broad, deep lines. The inscription is at the right of this disk, and nearer the top than the bottom of the stone. It is $34\frac{1}{2}$ cm. long. The letters, 6 cm. high, are incised, the lines being deep and clear but thin.

ΜΑΡΙΑΜΗ

Μαρίαμη

Mariamē.

I am not sure, however, that the last two letters are not an abbreviation: if so we should read Μαρία μ(νηστὶ)ῆ: *May Maria be remembered* (i. e. before the Lord)! Letters of this type were not common in this region before the sixth century: probably the tomb itself is not much if at all older than the reign of Justinian I.

1195. Near BĀNASTŪR. BOUNDARY STONE(?). On a stone like a boundary stele, fifteen minutes walk from Bānastūr, on the road to Surḡanyā. The stone is broken and very badly weathered. There seem to have been in all 15 lines, of 13 or 14 letters each. The last word is ΟΡΟΣ, i. e. ὄρος, *boundary*; but I was unable to decipher any more, and doubt if much more can be read. I think the inscription may have begun with the phrase κατὰ μέγεθος, like A. A. E. S. III, No. 75.

1. ΚΑΕ__ΑΟΙC

2. ΙΑΚΚΕ__Η_____

3. _ΝΑΔΟ_CΤΟC

4. ΔΙΟ_____ΛΝΟ_____



House-front with a Porch. Inscr. 1196.

1196. SURḠANYĀ. HOUSE(?), 406-7 A. D. On a lintel, probably in its original place, with a porch before it, as if this were the entrance to a private house: most of the building itself has disappeared. The lintel has a door-cap, along the top of which is a row of small disks: a larger disk ornaments the face of the lintel at each side of the cap. The inscription is below the door-cap: it is upside down, and begins at the right end of the stone. This door-cap shows conclusively that the lintel is in its original position. The in-

scription, then, was carved upside down. Compare No. 1167. The whole inscription is 1.38 m. long: it is incised in fairly good letters, all of which are still clear and certain. The first eight, however, and the last three are from 3 to 5 cm. high, while the rest are 7 cm. high.

ΗΤΟΥCΕΝΥΕΙCΘΕΟCΚΕΟΧΡΙCΤΟC

Ἦτους εν'. Εἰς Θεὸς καὶ ὁ Χριστός.

In (the) year 455. One God and his Christ. (406-7 A. D.)

See the commentary on No. 1126 above.

1197. LINTEL. On a large lintel, lying upon the ground, about 100 feet west of a single arch standing alone near the center of the town. The lintel is 2.45 m.



Ruins of Surkanyā.

long and 53 cm. high. The block is without mouldings, and its face is now very rough. The inscription, 55 cm. long, is placed about midway between the ends of the lintel, but near the top of the face. The letters are from 14 to 16 cm. high, and are executed in very deep lines, $1\frac{1}{2}$ cm. broad. There is nothing else upon the stone.

KAICY

Καὶ σὺ (χαῖρε or ὕμνε): *Thou too (rejoice)!*

I believe that the formula καὶ σὺ is quite distinct from the καὶ σοί, sc. τὰ διπλῶ, which is discussed above under Nos. 1073, 1125 etc. Of course καὶ σὺ and καὶ σοί were pronounced alike at this time, and possibly in the present inscription σὺ may be a mistake for σοί. But I think not: the formula of which καὶ σὺ seems to me to be a part was found in full by M. Kontoleon in an inscription at Smyrna: Λαμπάδης Παρθένου Πακτωλίου διακόνου χαῖρε· χαῖρε καὶ σὺ.¹ See what I have said on this subject in the commentary on *A. A. E. S.* III, No. 42, and compare also No. 1127 above.

On the other hand, the other examples of καὶ σὺ known to me are upon tombs, while from the fact that the present lintel was found near the center of the town it appears probable that it belonged to a dwelling house. I see nothing inappropriate to a dwelling, however, in the salutation καὶ σὺ χαῖρε.

¹ *B. C. H.* x (1886), p. 453, No. 1.

1198. HOUSE (?). On a lintel lying upon the ground in the ruins of what appeared to be a simple private house, about 100 yards north of the South Church. In the center is a raised rectangular plate, 23 cm. broad, which may have contained a cross in relief. The letters are on either side of this plate: they are 12 cm. high, incised in deep lines. I found no trace of any other letters.

ΕΙΘ square ΕΘ

Εἰς Θεός. *One God.*

A discussion of this formula will be found in *A. A. E. S.* III, p. 51 f., No. 25 commentary, and under No. 1126 above: see also No. 1168 f.

1199. FĀFIRTĪN. CHURCH, 372 A. D. On a lintel, originally over the easternmost door in the south wall of the church. All of the church has been destroyed except the apse. Div. II, B, p. 327. The lintel is 2.29 m. long and 59 cm. high. In the center is an incised circle enclosing a cross, 35 cm. in diameter. Both the upper corners of the stone have been cut away, so that some letters have been lost from the end of the third line, and probably from the ends of the first and second lines also. The letters are incised: they are irregular in size, most of them being 7 or 8 cm. high. The whole inscription is almost hopelessly weathered, and the reading is very uncertain.



Inscr. 1199.

Εὐ[θ]ῆ(α) ζωῆς ὁδὸς (ἔ)σ[τ]ιν. Ἐπὶ Ἀν[τιόχ]ου τοῦ (ἐπ)ισκόπου. Μάρ[τις] περιοδ[ευτής]. Εἰς Θεός
καὶ ὁ Χριστὸς αὐτοῦ, ὁ βοηθῶν. Ἐτους κ', μηνὸς Λό[ος].

*Straight is the way of life (?). Under Antiochos (?) the bishop (?). Maris, perio-
deutes. One God and his Christ, that giveth aid. In (the) year 420, month Loös.
(August, 372 A. D.)*

The first line of this inscription has a strong biblical flavor. Compare, for example, *Hosea* XIV, 10: Εὐθεῖαι αἱ ὁδοὶ τοῦ Κυρίου, καὶ δικαιοὶ παρέσονται ἐν αὐταῖς. *Proverbs* XV, 24: Ὅδοι ζωῆς διανοήματα συνετοῦ. *Proverbs* XX, 14: Καὶ εὐθεῖα ἡ ὁδὸς αὐτοῦ. *Acts* XIII, 10: Οὐ πάσῃ διατρέπων τὰς ὁδοὺς Κυρίου τὰς εὐθείας. See also *Psalms* CVI, 7 and CXLII, 10, and *Acts* II, 28 where *Psalms* XV, 11 is quoted. Something similar to the present inscription is perhaps contained in the perflexing inscription under No. 1208.

With regard to *perioδευτής* see No. 1118 above.

1200. BĀZĪHER. HOUSE (?). Lintel in the second story of a building, probably a private house, facing south, in the west center of the town. The inscription, in broad, deep strokes, is incised below a door-cap. The whole inscription is 1.62 m. long, the letters 5 to 5 1/2 high.


ΕΙΣΘΕΟCΟΒΟΗΘΩΝΠΑCΙΖΟΗΥΓΙΑ

Εἰς Θεὸς ὁ βοηθῶν πᾶσι. Ζωή. Ὑγία.

One God who helpeth all. Life! Health!

Compare Nos. 1126, 1168 etc.

1201. BĀTŪTĀ. COLONNADE, 363 (or 563) A. D. On the architrave of the second story of a colonnade or portico, facing south, about the center of the town. See Div. II, B, p. 332. The colonnade is formed by rectangular piers in the lower story, and columns in the upper. The sections of the architrave are about 2 m. long. The first from the east end contains five or six signs, which look like letters, but which neither Professor Littmann nor I could read. The second, third, fourth and fifth sections bear the inscription, upon a fascia 12 cm. wide. The letters are in a single line, except the last ten, which are in two lines: these ten are from 3 to 4 cm. high, the others 6 to 8 cm. Copied by Professor Littmann.



Colonnades at Bātūtā. Inscr. 1201.

Sec. 2. ΕΙCΘΕΟCΚΑΙΟΧΡΙCΤΟCΑΝΤΟΝΟΒΟ

Sec. 3. ΗΘΩΝΗΑΡΙΑΝΩΚΑΙΤΑΤΕΚΝΑΑΝΤΟΝ

Sec. 4. +ΒΟΗΘΙΗΑΡΙΑΔΗΝΚΕCΑΔΚΩΝΑΝΤΟΝC

Sec. 5. ΑΡΧΙΤΕΚΤΟΝΑCΕΤΕΛΙΟΘΗΕΝΗΗΝΙΖΑΝΔΙΚΟΝΤΟΝΑΙΥ
ΕΤΟC

Εἰς Θεὸς καὶ ὁ Χριστὸς αὐτοῦ, ὁ βοηθῶν Μαριανῶ καὶ τὰ τέκνα αὐτοῦ.
+ Βοήθει Μαριάδην καὶ Σακκωναν, τοὺς ἀρχιτέκτονας.
Ἐτετέλεθη ἐν μηνὶ Ξανδικῷ, τοῦ αὐτοῦ (?) ἔτους.


*One God and his Christ who helpeth Marianos and his children.**+ Help Mariades and Saakōnas, the architects!**Finished in the month of Xandikos, of the 411 (?) year. (April, 363 (?) A. D.)*

The last figure of the date is not absolutely certain: it may be X, instead of Y, and, if so, the date is 563 A. D.

The name Σακκωνας is the Syriac diminutive of Isaac, in Greek form.

1202. KEFR ANTĪN. HOUSE (?), 523 A. D. Lintel of the entrance of a small building, about the center of the ruins. Before the entrance is a vestibule. The lintel

is in situ. It is about 2 m. long and 59 cm. high. In the center is a square plate, 72 cm. broad, above and on each side of which the inscription is written in a curious fashion: the ΧΜΓ and the names of the two saints form a little inscription by themselves, on the left of the plate, while the rest frames the plate on three sides, extending outward at the bottom, to right and left, as mouldings often frame doors or windows in this region. The letters are incised: they vary from $3\frac{1}{2}$ to 5 cm. in height, are fairly well cut, and are all clear and certain.



Inscr. 1202.

Ch(rist) b(orn) of M(ary). St. Theodoros and St. Sergios.

Lord help they servant, Damianos, who built this building, in the month Loös, indiction first, the 571st year! (August, 523 A. D.)

Evidently the workman who carved this inscription inscribed the first two syllables of name *Δαμιανός* at the side of the square before he realized that he would not have space enough to complete the name there: when he began again above the square he wrote the name in full, repeating the first two syllables. On the letters ΧΜΓ see above under No. 1154.

1203. SIMKHÂR. HOUSE (?), 272-3 A. D. On a plain stone in the left jamb of a doorway, facing south, in the last group of buildings in the eastern part of the town. Before it was a colonnade of piers. It seemed to belong to a private house. It may, however, have been a religious building of some sort. The block is 43 cm. broad and 45 cm. high, the letters 5 cm. high. Drawn by Professor Littmann.



Inscr. 1203.

Ετους ακ'. Μνησθῆ ὁ γράψας.

In the year 321 (?). May he who wrote (this) be remembered! (272-3 (?) A. D.)

The second figure of the date is uncertain: it may be 1, and, if so, the date is 262-3 A. D. The symbol above the inscription is worthy of notice; but I could not determine its origin or significance.

The formula *μνησθῆ ὁ δεῖνα* is as common in Syrian inscriptions as the more classical

μνήσθητι τοῦ θεῖνου.¹ In Waddington's collection, for example, μνήσθη is found four times,² μνήσθαι³ (doubtless for μνήσθειν) once, and μνήσθητι four times.⁴ The form μνήσθη is regularly followed by the nominative.⁵ Compare, for example, *P. A. E. S.* III, A, 67: Μνήσθη Ἀδσάλλας, ὅπου ἂν ᾖ,⁶ or *A. A. E. S.* III, 336: Μνήσθη Μαρόνας, λειστούμος. Also Nos. 1170 and 1175 above, and 1204 and 1205 below. Clearly then this form was used in the passive sense: so also the forms ἐμνήσθησαν and ἐμνήσθη in *Acts* x, 31 and *Revelation* xvi, 19. In an inscription from "Deir-Salibé", published by M. Victor Chapot in *B. C. H.* xxvi (1902), p. 196, No. 43, the form μνήσθων appears: Χ Μ Γ μνήσθων Εὐφρόνης Μηνᾶς Βερνικιανῶς τεχνίται κτλ. In commenting upon this inscription M. Chapot says: "Au début la formule Χριστός, Μιχαήλ, Γαβριήλ,⁷ suivie du verbe μνήσθων pour invoquer le souvenir et appeler la protection de Dieu et des anges. Μνήσθητι est une formule usuelle dans les prières, et elle a passé dans les épitaphes." But whatever may be the meaning of the letters Χ Μ Γ, M. Chapot's interpretation of the μνήσθων is certainly erroneous. In view of the other texts just quoted, it seems to me clear that the verb in M. Chapot's inscription is passive, and that the names which follow it are the subjects.

Less strange than this use of deponent forms in a passive sense is the use of the third person singular of the subjunctive for the third singular of the imperative. As M. Uspensky has pointed out in editing the inscription published above under No. 1170, this use is in conformity with the development of the Greek language in post-classical times.⁸

1204. SAME BUILDING. On the lintel of the same doorway as Nos. 1203 and 1205. The stone is 1.84 m. long and 41 cm. high. It is without mouldings, and all the carving is crude and badly finished. Ornament and letters alike are incised. The letters are from 4 to 6½ cm. high. Copied by Professor Littmann.



Inscr. 1204.

Εἰς Θεὸς ὁ βοηθῶν ἡμᾶς.
Μνήσθῃ ὁ γράψας.

One God who aideth us.
May he who wrote this be remembered!

See the commentary on the preceding inscription.

1205. SAME BUILDING. On two stones, one below the other, in the right jamb of the same doorway as Nos. 1203 and 1204. I am not sure, however, that any two

¹ Compare *Luke* xxiii, 42, and *A. A. E. S.* III, 284 and 293.

² Wad. 1886 a, 2270, 2277 and 2278.

³ Wad. 2464.

⁴ Wad. 2087, 2090, 2562 l and 2634 = *A. A. E. S.* III, 293.

⁵ Even in Wad. 1886 a: Μνήσθῃ Μαρούς I believe that the name is certainly a nominative, and not a genitive from Μάρους as Waddington, supposed. Compare Clermont-Ganneau: *Recueil d'Archéologie Orientale*, I, p. 170.

⁶ See, however, *P. A. E. S.* III, A, 40: Μνήσθῃ Γεωργίου.

⁷ See above, p. 171 f.

⁸ Th. Uspensky: *Archaeological Monuments of Syria*, 1902, p. 72 note 2 = "Izvestiya" of the Russian Arch. Institute at Constantinople, Vol. VII, p. 164. K. Dieterich: *Untersuchungen zur Geschichte der griech. Sprache*, 1898, p. 206. Cf. Hatzidakis: *Einleitung in die neu-griechische Grammatik*, 1892, p. 218, and Fr. Blass: *Grammatik des Neutestament. Griechisch*, 2te Auflage, 1902, p. 213 f.

of these stones belonged together originally. The upper stone is 56 cm. long and 28 cm. high: the lower 42 long and 54 high. The letters on both stones are badly written and much weathered: they are 4 to 6 cm. high. Copied by Professor Littmann.

ΕΙCΘΕC
Ο ΩΝΗC
CΓΡΑΥΑC

ΕΙCΘΕC
ΙCΙCΤΙΓΛ
ΩΥΙΠΤΑΝ

Inscr. 1205.

Εἰς Θεός] ὁ [β]ωη[θών. Μνησθῆ] ὁ γράψας.

One God who aideth. May he who wrote this be remembered!

I cannot decipher the inscription on the lower stone with any confidence. Perhaps it was *Ἐλέει τοὺς γινώσκοντας*: *He will have mercy upon the discerning*, or some such words. Perhaps, however, this is only a part of a much larger inscription. The early date may explain the apparently cryptic character of these inscriptions.

1206. HOUSE (?), 349-50 A.D. On the lintel of a doorway in the second story of a small building, probably a house, facing east, in the southwest corner of the town: in the lower story there was a stable. In the center of the lintel is a disk, in relief, containing an incised geometrical design enclosing a \div . On each side of the disk is a dovetail plate in relief, the body of the plate being 25 cm. broad and 33 cm. high. The inscriptions are all incised. Inscr. A is on the left-hand plate, in letters 9 to 10 cm. high. Inscr. B is at the right of this plate, and a little above the level of the first line of A: it is 25 cm. long and $5\frac{1}{2}$ cm. high. Inscr. C is at the left of the right-hand plate, corresponding with B: it is 18 cm. long and 7 cm. high. Inscr. D is on the right-hand plate, in letters 6 to 9 cm. high. All the letters are clear.

A
ΕΙCΘ
ΙΧΘΥC

B
ΕΤΟΥC

C
ΗΓΤ

D
ΚΑΙ
ΕΟΙΟCΑΤΑ
ΔΙΠΛΑ

Εἰς Θεός. ΙΧΘΥC. Ἐτους η'γ'. Καὶ σοί, ἔσα (λέγεις), τὰ διπλᾶ.

One God. J(esus) Ch(rist) (the) S(on) of G(od) (our) S(avior). In (the) year 398. To thee also, whatsoever (thou sayest), (be) the double! (349-50 A.D.)

On Εἰς Θεός see above under No. 1126 and *A. A. E. S.* III, p. 18 f. On ΙΧΘΥC see No. 1188. On καὶ σοί πλ. see No. 1125.

1207. FRAGMENT, built upside down into the foundations of the north corner of the apse of the chapel at the southeast angle of the church: it is below the present ground level, with its face towards the interior of the apse. Div. II, B, p. 335. It is 1 m. long and about 23 cm. high. It is broken irregularly through the middle of the

second line of letters. The inscription is rudely incised in deep, broad, irregular strokes on a plain surface. The letters of the first line are 17 cm. high.

□□ΑΛΕΓΙ□□□
ΤΑΔΙΠΛΑ

Ὅσα λέγεις, σοὶ τὰ διπλᾶ.

What thou sayest, to thee the double!

I believe this to have been the lintel of a plain house of the third or fourth century. On ὅσα λέγεις κτλ. see Nos. 1073, 1125 and 1206, and *A. A. E. S.* III, 10.

1208. HOUSE (?). On the lintel of a building, apparently a house, facing west, a short distance southwest of the church. The inscription is incised on the uppermost band of the mouldings. This band is 2.06 m. long and 10¹/₂ cm. high. The inscription is 1.95 m. long, the letters 6 cm. high. Some of the letters are still clear, others are wholly lost. The 7th, 10th and 22nd are very uncertain. Between Η and Γ there is room for two normal letters. At the end, after Υ, there was perhaps one letter more.

ΙΦΕΘΕΑΥΟCΘΖΟΗ ΓΝΩΗΩΝΕΙΟΥ

I have been altogether unable to decipher this inscription satisfactorily, although most of the letters are certain, and not more than one letter, at most, can have been lost from either end. I have thought it possible to read (Εὔ)στ(ε)υ)σ(α) ζσῆ [Εὔ]γνομωνίου: *Prosperous (be the) life of Eugnomonios*, or (Εὔ)στ(ε)ι)α (σδ)ς <σ> ζσῆ[ς Εὔ]γνομωνίου: *Straight (be the) path of life of Eugnomonios!* Compare No. 1199. The name Εὐγνομώνιος occurs in *C. I. G.* 9449. But I have no confidence in either of these readings, and it may even be possible that this, the present inscription, is the same as that published by M. Chapot in *B. C. H.* xxvi (1902), p. 185, No. 27, from "Kimmar" in the neighborhood of Kal'at Sim'an. M. Chapot, however, describes the letters of his inscription as from 2 to 3 cm. high. His reading is: +ΟΘΕΟCΒΟΗCΟΝΑΝΙΩΝΝΩ, followed by about as much more, which possibly may have formed a second line overlooked by me.

1209. Near SIMKHÂR. STELE, beside the present road, about five minutes' walk from the town, southward. The stone was found face up, on the east side of the road: on the west of the road is the socket, cut in the living rock, for this stele. The edges are broken and weathered, so that my measurements are not strictly accurate: the stone is about 2.50 m. long, 86 cm. broad and 48 cm. thick. Near the bottom of the face is a dovetail plate, on which 5 or 6 lines were incised: above the plate were 3 or 4 lines more, and probably a cross. The stele is of lime-stone, and has evidently been lying face up for a long time: the inscription has almost disappeared. I could read a few letters here and there, but no word. I suppose this to have been another boundary stone: see No. 1195; also *A. A. E. S.* No. 75, No. 28 f. etc.

1210. SHEKH SLEMÂN. HOUSE, 407 A.D. On a double panel for the balustrade of the second story of a portico, apparently belonging to a house which faces south, about the middle of the south side of the ruins. The block is now broken into two

pieces, which were found partly buried in the earth among the ruins. The first piece is 1.63 m. long at the top, 1.08 at the bottom, and 86 cm. high. It contains the whole of the first panel and part of the second. The panels have a border 11 cm. wide, with a splayed edge $8\frac{1}{2}$ cm wide. The panels themselves are 64 cm. broad and 53 cm. high, inside. The second piece is 21 cm. long at the top and $76\frac{1}{2}$ cm. at the bottom. The inscription is incised. The first line is upon the upper border of the panels. The second is upon the splayed edge of the upper border, above the second panel only. The rest of the lines are within the panels. The letters are well formed and well executed: they are 6 to 7 cm. high, excepting those of the second line, which are only 5 cm. The inscription is complete.



Inscr. 1210.

One God and his Christ and the Holy Spirit. In (the) year 455, month Panemos 29th. Lord God help Martyrin and his children . . . (July, 407 A. D.)

I do not know the meaning of the last four letters, unless they signify ὅτι (= ἔτι)

φ(ιλοῦσίν σε): cf. *A. A. E. S.* III, 22.



Doorways of a Church. Inscr. 1211.

1211. CHURCH, 602 A. D.

On the lintel of the south door of the smaller of the two churches which stand on the hill southwest of the other ruins, and quite outside of the town. *Div. II, B, p. 337 f.* On the lintel are two ornamental squares, 40 and 50 cm. broad respectively. Between them is a disk, 30 cm. in diameter, and a cross measuring 22 cm. each way: the disk is placed rather below, the cross above the center of the stone. Inscr. A is at the left of this disk, Inscr. B is above the disk and at the left of the

cross. The first (A) is 30 cm. long and 23 cm. high: the letters are $4\frac{1}{2}$ cm. high. The second (B) is 35 cm. long, 12 cm. high, and its letters are from 2 to $3\frac{1}{2}$ cm.

high. At the right of the right-hand square is an inscription in Syriac: see Div. IV, B, 62. The last letter of the second line of B is precisely like the last letter of the first line of A, by which I judge that it is certainly Z. At the beginning of the third line of B there is room for one letter, and possibly traces of P: I believe, however, that there was no letter here.

A	B
+ MΛΩΟΥΖ	+ ΕΠΙΤΟΥΣΕΡ
ΤΟΥΝΧ	ΛΙΟΥΠΡΖ
ΕΤΟΥΣ	ΟΦΩΝ+
ΙΝΔΕ	

+ M(ηνός) Λώου ζ', τοῦ νχ' ἔτους, ἰνδ. ε'.

+ Ἐπὶ τοῦ Σεργίου, πρ(ε)σβυτέρου (ἡμ)ών.

+ *In the month Loös 7th of the 650th year, indiction 5.*

+ *Under Sergios, our presbyter. (August, 602 A. D.)*


1212. CHURCH. On the lintel of the north door of the "Church of St. Mary", the larger of the two churches on the hill southwest of the town. Before the doorway was a porch with two columns. Div. II, B, p. . The lintel is now broken in three pieces. The first fragment is 89 cm. long and 59½ cm. high. The inscribed band is 9 cm. wide: from the beginning of the band to the break the length is 27 cm. at the top and 31 at the bottom. The letters are incised, and are 7 cm. high. The second fragment is 1.38 m. long. The third fragment is 97 cm. long; but the inscribed band is 30 cm. long, from the break to its end. There seems also to be some sort of a monogram incised on a small disk in relief, in the center of the lintel; but, if so, I could not decipher it.

1. 2. 3.
+ ΑΓΙΑ ΜΑΡΙΑΘΕΩΤΟΚΗΒΟΗΘΙΕΡΓΙΩΤΗΚΤΟΙ ΒΕΙΔΜΗΝ

+ Ἁγία Μαρία, Θεωτόκη, βοήθη Σεργίω τέκτονι. Ἀμήν.

+ *Holy Mary, mother of God, help Sergios, (the) builder! Amen.*

1213. BUILDING. Lintel of a small plain building, facing west, in the southeast corner of the town. See Div. II, B, p. . The lintel is 2.42 m. long and 45 cm. high. It has no mouldings. Near the center is a sort of boss, or disk, with a plain face, 17½ cm. in diameter. The inscription is incised. The name ΣΕΡΓΙΟΣ is 30 cm. long, the letters 6 cm. high: it begins 12 cm. from the left end of the stone and is 16½ cm. from the bottom. The main line is 1.44 m. long, and 7 cm. from the bottom. It ends 91½ cm. from the right end of the stone, the space after it being blank. Its letters are from 4½ to 7 cm. high, and deeply cut. Though I was unable to understand the meaning when I made my copy, the letters all seemed to me uncompromisingly plain and certain. Perhaps the man who carved the inscription was inaccurate, or, because he attempted an innovation in the customary style, was prevented from finishing this monument.



Inscr. 1213.

Σέργης. ΟΙΟΚΟΡ_Ε_κοσι(σ)τού, ἰνδικτιῶν εἰ, τὸ κτί(σ)μα.

Sergis -hundredth (year), indiction 5, this building (was erected).

I suppose that the main line contains chiefly the date, and that ἑξακοσι(σ)τού, *six-hundredth*, may be read with some confidence. The years of the seventh century of the era of Antioch which correspond with indiction 5 are 605, 620, 635, 650, 665 etc. I am inclined, now, to read Ἐτ. εἰκοστ. ἑξακοσι(σ)τού, i. e. Ἐτ(ου)ς εἰκοστὸν ἑξακοσι(σ)τού, In the six hundred and twentieth year = 571-2 A. D. Or perhaps one might read Ἐτους εἰ ἑξακοσι(σ)του, In the six hundredth 35th year (635th) = 586-7 A. D. Somewhat similar methods of expressing a date are found elsewhere, e. g. τοῦ τετάρτου φ' ἔτους, in No. 1081 above, or τοῦ δεκάτου πεντακοσι(σ)τού ἔτους, in No. 1082: see also No. 1080, and *A. A. E. S.* III, 72.

On the other hand, the first seven letters of the main line certainly look more like οἰκοδόμος, or else Οἰκοβίου (for Ἰακώβου), or Θεοδορου (for Θεοδώρου), and this may be the name of the father of Sergis (= Sergios): if so, what follows may not be a numeral at all.

The Ν above the Τ, near the end of the inscription, may be the remains of a ΤΕΚΤΩΝ: a τέκτων (*builder or architect*) Sergios is mentioned in No. 1212, which I judge to be also of the sixth century.

ADDENDA AND CORRIGENDA.

- No. 813. See also Deissmann, *Philologus*, 1905, p. 475 ff.
 No. 829. See also *Bys. Zeitschr.* xv, p. 280.
 No. 830, p. 12, line 30. 559-60 A. D.
 No. 834. Φρ(ου)μενταρίου: D. Magie.
 No. 845. [δ' (?)].
 No. 850. Βέ(σ)σανος: Jalabert, *R. A.* xii, p. 328 and *Mélanges de Beyrouth* iii, p. 751. Φρ(ου)μενταρίου: D. Magie.
 No. 851, p. 20, last line. (569-70 A. D.).
 No. 865. (April, 561 A. D.).
 No. 867. Θεόδ[ωρος] . Add: (579-80 A. D.).
 No. 871, p. 27, first line. 543 A. D.
 No. 877. ἔξῃρ[γασμένοις]: Hiller von Gaertringen, *B. P. W.* 1908, Col. 999; G. Glotz, *R. E. G.* xxii, p. 319; ἔξῃρ[γάσας]: Jalabert, *Mél. d. B.* iii, p. 751.
 No. 881. πραγμ(α)τευτοῦ.
 No. 885. (τ)ῃ λέξει: Jalabert, *R. A.* xii, p. 328; *Mél. d. B.* iii, p. 751; G. Glotz, *R. E. G.* xxii, p. 319, No. 2. ἐπο[ίησεν] εὐσεβ(ῶς), (τ)ῇ λέξει γενομένη ἡμῶν δεσποίνῃ. τῷ(ν) ὑπὸ Λάζαρον κτλ.: Hiller von Gaertringen, *B. P. W.* 1908, Col. 999 f. κυράτορα.
 No. 891. βοήθι Θωμᾶ (καὶ) Ἰωάνν(η)ς (Ἰωάννη?): G. Glotz, *R. E. G.* xxii, p. 319, No. 3.
 No. 908. Cf. *I Cor.* x, 31: Deissmann, *Philologus*, 1905, p. 475-8; Clermont-Ganneau, *Recueil* vii, p. 225.
 No. 912. See also Seller, *Antiq. of Palmyra*, App. p. 172, No. x; Oestrup, p. 85; Hartmann, p. 97.
 No. 915, lines 5 and 6. καὶ [τὸν βίον] Φαιδρύνῃ καὶ τῇ πατρίδι, / δι' ὧν εὐγνωμονεῖς, ἀνεφάνης σωτήρ: Hiller von Gaertringen, *B. P. W.* 1910, Col. 196 f.
 No. 917. See also Clermont-Ganneau, *Bys. Zeitschr.* xv, p. 281.
 No. 922. Δομετίου Μαρίας: Clermont-Ganneau, *Recueil* vii, p. 226.
 No. 924. διαφ(έρει) Στεφάνου(?). See also Hartmann in *Z. D. P. V.* 1900, p. 99.
 No. 927. Probably Frag. A of this inscription, not of No. 929, was published by Seller, *Antiq. of Palmyra*, p. 171, No. v = *C. I. G.* 8931. I have not seen Seller's publication.
 No. 929. Probably not Frag. A of this inscription, but Frag. A of No. 927 was published by Seller, p. 171, and republished in *C. I. G.* 8931.
 No. 930. Ἀγίω.
 No. 938. αὐξίτω Σαλίρ[---]: Jalabert, *Mél. d. B.* iii, p. 744; *R. A.* 1909, 2, p. 311. Cf. Clermont-Ganneau, *Recueil* vii, p. 210 f.
 No. 939. Oestrup, *Bidrag* (= *Mém. Acad. Danemark*, 1895), p. 87; Hartmann, *Z. D. P. V.* 1900, p. 99; Lucas, *Bys. Zeitschr.* 1905, p. 44, No. 55b.
 No. 940 A. Seller, p. 172, No. ix; Lucas, *Bys. Zeitschr.* 1905, p. 44, No. 55 a.
 No. 968. Φιλοκτίστη.
 No. 969. ἀκοή Κ(υρίου): Clermont-Ganneau, *Recueil* vii, p. 227.
 No. 971. Σιλουα[ν]οῦ. See also Clermont-Ganneau, *Bys. Zeitschr.* xv, p. 281.
 No. 976. Burton and Drake, No. 32.
 No. 987. See Clermont-Ganneau, *Bys. Zeitschr.* 1906, p. 281.
 No. 992. See also *Bys. Zeitschr.* 1905, p. 755.
 No. 994. Burton and Drake, No. 35.

- No. 996, p. 83, line 7. Read: No. 339: Ἀγαθὴ Τύχη κτλ.
 No. 997. ὑπὲρ μνησίου [κὲ ἀ]ναπαύ[σεως]: Jalabert, *R. A.* 1919, 2, p. 311.
 No. 1003. δι(α)κ[όνου].
 No. 1005, p. 86, line 29. Add: (429-30 A. D.).
 No. 1009, p. 89, line 30. πατριάρχων.
 No. 1016, p. 92. Below the cut, read: I'djâz.
 No. 1018, line 11. [Χω](ρ)ιον.
 No. 1019, line 2. οἶκον.
 No. 1021. Perhaps εἰναετῆρες = *inhabitants*. For εὔτι read οὔτι.
 No. 1023. See *B. P. W.* 1910, Sp. 197.
 No. 1034, line 4. Π[ράκτου].
 No. 1037. Ῥωμανῶ.
 No. 1046. For *indiction 13* read: *indiction 11*.
 No. 1049. Ῥωμανῶ.
 No. 1056. Lucas, in *Byz. Zeitschr.* XIV (1905), p. 54, No. 86. See also *Byz. Zeitschr.* 1906 p. 281.
 No. 1057, p. 112, line 3. 557 A. D.
 No. 1062. Κεπρ[οβλ]-.
 No. 1070. For βααλα read Βααλα. Jalabert, *R. A.* 1909, 2 p. 311, suggests Βαλλα. Cf. Clermont-Ganneau, *Recueil* II, p. 86.
 No. 1071. Βασιλειδ[η κ]ε Γενέω: Jalabert, *R. A.* 1909, 2, p. 311.
 No. 1072, p. 118, line 17. Add: (July, 193 A. D.). The inscription at the left may be read: ἐκόλαψεν Τρειέννης Ἀραβέου ἀπενία: *Treiennes (son?) of Arabeos hewed out (this tomb) in (his) leisure*.
 No. 1080. For 452 A. D. read: 452 or 451 A. D. See below, under No. 1108.
 No. 1092, p. 129, line 19. Add: (July, 143 A. D.).
 No. 1106, p. 137, line 1. For Ἀρίστων read: Ἀρίστων. Line 9, read: *manibus*. Line 19, read: *manibus*. Line 26, read: 2.09½ m.
 No. 1107, p. 138. For BC. read: b. c. Line 29, read: dates; 446.
 No. 1126. μ(η)νός Ἀρτ(εμισίου).
 No. 1127. αὐτὸ.
 No. 1128. See Lidzbarski, *Ephemeris* II, p. 337.
 No. 1151, p. 166, line 34. (516-7 A. D.). Line 35. Ἀ[πελ(αίου)].
 No. 1165, p. 178, line 21. Ἐτ[εως].
 No. 1193. Θεοῖς.
 No. 1194. Μαρτιάμη.

TABLE OF ABBREVIATIONS.

- A. A. E. S. Publications of an American Archaeological Expedition to Syria in 1899—1900.*
New York, The Century Co. (Part III, 1908).
- A. J. A. American Journal of Archaeology.*
- A. J. P. American Journal of Philology.*
- B. C. H. Bulletin de Correspondance Hellénique.*
- B. P. W. Berliner Philologische Wochenschrift.*
- Burton and Drake: *Unexplored Syria*, 2 Vols., London, 1872.
- Byz. Zeitschr. Byzantinische Zeitschrift.*
- C. I. G. Corpus Inscriptionum Graecarum.*
- C. I. L. Corpus Inscriptionum Latinarum.*
- Class. R. Classical Review.*
- Clermont-Ganneau. See *Recueil*.
- C. R. de l'Acad. Comptes Rendus de l'Académie des Inscriptions et Belles-Lettres.*
- Div. II, etc. Division II etc. of the Publications of the Princeton University Archaeological Expeditions to Syria.
- Dölger. See *Fischsymbol*.
- F. H. G. Fragmenta Historicorum Graecorum.*
- Fischsymbol.* Fr. J. Dölger: *Das Fischsymbol in Frühchristlicher Zeit*, Band I, 1910.
- I. G. Inscriptiones Graecae.*
- I. G. R. Inscriptiones Graecae ad Res Romanas Pertinentes*, edited by Cagnat and Lafaye, Vol. III.
- Izvestiya.* Publications of the Russian Archaeological Institute in Constantinople.
- Journ. Asiat. Journal Asiatique.*
- Mél. de B. Mélanges de la Faculté Orientale de l'Université St. Joseph à Beyrouth (Syrie).*
- P. A. E. S. Publications of the Princeton University Archaeological Expeditions to Syria in 1904—1905 and 1909.* Leyden, Late E. J. Brill.
- Pal. Expl. Fund, Q. S. Quarterly Statements of the Palestine Exploration Fund.*
- Patr. Gr. Migne: Patrologiae Cursus Completus, Series Graeca.*
- R. A. and R. Archéol. Revue Archéologique.*
- R. des Ét. Anc. Revue des Études Anciennes.*
- Recueil.* Ch. Clermont-Ganneau: *Recueil d'Archéologie Orientale.*
- R. E. G. Revue des Études Grecques.*
- Revue Numis. Revue Numismatique.*
- de Rossi: *Bullettino di Archeologia Cristiana.*
- Sachau, E.: *Reise in Syrien und Mesopotamien*, Leipzig, 1883.
- S. C. Marquis de Vogüé: *La Syrie Centrale*, Paris, 1865—1877.
- Swainson, C. A.: *The Greek Liturgies*, Cambridge, 1884.
- T. A. P. A. Transactions and Proceedings of the American Philological Association.*
- Uspenski, Th.: *Archeologitcheskie Pamatniki Sirii* (Archaeological Monuments of Syria), Sofia, 1902
(Reprinted from the *Izvestiya* of the Russ. Arch. Inst. in Constantinople).
- de Vogüé. See S. C.
- Wad. and Waddington: *Inscriptions Grecques et Latines de la Syrie*, Paris, 1870 = Le Bas: *Voyage Archéologique*, Tome III.
- Z. D. P. V. and Z. P. V. Zeitschrift des Deutschen Palästina-Vereins.*
- Z. M. G. Zeitschrift der Deutschen Morgenländischen Gesellschaft.*

INDICES TO DIVISION III, SECTION B.

INDEX OF GREEK PROPER NAMES.

Only those forms of the names which actually occur in the inscriptions are contained in this list. Cases other than the nominative are indicated by a letter in brackets. The names of God or Christ, of heathen gods, and of emperors are printed with hairspacing. The numbers refer to the inscriptions.

- Αββάτου (g.), 874, 875, 881, 1142.
 *Αβραάμ, 832, 967, 1161.
 *Αβρααμίου (g.), 914, 967, 1056, 1121.
 *Αβράμης (?), 1148.
 Αβωων (g.?), 948.
 *Αγαπητοῦ (g.), 881.
 *Αγαπίου (g.), 1161.
 *Αγιον Πνεῦμα, 930, 949, 984, 994, 996, 1017,
 1029, 1031, 1076, 1077, 1086, 1098, 1108, 1140,
 1146, 1173, 1184 (?), 1210.
 *Αγριππῖνος, 980.
 *Αδωνις (?), 1144.
 *Αζίζος, g. -ζου, 952, 993.
 *Αηράμης (?), 1148.
 *Αθανάτορ, 868, 1103.
 *Αθηνις, 1094.
 Αθ[—]αβ[ο] (g.), 809.
 [*Αιδου], 944.
 Ακωβαν, 904.
 Αλδειος (?), 1128.
 *Αλεξάνδρῳ (d.), 1075.
 *Αλέξανδρος, g. -δρου, 1043, 1092, 1115.
 Αλιρο[—], 938.
 *Αλουλαῖος, 1133.
 Αλουμθα (g.?), 828.
 Αμροσίου (g.), 1160 a.
 Αμω[ν] (d.), 1070.
 *Αυαίου (?) (g.), 924.
 *Αναστασίου (g.), 1088.
 *Αναψώνης, 962.
 *Ανδρόνικος, 1175.
 *Ανιδώνω (?) (d.), 1208.
 *Αγκύριν (a.), 1053.
 *Ανας (g.), 924.
 *Αντίοχος, g. -χου, d. -χω, 1085, 1093, 1191, 1199.
 *Αντιπάτρου (g.), 1042.
 *Αντωνίου (g.), d. -ω, 888, 986, 1143.
 *Αντώνιος, g. -νίου, 1092, 1170, 1175.
 *Α[πελ(αίου)] (?) (g.), 1151.
 *Απταίω (d.), 1070.
 *Αργύριος, g. -ρίου, 1176, 1184.
 *Αρίστων, 1106.
 *Αρχαδίου (g.), d. -ω, 1006, 1007 (?).
 *Αρτεμισίου (g.), 813, 881, 1082, 1190.
 *Αρχας, 1069.
 Ασα (g.?), 934.
 Αύγαϊε (v.), 1132.
 Αύδυνάιου (g.), 821, 883, 948, 1138.
 Αυξίτως (?), 938.
 Αύρ(ήλιος), 1093.
 Αυσα (?), 1132.
 Αυσαλλα (?), 1132.
 Αὐτοκράτορος (g.), 1006, 1111.
 ΑΦροδῖος (?), 1171.
 *ΑΦροδισίου (g.), 1193.
 ΑΦρονιος (?), 1171.
 *Αχέου (?) (g.), 1173.
 Βαδρα (g.), 1190.
 Βαδωνες (?), 820.
 Βάκχος (?), 1160 a. See also Βάχχου.
 Β[α]β[α] (g.), 1157.
 Βαρθης, 1131.
 Βαρθων, 967.
 Βαραχ (?) (g.), 1136.
 Βάραχος, g. -χου, 1111, 1160 a.
 Βαραψα (g.), 1136, 1190.
 Βαρεχβηλος, 1092.
 Βαρλααας, 960, 1130.
 Βαρλάμου (g.), 967.
 Βαρσημεα, 985.
 Βαρσιμτησα, 1129.
 Βαρ[—], 1144.
 Βασιλείω (d.), 1071.
 Βάσσορ, 1043, 1117 (?).
 Βάστου (?) (g.), 1117.
 Βάχχου (g.), 1088. See also Βάκχος.
 Βα[—], 820.

Βεεσωνος (?) (g.), 850.
 Βελέου (g.), 935.
 Βερίωνος (g.), 1170.
 Βερνικιανός, 1092.
 Βε(σ)τωνος (?) (g.), 850.
 Βικτωρίνος, 1015.
 Βοσσυ (?) (g.), 1142.
 Βακλᾶ (?) (d.), 1070.

Γακρας (?) 854.
 Γαβριήλ, 1052.
 Γαβριήλου (g.), 1094.
 Γαδανᾶ (g.), 900, 903 (?).
 Γαδεῖος (?) 1128, 1129 (?).
 Γάιος, g. -ίου, 1111, 1170.
 Γαούλου (g.), 1101.
 Γενέφ (?) (d.), 1071.
 Γερμανικοῦ (g.), 1111.
 Γεωργίου (g.), 1180.
 Γορπιαίου (g.), d. -φ, 843, 890, 899, 1080, 1108, 1121, 1167, 1178.

Δαδ (g.), 839.
 Δαισίου, see Δεσίου and Δησίου.
 Δακικοῦ (g.), 1111.
 Δαμιανού (g.), a. -νον, 1114, 1202.
 Δανιήλου (g.), 834.
 Δάνου (g.), 1088.
 Δαρείου (g.), 1170.
 Δεσίου (g.), 848, 869, 930, 1072, 1083, 1086, 1087, 1114, 1117, 1120.
 Δησίου (g.), 1122.
 Δημητρίου (g.), 1042.
 Διαβόλου (g.), 1012.
 Διογένους (g.), 1050.
 Δισδώρος, 1076.
 Δίου (g.), 834, 896, 906, 970, 979, 1049, 1111.
 Δομετιανός, 1170.
 Δομετίου (g.), d. -φ, 920, 922, 1070.
 Δόμνου (g.), 1028, 1029, 1034.
 Δωμν[ινε] (v.), 1033.

Εβιδβουρως (?) 948.
 Εισίδωρος (?) 1152.
 Εισίδωτος, 1152.
 Έμμανουήλ, 866, 957, 1065.
 Έρμῆ (g. ?), 952.
 Ερωτᾶ (?) 1134.
 Εύγεγίου (g.), d. -φ, 967, 977.
 Εύγνωμανείου (?) (g.), 1208.
 Εύδημφ (d.), 1133.
 Εύδο[ξία], 869.
 Ευενᾶ (d.), 1067.
 Εύκλου (g.), 925.

Εύλαλίᾳ (d.), 968.
 Εύ[λόγιος], 872.
 Εύ[νό]μου (g.), 896.
 Εύρύαλος (?) 1115.
 Εύσέβιος, g. -ου, d. -φ, 939, 940, 980, 1074, 1075, 1089, 1115.
 Εύσέβιος, 955, 1094, 1096, 1120.
 Εύσέβων, 1124.
 Εύσταθίου (g.), 1177.
 Εύστολίου (g.), 881.
 Εύτυχίου (?) (g.), 1180.
 Εύφρανις (?) 1010.

Ζακκᾶ (d.), 1067.
 Ζαρια (g.), 815.
 Ζαρυλ (?) 1100.
 Ζαχέου (?) (g.), 1173.
 Ζεβινᾶ (g.), 1067.
 Ζεβινος, 1175.
 Ζεβουδις, 819.
 Ζοηστου (g.), 1093.
 Ζοΐλου (g.), 1068.
 Ζοκοτα (g. ?), 1180.
 Ζορυν (?) 1100.
 Ζωρᾶ (d.), 1067.
 Ζώιλλος, g. -λου, 987, 1002.
 Ζωραν, 904.

Ήρακλ[ί]του (g.), 1161.
 Ήλιοδώρου (g.), 869.
 Ήρώδης, 1092.
 Ήτυχίου (g.), 1026.

Θεκλα (?) 1035.
 Θεδώρος, g. -ρου, v. -ρε, 867, 926, 1202, 1213 (?).
 Θεοδοσίου (g.), d. -φ, 1006, 1007.
 Θεοδότῳ (d.), 1186.
 Θεός, g. -ου, d. -φ, v. -ός and -έ, 813, 817, 838, 857, 865, 868, 878, 908, 913, 915, 917, 920, 926, 928, 930, 932, 947, 968, 980, 989, 992, 996, 1016, 1017, 1019, 1022, 1027-1030, 1037, 1047, 1065, 1066, 1070, 1076, 1077, 1080-1086, 1089, 1090, 1098, 1103, 1108, 1109, 1110, 1118, 1121, 1126, 1139, 1150, 1151, 1166, 1168, 1169, 1178, 1184, 1186, 1189, 1192, 1196, 1198-1201, 1204-1206, 1208, 1210. See also Index of Phrases and Index of Symbols.
 Θεότεκνος, g. -νου, 935, 987, 997, 1000, 1118, 1170.
 Θεοφίλου (g.), d. -λφ, v. -λε, 982, 1033, 1191.
 Θρ[ι]τᾶ (d.), 1067.
 Θωμάς, g. -μᾶ, d. -μᾶ, v. μᾶ, 867, 891 (?), 914, 915, 918, 1121.

- Ἰακώβ (n. and g.), 928, 1141.
 Ἰάκωβος, g. -βου, 913, 915, 1094, 1122, 1157, 1213.
 Ἰαναίου (?) (g.), 924.
 Ἰησοῦς, g. -σοῦ, 857, 911, 989, 996, 1002, 1029, 1099, 1150, 1151. See also IXΘΥΣ.
 Ἰουδαί, 1014.
 Ἰουλιανός, 1127.
 Ἰουστίνου (g.), 1088, 1117.
 Ἰσίδωτος, see Εἰσίδωτος.
 Ἰσίδωρος, see Εἰσίδωρος.
 Ἰσραήλ, 831.
 Ἰσχυρός, 868, 1103.
 Ἰωάννης, g. -νου, d. -νη, a. -νην, 853, 871, 887, 891, 909, 917, 934, 935, 985, 988, 992, 993, 1015, 1028, 1029, 1034, 1043, 1053, 1059, 1088, 1110, 1114, 1120, 1122, 1177, 1179.
 Ἰωρδάνης, 985.
 Ἰωσήφ (a.), 831.
 Ἰωσήφ[ου] (g.), 914.
 Καίου (g.), 936 (?), 937.
 Καῖσαρ, g. -ρος, 1006, 1111.
 Καλλιόπιος, 980.
 Καλοποδίνου (g.), 1075.
 Καο(υ) (?), 936.
 Καοσεου (?), 936.
 Κάπερ Νάβου (d.), 1175.
 Καπρῶ (g.), 1175.
 Καπρ[οβα](ρ)η(ν)ῶν (g.), 1062.
 Κά(ρ)ο(υ) (?) (g.), 936.
 Κασιανῶ (g.), 1002.
 Κάσσανδρος, 1175.
 Κλαυδίου (g.), 1170.
 Κοδράτου (g.), 1152.
 Κόνωνος (g. ?), 1041.
 Κοσμᾶ (g.), 815 (?), 844, 855, 857, 1142, 1176, 1177, 1190.
 Κυριακοῦ (g.), 848, 1003, 1004.
 Κυρίκου (g.), 924.
 Κυρίλης (g.), 1074.
 Κύριος, g. -ου, v. -ε, 816, 817 (?), 822, 826, 827, 838, 841, 842, 877, 892, 895, 901, 905, 907, 910, 911, 915, 916, 919, 920, 923, 926-929, 933, 937, 942, 943, 947, 950, 951, 953, 960, 969, 977, 983, 998, 1002, 1016, 1028, 1035, 1037-1039, 1047, 1078, 1090, 1099, 1109, 1110, 1120, 1123, 1136, 1148, 1158, 1160, 1163, 1173, 1177, 1179, 1180, 1184, 1202, 1210. See also Index of Phrases.
 Κυρις, 1095, 1096.
 Κῦρος, 1076, 1159 (?).
 Κυριάνου (g.), 1172.
 Κώ(μης) Ολβανον (g.), 871.
 Λάζαρον (a.), 885.
 Λαυρέντις, 1014.
 Λεοντία, 1017 (?), 1020.
 Λέοντι (d.), 1170.
 Λέωνο(ς) (g.), 1019.
 Λεωνίδου (g.), 1190.
 Λιβανίου (g.), 1003, 1004.
 Λόγος, 1018, 1029.
 Λονγίνου (g.), 1058, 1175.
 Λο[υκ]ια[έ] (v.), 807.
 Λώου (g.), d. -ψ, 811, 818, 863, 894, 909, 1029, 1076, 1077, 1078, 1084, 1096, 1116, 1129, 1148, 1177, 1191, 1199, 1202, 1211.
 Μαίου (g.), d. -ψ, 826, 915.
 Μαλχιόνος (g.), 1179.
 Μάλχος, g. -χου, 904, 1041.
 Μανος, 966.
 Μαξιμείας (g.), 1072.
 Μαρκ (g.), 1119.
 Μαρέα (g.), 920, 922.
 Μαρία, g. -ας, v. -α, 860, 880, 911, 953, 1024, 1062, 1149, 1151, 1194 (?), 1212.
 Μαριάδην (a.), 1201.
 Μαριάμη (?), 1194.
 Μαριανῶ (d.), 1201.
 Μαριμης (?), 1154.
 Μάρις, 1146, 1199.
 Μαρίονος (g.), d. -νι, 1070, 1120, 1124, 1154 (?).
 Μαρκελλας, 1072.
 Μαρκελλίνου (g.), 996.
 Μαρκία (d.), 1152.
 Μαρκικνός, d. -νῶ, 1095 (?), 1096, 1174.
 Μάρκος, 1175.
 Μαρτίου (g.), 1126.
 Μαρτυριν, 1210.
 Μαρωνίου (g.), 815.
 Μαρωνος (?) (g.), 1154.
 Μάρως, 875.
 Ματτανάου (g.), 1072.
 Μεκ[—], 1144.
 Μερκούριον (a.), 1053.
 Μιχαήλ, 929, 1058.
 Μονογενής, 1188.
 Μοσέου (g.), 1099.
 Μουριμηνου (?), 1156.
 Μουσῆ (d.), 1076.
 Μο[—]εο[—], 1003.
 Μυαλος (?), 1115.
 Ναζωρεῖω, 1151.
 Νεϊκανδρος, g. -δρου, 1111.
 Νέρονα (g.), 1111.
 Νικάνωρ, 1133.
 Νεμεβρίω (d.), 908, 915.

- Νομερίου (g.), 1170.
 Νόνος, g. -νου, 1119, 1121, 1122, 1142.
 Ξανδικού see Ξανθικού.
 Ξανθικού (g.), 815, 864, 902, 981, 1068, 1070, 1079, 1094, 1103-1105, 1147, 1201.
 Ολβανον (g.), 871.
 Ουαλέριος, 1107.
 Ούρβικος, 1175.
 Παλλάδ(ος), 1161.
 Παλτω (d.), 1067.
 Πανέμου (g.), d. -μω, 836, 976, 1057, 1058, 1071, 1074, 1075, 1081, 1092, 1093, 1095, 1106, 1107, 1125, 1134, 1139, 1141, 1142, 1146, 1154, 1171, 1189, 1210.
 Πανήμου see Πανέμου.
 Πανωνίας Ἀνωτέρας (g.), 1107.
 Παντοκράτωρ, 1028.
 Παρθικού (g.), 1111.
 Πατρός (g.), d. -τρί, 949, 984, 994, 1029, 1031, 1140, 1146, 1173.
 Πατρικίου (g.), 1054.
 Παύλος, g. -λου, d. -λω, 936, 969, 979, 992, 993, 1025, 1032, 1076.
 Πκυλοσσου (?), 936.
 Πκυσι (g.), 1168.
 Πελαγίου (g.), 1176.
 Περιτίου (g.), 822, 884, 1067, 1069, 1109, 1170.
 Πέτρος, 1017, 1032, 1118, 1143.
 Πρώκλου (?) (g.), 1034.
 Πτολεμαίου (g.), 1152.
 Ρακίος, 1132.
 Ρ[αβ]ουλα (g.), 1190.
 Ραμλυσ (g.?), 1088.
 Ρεαδειος (?), 1128.
 Ρεζιθα (g.), 1175.
 Ρομούλλος, 1107.
 Ρουφινιανός, 1126.
 Ρουφίνος, 1153.
 Ρόχιος, 1121.
 Ρωμανού (g.), d. -νω, 1037, 1049, 1177.
 Ρώμης (g.), 855.
 Σακκωναν (a.), 1201.
 Σαβατίου (g.), 1105.
 Σαβαώθ, see Index of Phrases.
 Σαλαμάνης, 819, 904.
 Σαλεμου (g.), 1005.
 Σαλιρο (i), 938.
 Σαμουήλ, 1091.
 Σαμουήλου (g.), 909.
 Σεκνονος (?), 1129.
 Σεβαστής (g.), 1127.
 Σεβαστού (g.), 1111.
 Σειμίφ (d.), 1170, 1193.
 Σειμω see Σειμίφ.
 Σέλευκος, g. -κου, 1106, 1170, 1171.
 Σέου (g.), 936.
 Σεραπ[], 1060.
 Σέργιος, v. -γι, 1100, 1213.
 Σέργιος, g. -ου, d. -ω, 811, 823, 834, 1086, 1088, 1158, 1177, 1180, 1202, 1211, 1212.
 Σεργωνα (?) (g.), 1177.
 Σε[], 832.
 Σιλβανού see Σιλουανού.
 Σιλουανού (g.), 813, 971.
 Σιμέω (g.), 1167.
 Σίμων, 1014.
 Σολομωνίδα (g.), 1100.
 Στεφάνου (g.), 924, 988.
 Συβαβας, 1092.
 Συμβατιύλω (d.), 1170, 1193.
 Συμβετύλω, see Συμβατιύλω.
 Συμένων, see Συμεώνης.
 Συμεώνης, g. -νου, 815, 871, 963, 1117, 1120, 1148, 1154, 1156, 1159, 1167 (?), 1177. See also Συμόνης.
 Συμόνης, 1080.
 Συνκλητικ(ής) (?) (g.), 922.
 Σώπατρος, g. -τρου, v. -τρε, 809, 1170, 1175.
 Σωπάννας (g.), 1028.
 Σωτήρ, 915, 987a, 992, 1150. See also ΙΧΘΥΣ.
 Σωφίας (g.), 925.
 Τ., 1127.
 Τίλοκβαριν(ός) (?), 1161.
 Τουμιας (?), 1154.
 Τραϊανοῦ (g.), 1111.
 Τριάς, g. -δος, 930, 1017, 1087.
 Τίος, g. -ού, d. -ω, 949, 984, 994, 1029, 1031, 1140, 1146, 1150, 1151, 1173. See also ΙΧΘΥΣ and Index of Phrases.
 Τπερβερεταίου (g.), d. -ω, 850, 1036, 1099, 1102, 1119, 1135, 1140, 1152, 1155, 1176, 1192.
 Τψίστου (g.), 946.
 Φλ., 1006, 1074, 1075, 1101, 1135.
 Φλάουιος, 1127.
 Φιλέον, 1135.
 Φιλίπου (g.), 1121.
 Φωθλα (g.), 982.
 Χεριλλος, 1094.

Χριστός, g. -στοῦ, d. -στῶ, a. στόν, v. στέ, 814, 842, 911, 918, 930, 953, 960, 970, 977, 987a, 996, 1002, 1017, 1022, 1029, 1076, 1077, 1080-1086, 1095, 1096, 1098, 1099, 1108, 1122, 1126, 1139, 1142, 1147, 1150, 1154, 1156, 1160, 1162, 1186, 1189, 1191, 1192, 1196, 1199, 1201, 1210. See also ΙΧΘΥΣ, ΧΜΓ, and Index of Phrases.

Ὁδρέου (g.), 924.

---]ιος, 1193.

---]κ[---]υρ (a.), 1110.

---]κεων, 1003.

---]ρκε (g.), 1193.

---]στουρ (?), 1111.

INDEX OF GREEK WORDS.

Conjunctions, negatives, prepositions, pronouns, cardinal numerals and the words ἔτος and μὴν are omitted from this list.

Ἀγαθός, 919, 992, 1043, 1175, 1176.

ἀγαπάω, 838.

ἀγάπη, 1023.

ἄγγελος, 832.

ἀγίασμα, 1160.

ἅγιος, 856, 859, 860, 868, 895, 926, 930, 961, 962, 1024, 1033, 1038, 1058, 1062, 1086, 1087, 1100, 1103, 1108, 1109, 1123, 1149 (?), 1157 (?), 1173, 1202, 1212.

ἀγορά (?), 1074.

ἀγοράζω, 1074.

ἀγοραστής (?), 1074.

ἀγιάματα, 1088.

ἄδελΦή, 840, 1019.

ἄδελΦιδός, 840.

ἄδελΦός, 935, 993, 1011, 1019, 1034, 1075.

αἶ, 869.

αἰζών, 1017.

αἰπαρμένος, 860.

ἀθάνατος, 868, 1103.

ἀθέσμιος, 1018.

αἰεί, 1018.

αἰέν, 1018.

αἰνέω, 842.

αἰών, 930, 943, 1039, 1063, 1109.

αἰώνιος, 1043.

ἀκοντιστής, 896.

ἀλήθεια, 838.

ἄληπτος (?), 1018.

ἀλλήλων, 829.

ἄλλος, 915, 1067.

ἄλυπος, see Index of Phrases.

ἀμαρτίον, 917, 920.

ἀμαρτωλός, 838.

ἀμήν, 930, 969, 1039 (?), 1095, 1148, 1180, 1212.

ἄμους, 879.

ἀναβαίνω, 1109.

ἀναγιγνώσκω, 970.

ἀναλαμβάνω, 832.

ἀνανέω, 1088, 1108, 1109, 1119.

ἀνανέωσις, 1004, 1007, 1009, 1013.

ἀνανεωτήρ (?), 909.

ἀνάπαυσις, 997 (?), 1034.

ἀναπαύω, 960.

ἀναΦαίνω, 915.

ἀναΦέρω, 1107, 1177, 1178, 1187.

ἀνδρίζω, 1016.

ἀνεγείρω, 865, 971, 980, 996, 1002, 1022.

ἀνέρχομαι, 906.

ἄνευ, 1043.

ἀνεψιός, 915.

ἀνήρ, 1017.

ἄνθρωπος, 814, 1064.

ἀνίστημι, 860, 956 (?).

ἀνοίγνυμι, 840, 841, 918.

ἀνοικοδομέω (?), 952.

ἀντιλήπτωρ, 928.

ἀοίδιμος, 1018.

ἀπαλλοτριόω, 1127.

ἀπαρτί (?), 1193.

ἀπήμων, 1016.

ἀπόλυμι (?), 1021.

ἀπονία (?), 1072.

ἀπόστολος, 1006, 1008-1013.

ἀποτίθημι, 915.

ἄρετή, 829.

ἄρμα, 1016.

ἄροτήρ, 1023.

ἄροτος, 1019.

ἄρχάγγελος, 860, 913, 920, 921, 1050, 1052, 1058

ἄρχή, 1147.

ἀρχιμανδρίτης, 1000.

ἀρχιτέκτων, 1201.

ἄρχομαι, 915.

ἀστυΦέλικος, 1017.

ἀσυλία, 1062.

ἀσΦαλής, 993.

ἀτρύγετος, 1018.

αὐ, 918.

αὐλή, 838, 842.

- αὐξίτω, 938.
 αὐχέω, 1020.
 ἀφειδῶς, 992.
 ἀφεςις, 920.
 ἀφθιτος, 1018.
 ἀφιερῶ, 1067, 1106, 1111, 1127, 1134 (?), 1170.
 ἀφροντις, 1171.
 ἀχάριστος, 930.

 Βαθυκτέανος, 1016.
 βάρβαρος, 1020.
 βασιλεύς, 993, 1088.
 βασιλία, 1109.
 βάσκανος (?), 822.
 βέλτιστος, 915.
 βοηθῶ, 875, 913, 926, 959, 970, 1024, 1037, 1049, 1052, 1075, 1085, 1086, 1089, 1095, 1096 (?), 1100, 1110, 1120, 1122, 1123, 1136, 1142, 1154, 1158, 1162, 1168, 1186, 1189, 1201, 1208 (?), 1212. See also Index of Phrases.
 βοηθία, 892, 946, 1000.
 βοηθός, 1065, 1074, 1096 (?).
 βόστρυχος, 840.
 βούλευμα, 915, 992.
 βούλομαι, 1020.
 βρύω, 992.

 Γαῖα, 1018, 1023.
 γαμετή, 922.
 γενναῖος (?), 1071.
 γεννάω (?), 1151.
 γένος, 1020.
 γεω[μέρος], 918.
 γῆ, 859 (?), 1062-1064.
 γίγνομαι, 885, 993, 1049, 1074, 1098, 1117, 1140, 1154.
 γνω[φεύς], 956.
 γνήσιος, 1020.
 γουεύς, 1028.
 γράφω, 1019, 1170, 1171, 1177, 1203, 1204, 1205.
 γυνή, 1127, 1129, 1133, 1152, 1193.

 Δαίμων, 1017, 1127.
 δέκατος, 1080, 1082.
 δέμα, 1018.
 δεξιός, 919, 1152.
 δέσποινα, 885, 898.
 δεσπότης, 1029, 1117.
 διάκονος, 986, 992, 1003, 1096, 1105, 1119, 1121, 1143, 1158.
 διακνέω, 1019.
 διακτνέω, 1016.
 διαφυγή (?), 924.
 διαφυλάττω, 822.

 δίδωμι, 918, 1067.
 διηνεκές, 1127.
 δίκαιος, 826, 841, 907, 911, 915, 916, 920, 921, 927, 929, 947, 1035 (?).
 δικαιοσύνη, 841, 1023.
 διπλοῦς, 970, 1073, 1206, 1207.
 διώκω, 1016, 1018.
 δόμος, 1016, 1017.
 δόξα, 859, 895, 908, 947, 984, 1031, 1064, 1066, 1140, 1146, 1173.
 δοῦλος, 969, 977, 1037, 1053, 1072, 1110 (?), 1136, 1168 (?), 1202.
 δρόσος, 840.
 δύναμις, 861, 919 (?).
 δυνάμεις, 919, 928, 1109.
 δωρέομαι, 918.

 Ἐάν, 1027, 1067.
 ἐβοκατος, 1170.
 ἐγγονος, 1127.
 εἶδον, 839.
 εἰκοστός (?), 1213.
 εἰκάν, 1017.
 εἰμί, 839, 927, 1016, 1018, 1024 (?), 1043, 1107, 1108, 1127, 1151, 1192 (?), 1199.
 εἰναετήρ (?), 1021.
 εἰναέτηρος (?), 1021.
 εἶρηκα, 923.
 εἰρήνη, 911, 1016, 1064.
 εἶς, 838. See also Index of Phrases.
 εἴσειμι, 1029, 1152.
 εἰσέρχομαι 826, 841, 842, 907, 911, 915, 916, 918, 920, 921, 927, 929, 947.
 εἴσοδος, 816, 822, 910, 930, 933, 943, 1033, 1038, 1051, 1063, 1109, 1148, 1173.
 ἐκατοντάρχης, 1058.
 ἐκκλησία, 1003.
 ἐκλέγω, 838.
 ἐκπονέω, 992.
 ἐλαιοτρόπιον, 1170.
 ἐλέω, 868, 998, 1028, 1163, 1205 (?).
 ἔλεος, 838.
 ἐλπίζω, 1016.
 ἐμφαίνω, 831.
 ἐνδοξάτατος, 885, 1114.
 ἐνδύω, 1108.
 ἐνθα, 1151.
 ἐνθάδε, 829, 958, 1029.
 ἐξακοσιοστός (?), 1213.
 ἐξαπατάω, 1012.
 ἐξεργάζομαι (?), 877.
 ἔξεστι, 1127.
 ἔξοδος, 816, 822, 910, 930, 933, 943, 1038, 1051, 1063, 1109, 1148, 1173.

ἐξομολογέσμαι, 841, 842.
 ἐξομολόγησις, 842.
 ἐπάγω, 1175, 1178 (?).
 ἑπαλξίς, 993.
 [ἐπάν]ω (?), 956.
 ἑπαρχος, 1114.
 ἐπιγράφω (?), 1205.
 ἐπίδοσις, 915.
 ἐπίθυρον, 1177.
 ἐπιμελέσμαι, 1111.
 ἐπιμελητής, 1170, 1190 (?).
 ἐπιμελία, 1142, 1168.
 ἐπίσκοπος, 1003, 1115 (?), 1187, 1199.
 ἐπί]στύλ[ιον (?), 956.
 ἐπιτυγχάνω, 917.
 ἐπείκα for πεποίηκα (?), 1133.
 ἐπουράνιος, 1017.
 ἔργον, 815, 871, 888, 988, 1056, 1089, 1161.
 ἔρδω, 1156.
 ἔρῳ (?), 1185.
 ἐρωτάω (?), 1134.
 εὐγνωμονέω, 915.
 εὐδοκία, 1064.
 εὐδοξία (?), 869.
 εὐεργεσία (?), 1121.
 εὐθύς (?), 1199.
 εὐκτήριον (?), 1050.
 εὐλαβέομαι, 1020.
 εὐλαβεῖσθαι, 1099.
 εὐλογέω, 927, 930, 1038, 1039, 1109, 1148.
 εὐλογητός, 1088.
 [εὐλογία (?)], 1035.
 εὐμενής, 814, 1020.
 εὐσεβεῖσθαι, 885, 1088.
 εὐσεβῶς, 1043.
 εὐσθενέω (?), 1208.
 εὐτυχέω, 1020.
 εὐτυχής, 814, 924.
 εὐφραίνω, 923.
 εὐχαριστέω, 917.
 εὐχή, 855, 867, 922, 925, 1006, 1008-1013, 1042, 1076, 1173.
 εὐχόμαι, 868 (?), 917, 960-962, 1041.
 εὐψυχία, 958.
 ἐφετός, 960.
 ἐχθρός, 892.
 ἔχω, 1019.
 Ζάω, 1043.
 ζωή, see ζωή.
 ζυγόν (?), 1023.
 ζωή, 893, 912, 996, 1007, 1013, 1164, 1171, 1191, 1199, 1200, 1208 (?).
 *Ηγέομαι, 1019.

ήμέρα, 838, 890, 915, 1028.
 ήρ (?), 877.
 ήρωε, 829, 1106.
 Θαλάσση, 1018.
 θάπτω (?), 1192.
 θαυμάσιος, 915.
 θέλησις, 1118.
 θέμεθλα, 1021.
 θεμέλια, 915, 1017, 1176.
 θεός, 1106, 1127, 1134, 1137, 1170, 1193.
 θεμελίω, 930.
 θεοσεβέστατος, 898.
 θεοτόκος, 860, 1212.
 θεοφιλέστατος, 813, 1056.
 θεραπεύω, 915.
 θύρα, 840.
 *Ιασις, 918.
 ἴδιος, 961, 962, 964, 1105, 1152, 1182, 1193.
 ἰδιώτης (?), 878.
 ἱερός, 1043.
 ἱερώτατος, 1067.
 ἰκτήριον (?), 1050.
 ἵππος, 1016.
 ἵστημι, 1021, 1026, 1075, 1080-1084, 1089.
 ἰσχυρός, 868, 1103.
 ἰσχύω (?), 822.
 Κάθημαι, 831.
 κακώρρεκτος (?), 1018.
 κακός, 1029.
 κακός, 1012.
 καλός, 839, 968, 1121.
 καλύπτω (?), 1072.
 κάματος, 964, 968.
 καρδία, 1016.
 καρποφορέω, 877.
 καρποφορία, 1100.
 κάττρον, 865, 915.
 κατασκευάζω, 1106.
 κατασκευή, 1170.
 καταφύγιον, 921.
 καταχθόνιος, 1106, 1127, 1134.
 κατισχύω (?), 944.
 κατοικέω, 946, 958 (?), 1029, 1151.
 κείμαι, 1152.
 κέλυστις, 1108, 1195 (?).
 κέρδος, 1155.
 κεφαλή, 840, 1035.
 κληρονόμος, 1127.
 κοιμητήριον, 1041.
 κοινόν (?), 1115.
 κοινός, 1067.
 κοινωνέω, 1067.

κόκκινος, 839.
 κολλάπτω (?), 1072.
 κόμης, 1101, 1161 (?).
 κομίζω, 922, 1018.
 κόπος, 1105.
 κόρη, 1016.
 κοσμέω, 1043.
 κόσμος, 1018, 1085.
 κουράτωρ, 885.
 κραταίω, 1016.
 κρείστων, 838.
 κρίσις, 1028.
 κρούω, 840.
 κτίζω, 832, 835 (?), 896, 952, 1003, 1020, 1023,
 1028, 1029, 1050, 1058, 1074, 1085 (?), 1087,
 1098, 1105, 1115 (?), 1118, 1120-1122, 1153,
 1155, 1159, 1167, 1171 (?), 1175, 1176, 1202.
 κτίσμαι, 881, 971, 996, 1036, 1202, 1213.
 κτίστης, 1074, 1171 (?).
 κύκλος, 1016.
 κυριακός, 1072.
 κύριος, 968, 1003, 1006, 1007 (?), 1155, 1159 (?).
 κύρος (?), 1159.
 κομήτης (?), 1161.
 κομάρχη, 881.
 κόμη, 817, 819, 871, 879 (?).

Λαῖνες, 1016.
 λαλιά, 839.
 λαμπρότατος, 1050.
 λάσξ, 1008 (?), 1009, 1016.
 λεγεών, 1127.
 λέγω, 827, 960 (?), 970, 1073, 1206, 1207.
 λέξις (?), 885.
 λέπυρον, 839.
 λευκοργός, 1170.
 λιθοξόος, 871, 888, 988.
 λίθος, 1175.
 λίτομαι, 1017.
 λόγος, 1020.
 λουτρόν, 918.
 λυσίπηκτον, 1017.

Μακάριος, 1019.
 μάκρη, 1106, 1107, 1152.
 μάλλον, 838.
 μάρτυρ, 834, 1009, 1120 (?).
 μαρτύριον, 961, 962.
 μεγαίρω, 1021.
 μεγαλοπρεπείστατος, 1101.
 μεγαλύνω, 1016.
 μέγας (?), 861.
 μεθοδεία (?), 1012.
 μειλίχμος, 1018.

μενοινή, 1018.
 μετοίκιος (?), 1023.
 μέτοχος, 1043.
 μέτριος, 875.
 μήλον, 839.
 μήτηρ, 1019, 1137 (?).
 μιμνήσκω, 877, 1154, 1161, 1170, 1175, 1194 (?),
 1203-1205.
 μνεία, 997.
 μνημεῖον, 891, 952, 1127.
 μνήμη, 918, 1043.
 μονογενής, 1188.
 μόνος, 1017, 1045, 1070, 1166 (?). See also Εἰς
 Θεός κτλ.
 μοῦνος, see *μονος* (1017).
 μυριάς, 1016.
 μῶμος, 839.

Ναιετάω, 829.
 ναιετήρ, 1016.
 νάξ, 1115 (?), 1193.
 νεόκτιστος see *νεώκτιστος*.
 νεῦμα, 1017.
 νεώκτιστος, 1147, 1177.
 νικάω, 869, 886, 892, 1160, 1181.
 νίκη, 829, 1006.
 νομογράφος, 1068.
 νόμος, 915, 1020.
 νῦν, 930, 943, 1063, 1066.
 νύξ, 840.

Ξενίζω, 832.
 ξόανον, 1193.

Ὁδηγέω, 831.
 ὀδός, 1199.
 οἰκέω, 838, 970, 1175.
 οἰκησις, 1043.
 οἰκοδομέω, 1000, 1160 a.
 οἰκοδόμος, 1159, 1190 (?), 1213 (?).
 οἶκος, 822, 838, 894 (?), 923, 943, 977, 1019, 1024,
 1142 (?), 1160, 1166 (?), 1185, 1186.
 ὄλβος, 1017.
 ὄλος, 839.
 ὄμμα, 1018.
 ὄμνυμι, 829.
 ὄνυμα, 842, 860, 918, 949, 992-994, 996, 1002,
 1016, 1022, 1029, 1087, 1099, 1109, 1156. See
 also Index of Phrases.
 ὄπαδός, 1019.
 ὀπάζω, 1018.
 ὄπου, 814.
 ὄραω, 1018.
 ὄρος, 1062, 1195.

ὄρφανός, 1011.
 ὄσιος, 1142.
 οὐετρανός, 1107, 1127.
 οὐρανίος, 1017.
 οὐρανός, 859, 895.
 ὀφθαλμός, 822 (?), 839, 1016.

Παῖς, 1019.
 παν|αγία (?), 1024.
 πανθ(οχεῖον), 1154, 1155.
 πάντοτε, 1066.
 παρὰδειςος, 1043.
 παρὰμονάριος, 1114.
 παρὰρρίπτω, 838.
 παρέχω, 1020.
 πας, 813, 814, 859, 908, 918, 947, 1013, 1016, 1020,
 1109, 1152, 1162, 1170, 1189, 1200.
 πατήρ, 1019, 1020, 1034, 1133.
 πατριάρχης, 1088.
 πατρίς, 915, 992.
 πατρίως, 1170, 1193.
 πέμπτος, 882, 1081.
 πεντακοσιοστός, 1082.
 περιθωρακίζω, 1108.
 περιόδευτής, 1118, 1199.
 περιστέρα, 839, 840.
 περιτειχίζω, 930.
 πετρών, 1019.
 πήγνυμι, 1018.
 πηρός (?), 1062.
 πίμπλημι, 840.
 πιστός, 993.
 πλάζω, 1011.
 πλήρης, 859, 895.
 πληρώ, 1148.
 πλησίον, 839, 840.
 πλείων, 915.
 πλούτος, 915.
 ποιέω, 867, 872, 907, 919, 993, 1025, 1041, 1072,
 1093, 1095, 1096, 1098, 1107, 1126, 1129, 1133,
 1152, 1154, 1165 (?), 1182.
 ποιμαίνω (?), 831.
 πόλις (?), 915.
 πολον (?), 860.
 πολύς, 968.
 πόνος, 993, 1115 (?).
 που[τιφίκιον] (?), 1036.
 πορεύω, 923.
 πόρρω, 1017.
 πόντις, 829.
 πράγμα, 993, 1007.
 πραγματευτής, 881.
 πράττω, 873.
 πρέπω, 1160.

πρεσβύτερος, 813, 815, 834 (?), 883, 955, 963, 988,
 1003, 1005, 1010, 1022, 1026, 1056, 1076, 1088,
 1095, 1099, 1119, 1120, 1126, 1211.
 πρόβατα, 831.
 προῖάλλω, 1017.
 πρόκειμαι, 822, 906, 944.
 προνοία (?), 1056.
 προπύλαια, 1043.
 προσδέχομαι, 1100.
 προσέχω, 831.
 πρόσσος, 1170.
 πρόσσος, 1099.
 προστίθημι (?), 1105.
 προσφέρω, 917, 920.
 πρύθετον, 873.
 προφήτης, 1009.
 πρώτος, 976, 1152, 1202.
 πτέρυξ, 1016.
 πύλη, 823, 826, 841, 842, 907, 911, 915, 916, 920,
 924, 927, 929, 944, 947, 1016, 1048, 1088.
 πυλών, 833, 1075, 1080-1084, 1089.
 πύργος, 839, 860, 992, 1058, 1117.
 πωλέω, 1067.
 πῶμα, 1106.

ῥίζα, 1017.
 ῥέα, 839.
 ῥύομαι, 1016.
 ῥώννυμι, 1185.

Σάλαπιγξ, 1109.
 σκεπάζω, 1016.
 σκέπη, 1016.
 σκήνωμα, 838.
 σκερπίζω, 1011.
 σοφία, 1024.
 σοφός, 992.
 σοφάτατος, 1019.
 σπαρτίον, 839.
 σπουδή, 915, 992, 1121 (?).
 σταυρός, 822, 944.
 στέγη (?), 1121.
 στηρίζω, 930.
 στίχος, 1019.
 σταά, 1026, 1148.
 στυγερός, 1018, 1023.
 συγκλητικός (?), 1075.
 συλλαμβάνω, 915.
 σύμβιος, 1075, 1107, 1183 (?).
 συναγωγή (?), 1009.
 σύναξις (?), 1161.
 συνάπτω, 1020.
 συναχτός (?), 1161.
 συνεπιτίθημι, 1016.

συντελέω, 1069, 1170.

σώζω, 1016.

σώτειρα, 1019.

σωτήρ, 842 (?), 915, 942, 950, 1120 (?).

σωτηρία, 855, 922, 993, 1034.

σωτήριος, 992.

Ταμι(εῖ)ον, 1067.

ταπεινός, 1117.

τάττω, 1111.

τέκνον, 855, 925, 985, 1008 (?), 1016, 1175, 1201, 1210.

τέκτων, 1170, 1212, 1213 (?). See also τηκτόνης.

τελέθω, 1017.

τέλειος, 840.

τελείω, 1077, 1099, 1172, 1201.

τελευτάω (?), 862.

τελέω, 815 (?), 862 (?), 881, 958, 960 (?), 961, 962, 965, 1026, 1036, 1070, 1151, 1156.

τέμνω, 1023.

τέσσαρες, 829.

τέταρτος, 1081.

τεχνίτης, 1076, 1080, 1089, 1094, 1096, 1120, 1141, 1146, 1161, 1176, 1177.

τηκτόνης, 1143.

τιμιώτατος, 1020.

τόπος, 1043.

τοῦνεκεν, 1017.

τουτί, 993.

τράχηλος, 839.

τρίτος, 1148, 1152.

τρομέω, 1017, 1023.

τρόπος, 1127.

τύχη, 1175, 1176.

Ἔγλις, 918, 996, 1155, 1191, 1200.

ὕγιαίνω, 1185.

ὕϊς, 867, 914, 980, 993, 1025, 1074, 1094, 1121, 1124, 1152, 1160a, 1175, 1180.

ὕμνος, 842.

ὕπερασπιστής, 1016.

ὕπερθυρον, 906, 915, 1178, 1187.

ὕπηρέτης, 993.

ὕποζύγιον (?), 1023.

ὕποκειμαι, 958.

ὕποτίθηναι, 1067.

ὕψιστος, 1064.

ὕψω, 919.

Φαιδρύων, 915.

Φημί, 919, 923.

Φῆμις, 879.

Φθόνος, 1018.

Φιλέω (?), 1210.

Φιλόκτιστος, 1024.

Φιλοκτίστης, 968.

Φίλος, 992.

Φιλοτιμία, 915.

Φοβέομαι, 942, 950, 1016, 1108.

Φροντίζω, 915.

Φρούραρχος (?), 834, 850 (?).

Φρουρέω, 992, 1019.

Φρούριον, 993.

Φυλάττω, 816, 822, 910, 943, 1016, 1033, 1051, 1063, 1173. See also Index of Phrases.

Φύω, 993.

Φωνή, 840, 1109.

Φῶς, 893, 912, 1018, 1024.

Φωτισμός, 942, 950.

Χαίρω, 807, 809, 1128, 1131, 1132, 1185 (?).

χαρά, 1164.

χαρίς, 918, 932, 1018, 1020, 1050.

χεῖλος, 839.

χεῖρ, 1018.

χερουβεῖμ, 830, 831.

χῆρα, 1011.

χιλιάς, 838.

χρήμα, 1020.

χρηστός, 842.

χρόνος, 1003, 1176.

χρυσίον, 992.

χρυσοῦς, 1193.

χωρεπίσκοπος, 811, 812.

χωρίον, 993, 1017.

Ψαλῖς, 1152.

ψευδής, 840.

ψυχή, 1028.

ᾠδὴ, 960.

ᾠραῖος, 839.

ᾠς, 839, 991.

ᾠσεῖ, 831.

INDEX OF LATIN NAMES AND WORDS.

Abalieno, 1127.
Aug(ustae) (g.), 1127.

Curator, see *κουράτωρ*.

Dedico, 1127.
diis, 1127.

Evocatus, see *ἐβοκῆτος*.

Fl(aviae) (d.) 1127.
Flavius, 1127.

Heres, 1127.

Inferi, 1127.
Iulianus, 1127.

Legio, 1127. See also *λεγεών*.
licet, 1127.

Manes, 1127.
modus, 1127.
monumentum, 1127.

Posteri, 1127.

Sempiternum, 1127.

T(itus), 1127.
Titiae (d.), 1127.

Uxor, 1127.

Veteranus, 1127. See also *οὐστρανός*.

INDEX OF PHRASES AND FORMULAE.

Ἀγαθὴ τύχη, 1175, 1176.
ἀγία Μαρία βοήθι, 1212.
ἅγιος, ἄ., ᾱ., K. Σαββάθ, κτλ., 856, 859, 895.
ἅγιος ὁ Θεός, κτλ., 868, 1103.
ἄλυπε χάρις, 807, 809, 1128, 1131, 1132.
ἀπὸ τοῦ νῦν κτλ., 930, 943, 1063.
αὕτη ἡ πύλη τοῦ Κυρίου, κτλ., 826, 841, 907, 911,
915, 916, 920, 927, 929, 947.

Βοήθησον, or βοήθησον τῷ δεῖνι, see βοήθι κτλ.
βοήθι κτλ., 891, 901, 933, 934, 937, 951, 969, 977,
1053, 1070, 1078, 1110, 1122, 1136, 1142, 1154,
1158, 1162, 1166, 1177, 1179, 1180, 1191, 1201,
1202, 1208 (?), 1210.
ὁ βοηθῶν κτλ., 875, 968, 1049, 1075, 1089, 1095,
1168, 1186, 1189, 1195, 1200, 1201, 1204, 1205.

Διὰ εὐχῆς, 1173.
δόξα ἐν ὑψίστοις Θεῷ, κτλ., 1064.
δόξα Πατρὶ κτλ., 984, 1031, 1140, 1146, 1173.

Εἰ ὁ Θεός ὑπὲρ ἡμῶν, κτλ., 905, 1027, 1030, 1066;
cf. 926, 928, 1044.
εἰς βοήθειαν, 1000.
εἰς Θεός, κτλ., 875, 959, 968, 971, 1045, 1070,
1075, 1089, 1090, 1166, 1168, 1169, 1198, 1200,
1204, 1205, 1206.
εἰς Θεός καὶ ὁ Χριστός, κτλ., 1049, 1074, 1076, 1077,
1080-1086, 1095, 1098, 1126, 1139 (?), 1186,
1189, 1192, 1196, 1199, 1201, 1210.

εἰς τοὺς αἰῶνας αἰώνων, 1109.
ἐκ τῶν ἰδίων, ἐξ ἰδίων, etc., 961, 962 (?), 1105, 1182,
1193.
Ἐμμανουὴλ μεθ' ἡμῶν, 1065. See also 866, 937.
Ἐν νόματι κτλ., 860, 949, 992, 994, 996, 1002,
1016, 1022, 1029, 1087, 1099, 1109, 1156.
ἐν τούτῳ νικῶ, 892.

Ζωή, ὑγία, 996, 1191, 1200. See also 893.
ζωή, Φῶς, 893, 912, 915.
ζωή, χαρά, 1164.

θεοῖς καταχθονίοις, 1106, 1127, 1134 (?).
θεοῖς πατράσις, 1170, 1193.
Θεός μεθ' ἡμῶν, 1044. See also εἰ ὁ Θεός κτλ.,
and Πνεῦμα τὸ Ἅγιον κτλ.
Θεοῦ χάρις, 932, 1050.

Καὶ σοί, 1125, 1163a, 1206. See also ὅσα λέγεις κτλ.
καὶ σύ, 1127, 1197.
ὁ κατοικῶν ἐν βοήθειᾳ κτλ., 946.
Κύριε κτλ. βοήθησον or βοήθι, see βοήθι κτλ.
Κύριε ἐλέησον, 998, 1163 (?).
Κύριε εὐλόγησον κτλ., see Κύριος εὐλογῇσει.
Κύριε ὁ Θεός, 1016, 1110, 1184 (?), 1210.
Κύριε Φύλαξον, see Κύριος Φυλάξει.
Κύριε Χριστέ, 910.
Κύριος μεθ' ἡμῶν, 926, 938. See also εἰ ὁ Θεός κτλ.
Κύριος Σαββάθ, 856, 859, 861 (?), 895.
Κύριος τῶν Δυνάμεων, 928, 1109.

Κύριος εὐλογήσει τὴν εἴσοδον κτλ., 1038, 1039, 1109, 1148.

Κύριος Φυλάξει τὴν εἴσοδον κτλ., 816, 822, 910, (933), 943, 1051, 1063, 1173.

Κύριος Φωτισμός μου κτλ., 942, 950.

Μετὰ τῶν ἰδίων, 962.

μνήμης χάριν, 1043.

μνησθῇ ὁ δεῖνα, 1154, 1170, 1175, 1194 (?), 1203, 1204, 1205.

Ὅσα λέγεις, Φίλε, κτλ., 970, 1073, 1206, 1207.

See also καὶ σοί.

ὅτι Φιλοῦσίν σε (?), 1210.

Πάντα εἰς δόξαν Θεοῦ, 908, 947.

πάντα ἐκ Θεοῦ, 813.

Πνεῦμα τὸ Ἅγιον μετ' ἐμοῦ ἐστίν, 1108.

Σπουδῇ καλῇ καὶ εὐεργεσίᾳ (?), 1122.

σὺν Θεῷ, 865, 915, 952 (?), 980, 1074, 1178.

σὺν τέκνοις, 1175.

Τὰ σὰ ἐκ τῶν σῶν κτλ., 920.

τοῦτο νικᾷ, 886, 1181.

ὑπὲρ ἀνανεώσεως, 1004.

ὑπὲρ εὐχῆς, 855, 867, 922, 625; cf. 1173.

ὑπὲρ εὐχῆς καὶ σωτηρίας, 855, 922.

ὑπὲρ μνείας, 997.

ὑπὲρ σωτηρίας, 1034.

Φῶς, Ζωή, see Ζωή, Φῶς.

Χριστέ, βοήθι, see βοήθι κτλ.

Χριστέ, Σωτήρ (?), 842.

Χριστὸς νικᾷ, 1160.

INDEX OF ABBREVIATIONS AND SYMBOLS.

The common abbreviations for Κύριος, Ἰησοῦς and Χριστός, and for ἔτους, ἰνδικτιῶνος and μηνός are omitted.

Αἰ (= αἰῶνας?), 1109.

ΑΚΟΗ, 969.

ἀκόντις, 896.

ἀμαρ, 920.

Ἄρ, 810.

ἄρχ, 994.

Αὐ, 883.

Αὐρ, 1093.

αὐτ, 1189.

ΑΩ, 844, 953, 1035.

Β (= βοήθι), 969.

βασιλ, 1088.

βο (= βοήθι), 937.

βο (= βοηθῶν), 1049.

Γορπ, 1178.

Γρ, 1167.

Δ (= δούλω), 969.

Δε, 930.

Δεσ, 1114.

δεσπ, 1117.

δι, 970.

διακ, 986, 992, 1119, 1121.

δικφ (?), 924.

δου (?), 1123.

δουλ, 1174.

Ἐγεν, 1154.

εἴσοδ, 1033.

ἐκτ, 1155.

ἐν (= ἐργον?), 988.

ἐνδοξ, 1114.

ἐπαρχ, 1114.

ἐργ, 888.

ἐτελ, 1151.

ἐτο, 981, 1088.

Ευ, 948.

εὐλαβ, 1099.

εὐλογ, 1088.

εὐσεβ, 1088.

εὐσεβ (= εὐσεβῶς), 885.

εὐτυχ, 924.

ΗΓΩ, 1090.

ημ (= ἡμῶν), 1117.

ημν, 1088.

Θ, 1047, 1206.

Θε, 913, 1121.

Θεμελιν, 915.

Θε, 817, 920, 1016, 1028, 1030, 1049.

Θυ, 878, 908, 915, 947, 992, 996, 1016, 1028,

1029, 1050, 1118, 1151.

ΘΧΜΓΚ, 1047.

Θω, 865, 915, 917, 930, 1064, 1178.

ΘΩΜΑ, 915.

Τ, 848, 1139, 1146, 1155, 1190.

ΙΧΘΥΣ, 969, 971, 972, 999, 1070, 1120, 1147, 1150, 1188, 1206.

Κ (= καί), 829, 860, 910, 915, 933, 985, 994, 1016, 1051.

καρποφορ, 1100.

καστρ, 915.

κατ, 958.

καταχθ, 1134 (?).

κτι, 1213.

κω, 819.

κωμάρχ, 881.

Λ, 1191.

Λιθεξ, 988.

Μ, 1095.

μ, 834.

μαρ, 1120.

Μαρτ, 1126.

μεγαλοπρε, 1101.

ΜΚ, 953.

μν, 891.

μονογ, 1188.

Νι, 1160.

Νοεμβρ, 908, 915.

Ξ, 981.

Ξανθικ, 864, 902.

Οίκωδ, 1160a.

Πα, 1075, 1088.

Παλλαδ, 1161.

Παν, 1058, 1125.

πανδ, 1154, 1155.

Πανευμ, 1141, 1189, 1074.

παρριμοναρ, 1114.

Παυ, 969.

Περ, 884.

Πν, 949, 996.

Πνκ, 1077.

Πνι, 930.

Πνυ, 1140, 1146.

πρ, 883, 1022, 1026, 1088, 1120 (?).

πραγμα, 881.

πρβ, 813, 1010.

πρε, 988, 1003, 1005.

πρεσβ, 815, 1056, 1076, 1119, 1120.

πρεσβε, 955.

πρσ, 1099, 1211.

πτρ, 1140.

πυλ, 1075.

ϑθ, 969.

Σερ, 811, 823.

σινγ, 1075.

στρ, 1120.

συνκ, see σινγ.

συνκλητικ, 922.

Τ (= τους), 832.

τ (= τῶ), 969.

τ (= τοῦ), 887, 1087, 1088.

τεχ, 1141.

τεχνι, 1120.

τεχνιτ, 1146.

τχ, 1096.

Υπερβ, 850, 1099, 1119, 1155.

υπερθυρ, 915, 1178.

υτ, 867, 1151.

Φ, 1210.

Φλ, 1074, 1075, 1101, 1135.

Φλα, 1006.

Φρ, 834, 850.

Χ/ΑΩΜΚ, 953.

ΧΜ, 845 (?), 970.

ΧΜΓ, 845 (?), 846, 853, 864, 910, 913, 924, 941, 945, 969, 970, 973, 981, 985, 1002, 1047, 1154, 1156, 1202.

χρ, 812.

χρρ, 811.

χω, see χρ.

χωρ, see χρρ.

ΩΛ, 1121.

✱, 1067.

/ (mark of abbreviation), 810, 811, 813, 814, 826, 829, 830, 837, 843, 846, 864, 890, 894, 899, 902, 906, 908, 913, 915, 947, 1016, 1029, 1046, 1050, 1056, 1059, 1084, 1086, 1087, 1088, 1104, 1105, 1114, 1120, 1146, 1151, 1154, 1155, 1156, 1167, 1176, 1178.

/ (= καί), 860, 867, 871, 922, 924, 936, 967, 1028, 1029, 1034, 1043, 1049, 1086, 1088, 1120, 1155, 1177, 1192.

/ (Punctuation mark), 817, 869, 915, 922, 988, 1029, 1046, 1077, 1088, 1155, 1192.

GRAMMATICAL AND ORTHOGRAPHICAL INDEX.

- Accusative for dative: 875, 970, 1053, 1089, 1095, 1110, 1136, 1201, 1202, 1204, 1210 (?).
 Accusative for genitive 885.
 Dative for genitive: 1177.
 Genitive for dative: 1074, 1085, 1107, 1136, 1158, 1173, 1179, 1180, 1186.
 Letter added to fill space: 1094.
 Ordinal numerals: 822, 976, 1080-1082, 1152, 1202, 1213.
 ἀναγινώσ[κοντα]: 970.
 ἀνένχθι for ἀννηέχθη: 1177.
 ἀννηέσθη: 1088, 1109.
 Ἀγκύριον: 1053.
 ἀντιλήμπ[τωρ] for ἀντιλήπτωρ: 928.
- Βοηθεῖν with genitive: 1085, 1122, 1158, 1179, 1180, 1186.
 βοηθεῖν with accusative: 875 (?), 970, 1053, 1089, 1095, 1110, 1201, 1202, 1204, 1210 (?).
- Γράψοι for γράψαντος: 1177.
- Ἐγ' δεξιῶν: 1152.
 εἰσοδοῦ for εἰσοδόν: 1038.
 ἐλπίζω ἐπί: 1016.
 ἐπειοισεν for ἐποίησεν: 1095.
 ἐπέτυχα for ἐπετύχησα or ἐπιτέτυχα: 917.
 ἐποίηκα for πεποίηκα: 1133.
 ἐπόση (?) for ἐποίησε (?): 1133.
 ἔσταν for ἔστη or ἔστησαν: 1080.
 ἔτος for ἔτους: 899, 1079.
 εὐμενέ, fem. from εὐμενής: 1020.
- Ἡνέφξεν for ἀνέφξεν: 918.
- Θεέ, voc. of θεός: 1037.
- Τ: 848, 1139, 1146, 1155, 1190.
- Κτισθέντα for κτισθέν: 1050.
 Κύριε for Κύριε: 1078.
 κωμέτου for κόμητος (?): 1161.
- Μετά for ὑπό: 1058.
- Ξανδικού: 1068, 1070, 1079, 1094, 1147, 1201.
- Παραδίσσου for παραδείσου: 1043.
 πέμπτου for πέμπτου: 882.
 προσένικα for προσήνεγκα: 917.
- Συνβίβ for συμβίβ: 1107.
- Ἵ(γ)ειένων for ὑγιαίνων: 1185.
 ὑπό with accusative: 885.
 ὑπό with dative, for ἐπί (?): 1088.
- Α for ε: 957.
 α for ο: 875, 1011, 1019.
 α for ω: 878.
 αι for ε: 919, 1176.
- Β for ου: 813.
- Ε for α: 1036.
 ε for αι.¹
 ε for η: 820, 865, 877, 947, 950, 1033 (?), 1057, 1067, 1077, 1079-1082, 1093, 1095, 1100, 1122, 1151, 1154, 1161, 1177, 1187.
 ε for υ: 821.
 ει for ε: 1011.
 ει for η: 826, 1099, 1178.
 ει for ι: 830, 831, 838, 915, 962, 1002, 1103, 1111, 1133, 1185, 1208, 1212.
 εσ- for εἰσ-: 920.
 ευ for αυ: 821, 948.
- Ζ for σ: 1211.
- Η for αι: 947, 1122, 1146, 1173.
 η for ε: 814, 832, 925, 1016, 1071, 1074, 1088, 1093, 1099, 1100, 1109, 1117, 1122, 1143, 1159, 1161, 1162, 1163, 1173, 1196, 1212.
 η for ει: 923, 930, 1053, 1063, 1086, 1158.
 η for ι: 1058, 1150, 1161.
- Θ for τ: 891.
- Ι for αι: 1017.
 ι for ει.¹
 ι for η: 819, 823, 826, 859, 879, 885, 887, 893, 923-925, 927, 930, 1085, 1101, 1123, 1136, 1151, 1177.
 ι for υ: 1135, 1138.
- Νγ for γγ: 860, 1058, 1109, 1175.
 νκ for γκ: 922, 1053.
- Ο for α: 970, 1011, 1213 (?).
 ο for ου: 852, 853, 1117, 1201.

¹ Examples of ε for αι, ι for ει, ο for ω and ω for ο are so common that they are not included in this index.

o for ω.¹
 oi for ι (?): 1213.
 oi for υι: 1173.
 ou for ο: 923.
 ou for ω: 1012.

Συλλ- for συλλ-: 915.

T for η: 1027.

υ for ι: 1049.
 υ for oi: 1041.
 υ for ou: 885.
 υ for υι: 1121.

Ω for α: 1151, 1202.
 ω for ο.¹
 ω for ou: 1114, 1167.

INDEX OF DATES.

All these are of the Christian era.

73-4,		No. 1144.	387,	August,	No. 1191.
116,	November,	No. 1111.	389,	April,	No. 1094.
122 (?),	August,	No. 1129.	390,	August,	No. 1095.
143,	July,	No. 1092.	391,	October,	No. 1135.
152,	October,	No. 1152.	392,	October,	No. 1036.
164,	July,	No. 1106.	393-4 (?),		No. 1061.
193,	July,	No. 1072.	394-5,		No. 958.
199 (?),		No. 1113.	401,	August,	No. 1096.
207-8,		No. 1175.	402 (?),	October,	No. 1102.
224,	February,	No. 1170.	402-3,		No. 968.
227 (?),	February,	No. 1067.	403-4,		No. 1097.
235,	April,	No. 1068.	406-7,		No. 1003.
236,	July,	No. 1125.	406-7,		No. 1196.
240,	July,	No. 1134.	407 (?),	March,	No. 1126.
262-3 (?),		No. 1203.	407,	July,	No. 1189.
272-3 (?),		No. 1203.	407,	July,	No. 1210.
275-6,		No. 809.	407-8,		No. 1098.
295-6 (?),		No. 1073.	408-9,		No. 973.
308,	July,	No. 1171.	408-9,		No. 974.
310,	July,	No. 1107.	411,	January,	No. 1138.
334-5,		No. 1153.	411-12,		No. 975.
339-40 and 350,		No. 1074.	418,	August,	No. 1076.
341-2,		No. 1145.	418 (?),	November,	No. 1049.
344,	May,	No. 881.	418-9,		No. 1026.
349-50,		No. 1206.	419,	January (?),	No. 948.
350,	July,	No. 1074.	420,	July,	No. 976.
352,	July,	No. 1093.	421 (?),	July,	No. 1139.
355,	July,	No. 1075.	423,	October,	No. 1119.
359,	February,	No. 1069.	424,	October,	No. 1140.
359-60 (?),		No. 1091.	427 (?),	July,	No. 1146.
360,	August,	No. 1116.	429-30,		No. 1005.
362,	June,	No. 869.	431,	August,	No. 1077.
363 (?),	April,	No. 1201.	434 (?),	August,	No. 1078.
365,	November,	No. 970.	436,	April,	No. 1079.
368-9,		No. 971.	436-7,		No. 977.
372,	August,	No. 1199.	439,	April,	No. 1147.
373,	November,	No. 896.	441-2 (?),		No. 959.
375-6,		No. 1118.	443-4,		No. 978.

¹ Examples of ε for αι, ι for ει, ο for ω and ω for ο are so common that they are not included in this index.

444,	November,	No. 979.	526-7 (?),	No. 1123.	
445-6,		No. 1172.	528-9,	No. 910.	
452,	September,	No. 1080.	529-30,	No. 897.	
453 (?),	July,	No. 1141.	531-2,	No. 994.	
453-4,		No. 882.	533-4,	No. 913.	
455-6,		No. 980.	534,	March,	No. 870.
456,	July,	No. 1081.	537,	June,	No. 1086.
457,	April,	No. 981.	538,	September,	No. 1121.
462,	May,	No. 1082.	539,	June,	No. 1122.
462-3,		No. 954.	538-9,		No. 995.
465-6,		No. 982.	542,	August,	No. 894.
466-7,		No. 1136.	543,	March,	No. 871.
468-477,	November,	No. 834.	544,	January,	No. 821.
469-70,		No. 849.	545-6,		No. 914.
473,	April,	No. 1103.	546-7,		No. 1016.
474-5,		No. 983.	547,	February,	No. 822.
475-6,		No. 967.	551,	June,	No. 1087.
477-8,		No. 985.	556-7,		No. 898.
479,	July,	No. 1154.	557,	July,	No. 1057.
479,	October,	No. 1155.	558 and 559,	May,	No. 915.
480,	October,	No. 1099.	559,	July,	No. 836.
483-4,		No. 835.	559,	November,	No. 915.
485,	June,	No. 1083.	559-60,		No. 830.
485,	August,	No. 1084.	559-60,		No. 831.
486-7,		No. 986.	561,	April,	No. 864.
487,	April,	No. 1104.	561,	September,	No. 1178.
487,	September,	No. 1167.	561,	November,	No. 906.
489,	July,	No. 1142.	563 (?),	April,	No. 1201.
489,	October,	No. 850.	564,	September,	No. 899.
491,	October,	No. 1176.	564,	November,	No. 908.
492,	October,	No. 1192.	565,	August,	No. 811.
493,	May,	No. 1150.	566-7,		No. 1088.
496,	August,	No. 1177.	569-70,		No. 851.
496-7,		No. 1027.	571-2 (?),		No. 1213.
497,	September,	No. 1108.	572,	June,	No. 1117.
500,	June,	No. 1120.	572-3,		No. 889.
504-5,		No. 987.	574-5,		No. 837.
504-5,		No. 1173.	574-5,		No. 893.
506,	May,	No. 810.	577,	May,	No. 826.
507,	August,	No. 909.	577-8,		No. 947.
509 (?),	August,	No. 819.	577-8,		No. 1046.
509-10,		No. 992.	578-9,		No. 823.
510,	August,	No. 1148.	579,	June,	No. 1114.
510-11,		No. 988.	579-80,		No. 867.
515-6 (?),		No. 1085.	582,	September,	No. 890.
516,	December(?),	No. 1151.	583-4,		No. 919.
516-7,		No. 1151.	584,	January,	No. 883.
517,	February,	No. 1109.	585-6,		No. 845.
517-8,		No. 1028.	586-7 (?),		No. 1213.
522 (?),	April,	No. 1105.	590,	March,	No. 846.
523,	August,	No. 1202.	591-2,		No. 847.
524,	August,	No. 1029.	592-3,		No. 852.
526,	July,	No. 1058.	597,	February,	No. 884.
526-7,		No. 1050.	597-8,		No. 812.

597-8,		No. 858.	—, April,	No. 815.
598,	September,	No. 843.	—, April,	No. 902.
598-9,		No. 838.	—, June,	No. 848, 930.
602,	August,	No. 1211.	—, August,	No. 863.
605,	May,	No. 813.		
609-10,		No. 1100.		

INDICTIONS.

Ind. 1: Nos. 858, 890, 1202.	Ind. 9: No. 864.
Ind. 2: Nos. 815, 843, 1029, 1154.	Ind. 10: Nos. 826, 847 (?), 906, 1016, 1109, 1146, 1168 (?), 1178.
Ind. 3: Nos. 1148, 1155.	Ind. 11: Nos. 913, 947, 1046, 1167.
Ind. 4: Nos. 845 (?), 1177.	Ind. 12: Nos. 833, 1114.
Ind. 5: Nos. 894, 898, 1050, 1056, 1057, 1117, 1211, 1213.	Ind. 13: Nos. 811, 899, 908, 930.
Ind. 6: Nos. 871, 915, 1059 (?), 1108, 1141 (?).	Ind. 14: No. 1087.
Ind. 7: Nos. 836, 946 (?).	Ind. 15: Nos. 884, 909, 1059 (?), 1082, 1086, 1088, 1105, 1176.
Ind. 8: Nos. 813, 830, 831, 837, 846, 915, 1083, 1084, 1140.	

INDEX OF PLACES.

Abū Ḥaniyeh, p. 85 f.	Fa'lûl, p. 108-111.
Abū il-Ḳudûr, p. 34.	Fidreh, p. 160-163.
‘Aibân, p. 108.	
Il-Anderin, p. 43-60.	Il-Ghadfeh, p. 107.
Il-‘Anz, p. 34 f.	
	Il-Habbât, p. 112.
Babışka, p. 128-133.	Ḥalbân, p. 26-30.
Banastûr, p. 200.	Ḥerâkeh, p. 99-102.
Il-Bârah, p. 113 f.	Il-Hômeh, p. 60.
Bâshamrâ, p. 178.	
Başûfân, p. 178.	I’djaiyiz, p. 99.
Batûta, p. 203.	I’djâz, p. 86-99.
Bâziher, p. 202 f.	Idnin, p. 25 f.
Il-Berdôneh, p. 21 f.	
Brâd, p. 188-97.	Ḳal‘at Sim‘ân, p. 176 f.
Burdaqlî, p. 136-143.	Ḳal‘at Kalôta, p. 199 f.
Burdj Ḥêdar, p. 178-80.	Kalôta, p. 198 f.
Burdj il-Ḳâs, p. 197 f.	Ḳaşr Ibn Wardân, p. 38-41.
Burdj is-Sab‘, p. 147.	Ḳatûrâ, p. 153-160.
Il-Burdj, p. 112.	Kefr Rûmâ, p. 113.
	Kfêr, p. 146 f.
Id-Dabbaghîn, p. 37 f.	Kefr Antîn, p. 203 f.
Dâr Ḳitâ, p. 119-128.	Kefr Lâb, p. 178.
Dellôza, p. 115 f.	Kefr Nabô, p. 180-8.
Dêr Nawâ, p. 18.	Kerrâtin, p. 70-85.
Dêr Sim‘ân, p. 169-76.	Kfellusin, p. 135 f.
Dur‘amân, p. 145 f.	Kharâb Shêkh Berekât, p. 152 f.
	Khîrbit il-Khaṭîb, p. 133.
Fâfirtin, p. 202 f.	Khîrbit Têzin, p. 133.

- Kôkabā, p. 114 f.
 Ksedjbeh, p. 128.
 Kunbus, p. 25.
 Kwârō, p. 116-118.

 Ma^crâtā, p. 102 ff.
 Ma^cšarān, p. 107 f.
 Millis, p. 118.
 Mir^câyeh, p. 68-70.
 Il-Mishrifeh, p. 30-32.

 Nawā, p. 14-17.

^cÔdjeh, p. 65-68.

 Refādeh, p. 163-166.
 Ir-Rubbeh, p. 2.
 Ir-Ruḥaiyeh, p. 35-37.

 Sabba^c, p. 8 f.
 Is-Sekê^cah, p. 111.
 Serā^c, p. 61-64.
 Serdjilla, p. 113.

 Shêkh ^cAlī Kāsûn, p. 3-8.
 Shêkh Slēmân, p. 207-10.
 Simkhâr, p. 204-7.
 Sindjâr, p. 64 f.
 Sitt ir-Rûm, p. 166-8.
 Srîr, p. 143 f.
 Sṭabl ^cAntar, p. 60 f.
 Surkanyā, p. 200-2.
 Iṭ-Ṭaiyibeh, p. 22-25.
 Tarrād, p. 2 f.
 Tell ^cAḳibrin, p. 145.
 Tell id-Deheb, p. 20 f.
 Temek, pp. 11-13.
 It-Ṭhedjeh, p. 65.
 Iṭ-Ṭûba, p. 32-34.

 Umm Ḥartên, p. 22.
 Umm it-Tuwêneh, p. 10 f.
 Umm Wilât, p. 68.

 Zabbûdeh, p. 19 f.
 Zerzitā, p. 147-152.



NORTHERN SYRIA


DJEBEL SIM'ÂN. DJEBEL ḤALAKAH

AND PART OF
DJEBEL BĀRÎSHĀ

FROM SURVEY BY
F.A. NORRIS, C.E.

1905

SCALES



- | | | | |
|------|--------------------------|---|-------------------|
| BRÂD | Large Towns or Ruins | □ | Temenos |
| Srîr | Villages and Minor Ruins | ○ | Village |
| aa | Kurdish Encampment | ≡ | Rains |
| — | Roman Road | ⊕ | Village and Ruins |
| — | Road | ⊕ | Mosque or Well |
| --- | Expedition's Route | ⊙ | Expedition's Camp |
- TELANISSVS Ancient Name

C.F. Cook, C.E., Del. December 1905



SCHEME FOR PUBLICATIONS OF PRINCETON ARCHAEOLOGICAL EXPEDITIONS TO SYRIA

DIVISION I. Geography and Itinerary.	DIVISION II. Architecture.	DIVISION III. Greek and Latin Inscriptions.	DIVISION IV. Semitic Inscriptions.
<i>SECTION A.</i> Southern Syria.	<i>SECTION A.</i> Southern Syria. PARTS. 1. * Ammonitis. 2. * Southern Ḥaurān. 3. * Umm idj-Djīmāl. 4. * Bosra. 5. * Djebel Ḥaurān and Ḥaurān Plain. 6. * Sī. 7. * Ledjā.	<i>SECTION A.</i> Southern Syria. PARTS. 1. * Ammonitis. 2. * Southern Ḥaurān. 3. * Umm idj-Djīmāl. 4. * Bosra. 5. * Djebel Ḥaurān and Ḥaurān Plain. 6. * Sī. 7. * Ledja.	<i>SECTION A.</i> * Nabataean Inscriptions.
<i>SECTION B.</i> Northern Syria.	<i>SECTION B.</i> Northern Syria. PARTS. 1. * The 'Alā and Kaṣr Ibn Wardān. 2. * Anderīn-Kerrātīn- Ma'rātā. 3. * Djebel Riḥā. 4. * Djebel Bārishā. 5. * Djebel Ḥalaḳah. 6. * Djebel Sim'an.	<i>SECTION B.</i> Northern Syria. PARTS. 1. * The 'Alā and Kaṣr Ibn Wardān. 2. * Anderīn-Kerrātīn- Ma'rātā. 3. * Djebel Riḥā and Djebel il-Waṣṭānī. 4. * Djebel Bārishā. 5. * Djebel Ḥalaḳah. 6. * Djebel Sim'an.	<i>SECTION B.</i> Syriac Inscriptions. <i>SECTION C.</i> Safaitic Inscriptions. <i>SECTION D.</i> Arabic Inscriptions.

* Published.



CENTRAL ARCHAEOLOGICAL LIBRARY,
NEW DELHI

Issue Record

Catalogue No. 913.394/PO.A.E.S.
~~913.569/P.P.U.A.~~

Author— P. P. U. A. Es

Greek & Latin Ins. in Syria
Title—Sec. B Northern Syria
Pt. 6 Diebel Siman

Borrower No.	Date of Issue	Date of Return

"A book that is shut is but a block"

CENTRAL ARCHAEOLOGICAL LIBRARY
GOVT. OF INDIA
Department of Archaeology
NEW DELHI.

Please help us to keep the book
clean and moving.